

(1) Number of pages 1

(2) Date of repair 28.8.38

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 2473	Press ~~Mis~~
327-28	
Dated 13. 8	1867 .

Not to be folded or roughly handled

(1)

*Proceedings of the Madras Government, Public Works Department,
13th August 1867.*

No. 327. Read the following Proceedings of the Madras Government in the
Military Department:—

Approving of an estimate of Rupees 2,350 for
the construction of line sheds, cisterns, &c., } (Here enter 8th August 1867, No. 2,934.)
for the new horse lines of the B. Troop,
Royal Horse Artillery, at Bellary.

No. 328. ORDER THEREON, 13th August 1867, No. 2,473.

MILITARY WORKS, No. 24.

Communicated to the Superintend-
ing Engineer of the 3rd Division.

(True Extract.)

(Signed) J. H. M. SHAW STEWART, Major, R. E.,
Under Secretary to Government.

To the Superintending Engineer, 3rd Division, with one Specification.
,, Controller of Public Works Accounts.
,, Accountant General.

Exd. S. T. Augustin.

Carried forward

118	2
1314	

ABSTRACT ESTIMATE.

Bellary District.

Work Constructing Line Sheds &c in the New Horse Lines for B Troop Royal Horse Artillery.

Quantities.	Description of Work.	Rate.	Amount.	Amount of each part.
<u>Line Sheds.</u>				
1129 1/2	Cft. Stone in Mud	Cft. 1 4	94 2	
1061 1/2	Sft. Plastering with Chunan	Sft. 2	21 3 8	
1	Door Rough Battens 3x6 1/2	Ct. 10	10	
3	Windows rough frame & Wood bars 3x4	Ct. 7	21	
24	Rft. Granite Slabs	Rft. 1 1/2	9	
40.8	Cft. Tugger wood wrought and put up	Cft. 3 8	142 5 4	
516	Sft. Plastering with Bamboo paper	Sft. 10	51 9 6	
216	Sft. Plastering with Gravel	Sft. 1	2 2 7	
12	Cy. Excavation	Cy. 2 1/2	2 1/4	
	Summes		353 11 1	
	Total for one		17 4 1	
	for three		371	1113
<u>Cisterns</u>				
84	Cft. Foundation stone in Chunan	Cft. 2	10 8	
54	Ct. Walls above Bricks in	Ct. 3	10 2	
138	Sft. Plastering with Chunan	Sft. 3 8	4 13 3	
3 1/2	Cy. Excavation	Cy. 3	9 4	
	Summes		26 1 4	
	Total for one		27 8	
	for three		82	82
<u>Tray Stands</u>				
684	Cft. Building 57 Pillars 2x2x3	Cft. 2	85 8	
	Plastering & relaying 62 long	Ct. 6	33 4	
16 8/9	Cy. Excavation for Pillars	Cy. 3	3 2 8	
	Summes		111 12 9	
	Carried forward		6 9 4	118 8
				1314

PROCEEDINGS OF THE MADRAS GOVERNMENT.

From the Superintending Engineer, 3rd Division, Bellary, 18th July 1867,
No. 1119; to the Secretary to Government, Public Works Department, Madras.

2. The above estimate was prepared on the representation of the Officer Commanding the Artillery, and I beg to quote his remarks "that as the horse lines into which it is necessary that the horses of the Battery under my command should be removed (the men being now located in the new Barracks) were originally built for a Field Battery, and therefore hardly enough to contain half the horses of a Battery of Horse Artillery."

Referred to the Military Department. No funds are available in the Public Works Department.

24th July 1867.

Approved for execution on funds being available.

Alamilton Colonel,

To the Public Works Department, with two plans,
estimate and specification.
,, Quarter Master General.

Exd. A. W. Cooke.

[illegible]

10. 1867. Dept
Pro: of the Madras Govt.
No 3002

Pro: of the Madras Govt.
Mil: Dept.

Dated 8th {
Rec^d 10th { Aug: 1867

Encls: 42 No: 2934.

Approving of an
estimate of Rs: 2350 for
the construction of lime
sheds, cisterns, &c, for the
new horse lines of the
B. Troop, Royal Horse
Artillery, at Bellary.
No. 2173-135. dated 1867

With an order

10. 1867

No 2473

Command to the Judge
Engineer of the 3rd Bn

No 327-328

10. 1867. 3 Bn. with one horse
in Contable

Recd 14/1867

Start 1867
13. ending 1867