

(1) Number of pages 1-10
(2) Date of repair _____
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2716 -	Press
82-83.	Mis.
Dated 4-9 -	18 67

Not to be folded or roughly handled

96

*Proceedings of the Madras Government, Public Works Department,
4th September 1867.*

No. 82. Read the following letter from the Inspector General of Military Works, Government of India, Public Works Department, to the Secretary to the Government of Madras, in the Public Works Department, dated Simla, 13th August 1867, No. 869 M:—

1. I am directed to acknowledge receipt of your letter No. 2,039, dated 8th July 1867, and in reply to state that the Governor General in Council sanctions the estimate therewith submitted, amounting to Rupees 26,000, for four Harness rooms with Collar-makers or Carpenter's Workshop for the Artillery on the Race Course at Bangalore.

2. The above sanction has been entered as No. 63 M of 1867-68 in the Register of this Office. The estimate and plan are returned.

No. 83. ORDER THEREON, 4th September 1867, No. 2,716.

MILITARY WORKS, No. 9.

1. Communicated to the Superintending Engineer of the 5th Division for information and guidance with reference to the Proceedings of Government No. 2,038 of the 8th July 1867.

2. With a view to the work being put in hand at once, the Government sanction the transfer to it of Rupees 13,000 from the allotment for Item No. 13 of the Budget, subject to the approval of the Government of India.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division.

„ Controller of Public Works Accounts.

„ Accountant General.

„ Military Department.

Exd. S. T. Augustin.

Abstract Estimate No 36 of 1866/67.

Maintenance of Bangalore

Work Constructing Garages Room with Collar makers or Carpenters Workshop for Military on New Lines Bangalore

Quantity	Description of Works	Rate	R	S	P	Per	Amount	Total
2714	Cft of Excavation	"	"	1	Cft		14	
2714	" " Foundation Stone in Chumam	"	2	6	"		424	
1641	" " Basement do	"	2	6	"		256	
6288	" " Brick in Chumam	"	2	9	"		1081	
525	" " Archwork do	"	4	"	"		131	
344	Rft of Cornice Work in Chumam	"	4	6	Rft		97	
10678 100	Sqr of Plastering with 2 Coats of Chumam	2	8	"	Sqr		267	
7213 100	" " Whitewashing two Coats	"	3	"	"		14	
3465 100	" " Blue Washing do	"	4	"	"		8	
288-1-0	Cft of Teak Wood Wrought & put up	3	8	"	Cft		1008	
5	Frames Complete with all its ironwork	65	"	"	"		325	
5966 100	Sqr of Terracing with brick on edge Jelly 3 Coats of flat tile 3 Coats of Chumam Plastering & Complete	28	"	"	Sqr		270	
2880 100	Sqr of Roofing with teak rafters flat and painted Chumam borders & Complete	18	"	"	Sqr		518	
2502 100	Sqr of Paving with granite slabs bed ded in sand and pointed with Chumam	10	"	"	"		250	
66	Rft of Stone Slabs for tread of steps	"	4	"	Rft		17	
2614	Cft of Filling the foundation with to Basements height	"	"	1/4	Cft		3	

Carried forward 4683
4670

Quantity	Particulars of Works	Rate	R. S. P. Rs. Amount	Total
	Brought forward			4670.
1830	Cft of Filling the foundation earth			4683
	to Basement height from distance	" " 2 Cft.	19	
42	Rafter Nails	" " 9 each	2	
224	do	" " 5 "	6	
60	Harness or Saddles Complete	3 8 " "	210	
60	Accoutrements Pigs	" 12 " "	15	
6	Pairs of Panelled Doors with framing and with all its Ironwork Complete	1 8 " "	288	
2	Pairs of Panelled Windows shutters with iron bars and frames Complete	25 " "	50	
82	Rft of Ridge Ventilators	3 14 " Rft.	318	
10	Living Windows in stock which can be used in the building	7 13 " each	78	
10	do Repairing and finishing	2 " " "	20	
10	Sun shades	12 " " "	120	
14	Rft of Iron Galvanized Sheets to carry water from the Centre wall	11 " " "	176	
2	Marking boards	5 " " "	10	
3	Inventory Boards	" 12 " "	2	
10	Stone Slabs under the Doors	" 8 " "	5	
38 ³² / ₁₀₀	Sqr of Wood oiling two Coats	2 " " Sqr	77	
1	do Green painting two Coats for Living Windows	5 " " "	5	
168	Rft of Earthen pipes 3 Inches internal diameter	" 1 " Rft.	11	
66	Cybs Ramp around the Building	" 8 " Cycle	33	
26	Sqr of Graveling	1 " " Sqr	26	6184
	Sundries		310	
	Total Rupees for one			6175

Total Rupees for four — ²⁵⁷⁷⁶ 24684 5

Sundries — 1210

Registering Fee — ²⁴ 2-6

Grand Total Rupees ²⁵⁷⁷⁶ 25950

By Sups Office
Bangalore
5th Oct 1866

[Signature] Captain R.E.
Executive Engineer Bangalore

[Signature] Lieut Col R.E.
Superintending Engineer

22

183

22

Abstract Estimate for
Constructing four Stables
rooms with Collar makers
or Carpenter's work shops
for sitting on Race Course
Bamucke Bangalore
1867
J. S. M. 1867/68
No. 36

3

1

Bengalore 2/169/1
No 36

Military Camp

Accommodation for Stables

From the Executive Engineer

to the Deputy Engineer

of the Division

Walter & Co. 1867/68

Received 1326

P. 1867/68

N^o 869 M

Government of India.
Public Works Department.
Military Works.

To The Secretary to Govt. of Madras
in the Public Works Department.

Simla 13th August 1867.

Sir,

I am directed to acknowledge receipt of
your letter N^o 2039 dated 8th July 1867 and in reply
to state that the Governor General in Council sanctions
the estimate therewith submitted amounting to Rs. 26,000/-
for four Stables rooms with Collar makers or Carpenter's
Workshop for the Artillery on the Race Course at
Bangalore.

2 The above sanction has been entered as
N^o 13 M of 1867/68 in the Register of this office. The
estimate and plan are returned.

Have the honor to be
Sir

Your most Obedient Servant

W. H. M. C. Colonel R. E.
Inspector General of Military Works.

Public Works Department

Pro: of Govt. for September

No. 2716

Pro: of the Madras Govt.
D^d 4th September 1867

Communicating to the
Supg. Engrs. of the 6th Division
the Letter from the Inspector
General of Military Works.
stating that the estimate of
Rs. 26,000 for four Harness
rooms with collar-makers or
carpenter's workshop for the
Artillery at the Race Course
Barracks Bangalore, has
been sanctioned by the Govt.
of India