M.R.O. 1—77,006—8-6-37.

(1) Number of pages 10

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 3065 — Press — Mis. —

38-39

Dated 3. 10. 1867.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 3rd October 1867.

No. 38. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Salem, 25th September 1867, No. 124 :—

1. I have the honor to submit, for the sanction of Government, a revised estimate of Rupees 3,070, for constructing a Cook-room for Serjeants in Nos. 3 and 4 quarters, Royal Horse Artillery Barracks at Bangalore.

1 Revised Estimate.

2. An estimate of Rupees 2,270 for this work was sanctioned in G. O. No. 1,383, of the 13th May 1864; and again in paragraph 6 of G. O. No. 3,640, of the 15th of November 1866. An application for funds for this work was to have been made during this year, but this has not been done on account of demands for funds for works of more urgency. The Major-General Commanding now desires that the estimate may be entered in the Budget for the ensuing year, as it now exceeds Rupees 2,500.

3. The original estimate was framed so long ago as November 1863, and since then rates at Bangalore having considerably risen, the revision of the sanctioned estimate is absolutely necessary.

4. In this estimate only the rates have been altered, and stone-in-chunam has been substituted for stone-in-sand for foundation. The plan, specification, and quantities are precisely as originally sanctioned.

No. 39. ORDER THEREON, 3rd October 1867, No. 3,065.

MILITARY WORKS, No. 1.

Under the explanation afforded, the Governor in Council sanctions the revised estimate submitted with this letter amounting to Rupees 3,070, and directs that the work be entered in the Budget for the ensuing official year.

(True Extract.)

(Signed) J. H. M. SHAW STEWART, Major, R. E.,
Under Secretary to Government.

To the Superintending Engineer, 5th Division.
" Accountant General.
" Controller of Public Works Accounts.
" Military Department.

Exd S. T. Augustin.

Estimate

Revised Abstract of the probable cost of Constructing Cook Room for No. 3 and 4 Serjants Quarters in No. 2 Block Horse Artillery Barracks Bangalore.

Quantity	Descriptions of Work	Rate	Per	Amount	Total
1756	Cubic feet of Excavation	" 1	Cft.	7	
1256	Do. of Foundation Stone in Chunam	" 2 6	Do.	196	
905	Do. of Basement Stone in Do.	" 2 6	Do.	141	
3509	Do. of Superstructure Brick in Chunam	" 2 9	Do.	603	
224	Do. of Arch work in Do.	" 4 "	Do.	56	
166	Rft. of Cornice	" 4 "	Rft.	42	
270	Cft. of Burnt Brick in Mud	" 1 9	Cft.	30	
64	Granite Stones for Windows 3×1½×½	2 11 "	Each	172	
60 82/100	Squares of Plastering in Chunam including Whitewashing	2 11 "	Sqr.	162	
26 05/100	Do. of Plastering in Chunam including Blueiwashing	2 12 "	Do.	72	
11 50/100	Do. of Flooring with granite Stone bedded in Sand and pointed with Chunam	10 " "	Do.	115	
183-5-3	Cft. of Teak wood wrought and put up	3 8 "	Cft.	642	
1	Trusses Complete (40 ft. Span)	46 10 8	R	187	
8	Stone Plates under Trusses	" 4 "	Do.	2	
14 85/100	Squares of Roofing with Teak Rafters, Nails, Flat tiles and pan tiles & Chunam borders Complete	18 " "	Sqr.	267	
	Carried Over				2695

	Brought Over				2695
11 7½/100	Squares of Terracing with brick on edge 3" Jelly 3 Course of flat tiles and plastered with 2 Coats of Chunam	2	5	Sqr	32
168/100	Do of Terracing the Chimney with flat Stone in Chunam & plastering 2 Coats for complete	15	"	Do	95
54	Rft of Drain from the Cook Room into Cess Pool	"	4	Rft	11
1130	Cft of Excavation for Cess Pool	"	"	1 Cft	6
630	Do of Stone in Chunam Do	"	2	Do	98
8	Rft of Covering Stone for Do 6×1½×½	"	17	Rft	6
	Clearing the Site for the building				50
					2996
	Sundries				114
	Total Estimate of Rupees				3070

Ex. Engineer's Office
Bangalore 10th September
1867

Do J. Prinyeur A. Smith Lt R.E
Executive Engineer
Bangalore

Ed Ford Lieut R.E.
Assistant Engineer & Secy

Superintg Engrs Office, 5th Divn
Salem 25th September 1867.

No. 124.

From,

The Superintending Engineer
5th Division

To

The Secretary to
Government P.W.D.

Sir,

Enclosure
Revised estimate—

I have the honor to submit for the sanction of Government a revised estimate of Rupees 3,070, for constructing a Cook room for Serjeants in No. 3 & 4 quarters, Royal Horse Artillery Barracks at Bangalore.

2. An estimate of Rupees 2,270 for this work was sanctioned in G.O. No. 1383 of the 13th May 64; and again in para 6 of P.O. No. 3,640 of the 15th of November 1866. An application for funds for this work was to have been made during this year, but this has not been done on account of demands for funds for works of more urgency. The Major General Commanding now desires that the estimate may be entered in the Budget for

P.W. 3583/5

Revised Estimate for Constructing Cook Room for 3 & 4 Sergeants Quarters Royal Horse Artillery Bangalore

Amount of Estimate 3070

for the ensuing year, as it now exceeds Rupees 2,500.-

3- The original estimate was framed so long ago as November 1863, and since then, rates at Bangalore having considerably risen, the revision of the sanctioned estimate is absolutely necessary.-

4. In this estimate only the rates have been altered, and Stone in Chunam has been substituted for Stone in sand for foundation. The plans, Specifications and quantities are precisely as originally sanctioned.-

I have the honor to be
Sir,
Your most Obedient Servt.

E A Ford Lt. Col R.E.
Superintg Engineer
5th Division.

P. W. 156
Pro: of Govt for October
From, No. 3083

The Supt'g Engr
5th Divn

To, The Secretary to
Government P.W.D.

Dated 24th
Recd 27th } September 67

No. 124,
Encl: I.

No. 3065 - 3rd Octr 1867
Forwarding for sanction
a revised estimate of
Rs 3070 for Constructing
a Cook room for Sergeants
in Nos 3 & 4 quarters
Royal Horse Artillery
Barracks at Bangalore

Written on Slate

Nos 38 39

Connect

Public Works Dept

3065

No. 3065

Under the explana-
tion afforded, the Govern-
ment Council sanctions the
revised estimate submitted
with this letter amounting
to Rupees 3070, and directs
that the work be entered
in the Budget for the
ensuing Official year.

M.

30

5

Fort St George
3rd Octr 1867
Despd 4/10/67

6 Loss Dft
3 Ac 81
Gen Controller
for mil Dept