M.R.O. 1—77,000—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 3075 Press / Mis.

58-59

Dated 4. 10. 1859.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 4th October 1867.

No. 58. Read the following letter from the Inspector General of Military Works to the Government of India, Public Works Department, to the Secretary to Government of Madras, in the Public Works Department, dated Simla, 13th September 1867, No. 1,007. M :—

1. I am directed to acknowledge receipt of your letter No. 2,529, dated 19th August 1867, and in reply to state that the Governor General in Council sanctions the estimate therewith submitted, amounting to Rupees 5,400, for an Armourer's Workshop for the Cavalry in the Race Course at Bangalore.

Five thousand four hundred Rupees.

2. The above sanction has been entered as No. 69 M of 1867-68 in the Register of this office. The estimate is returned.

No. 59. ORDER THEREON, 4th October 1867, No. 3,075.

MILITARY WORKS, No. 3.

Communicated to the Superintending Engineer of the 5th Division, with reference to the Order of the 19th August 1867, No. 2,528.

(True Extract.)

(Signed) J. H. M. SHAW STEWART, Major, R. E.,
Under Secretary to Government.

To the Superintending Engineer, 5th Division.
" Accountant General.
" Controller of Public Works Accounts.
" Military Department.

Exd. S. T. Augustin.

Carried over 2977

Military Building- 5th Division S.P.W. New Work

Bangalore- 3

Abstract of an Estimate &c. of 1867/68-

Work. Constructing an Armourers Shop for Race Course Barracks Bangalore.

Quantity	Descriptions of Work	Rate	Per	Amount	Total
2680 3/4	Cft. of Excavation	"	1 Cft.	14	
2681	Do. of Foundation Stone in Chunam	"	26 "	419	
1603	Do. of Basement Do.	"	26 "	250	
6695	Do. of Superstructure Brick in Chunam	"	29 "	1047	
458	Do. of Arch work Do.	"	4 " "	115	
86 48/100	Squares of Plastering two Coats Chunam	2	8 "	Sqre	216
54 77/100	Do. of Whitewashing Do.	"	3 " "	10	
31 79/100	Do. of Bluewashing Do.	"	4 " "	8	
344	Rft. of Cornice Work in Do.	"	4 "	Rft.	86
18 65/100	Squares of Paving with granite Stone	10		Sqre	187
16 99/100	Do. of Roofing with teak peepers Nails, flat and Pan tiles &c complete	18	" "	"	305
11 28/100	Do. of Terracing Verandah Brick on edge Jelly flat-tiles Chunam &c complete	19	" "	"	214
4	Stone plates under the Trusses	"	4 "	Each	1
11-1/2	Rft. of Ridge Ventilators	3	14 "	Rft.	45
120	Do. of Zinc pipes	"	8 "	"	60
	Carried over				2977

Quantity	Descriptions of Work	Rate	Per	Amount	Total
	Brought over			2977	
214.7-6¾	Cft of Seasoned wrought and put up	3 8	Cft	751	
2	Trusses Complete	80	Each	160	
4	Pair of half pannelled and half glazed doors with frames and iron works complete 6×7	31 8	Pr	126	
3	Pair of Pannelled doors with frames and iron works complete 6×7	35	"	105	
12	Pairs of Sliding Windows with frames Yc 6×1½	9	"	108	
1	Iron barred door with bolts hinges locks Yc complete 6×7½	115	"	115	
3	Pair of Venetian Windows with frames hooks hinges and bolts Yc complete 3×5	20 10	"	62	
2	Pair of Glazed window Shutters with frames Yc complete 5×6	7 1	"	113	
1	Pair of Almirah or Cupboard let into the wall with Padlock Yc complete for Spare tools and Chemical 6×7	10	"	10	
5 17/100	Squares of Green Paint two coats	5	Sqre	25	
29 30/100	Yd of Wood oiling two coats	2	"	59	
2258	Cft of Filling the Basement (in close)	"	¼ Cft	3	
1170	Yd of Yd (in distance)	"	2 "	15	
26	Rft of Lance rests for Stand Arms	1 10	Rft	113	
	Carried over			4662	

Quantity	Descriptions of Work	Rate	Per	Amount	Total
	Brought over			4662	
5	Rft of Lance rests with Stand Yc complete to be fixed in the Centre of the Room	1 8	Rft	23	
1	Boiler for browning Arms	35	Each	35	
24	Rft of Bench 32" high 3' wide to run whole width of shop (working table)	10	Rft	240	
2	Hand Vices and Rack two horses on which to rest Rifle barrels when under Repair (with fitted on the bench Yc)	40	Each	80	
36	Rft of Tool racks	" 6	Rft	9	
36	Yd of shelf for tools	" 6	"	11	
24	Rft of Sloping shelf to hold tools in use (over the table)	" 12	"	18	
1	Forged iron Hood and the Rod with sheet iron cover Yc complete	25	Each	25	
	Bench for Lathe	12	"	24	
2	Square for Bar	1 8	Sqre	2	
1	Levelling the Earth	"	"	7	
	Carried over			5139	

Quantity	Description of Work	Rate	Per	Amount	R
	Brought Over			5139 " "	
1	Hearking Board	5 " "	Each	5 " "	
1	Inventory Board	" 12 "	"	1 " "	
				5145 " "	
	Sundries at 5 per cent			255 " "	
	Total Rupees				540

Executive Engrs Office
Bangalore 2d July
1867

Lt J. Pennycuick Lieut R.
Executive Engr Banga

Lt Ind Lieut Colt R.E.
Assistt Engineer 5th Division

No. 1007 M

9

Government of India.
Public Works Department.
Military Works

To
The Secretary to Govt. of Madras,
in the Public Works Department.

Simla 13th September 1867.

Sir,

I am directed to acknowledge receipt of your letter No. 2529 dated 19th August 1867 and in reply to state that the Governor General in Council sanctions the estimate therewith submitted amounting to Rs. 5,400 for an Armourer's Workshop for the Cavalry in the Race Course at Bangalore.

2. The above sanction has been entered as No. 69 M of 1867/68 in the Register of this office.—The Estimate is returned.—

five thousand four hundred Rs.

I have the honor to be
Sir
Your most Obedient Servant.

W Cunningham Colonel
Inspector General of Military Works.—

audited

6/10

7th Division P.W.
Bangalore

P.W. 3689/67

Abstract of an estimate for
Constructing an Armourers
Shop on the Race Course
Barracks

Sanctioned by No. 1007 M dated 13th Sept 1867

Amount of Estimate Rs. 5400

Ent. 1867
Pro: of Govt. for Sept.
Fo 3089.

Cir

From
The Inspector General
of Mily: Works
Govt of India
Dated 13th Sept
Recd 27- - } 1867

No 1007 Gn-

Gn: N

Commencing
the sanction of the Govt
of India to the estimate
of Rs: 5400 for an Ar-
mourer's workshop
for the Cavalry in the
Race Course at Ban-
galore-
ese 3075- dtd 6th Octr 1867

Wm Ayder

No 58-59

2nd Octr 1867 Da 3rd

No 3075

Commd to the Supg
Engineer of the 5th Divn
with reference to the
order of the 19th August
1867, No 2528-

M.

Genl St George
4th Octr 1867

6 Bo ES Dn
3 Mil
4 Mounted
7 Ins Dept

Dispd 5/10/67