M.R.O. 1—77,006—8-6-37.

6

(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

# MADRAS RECORD OFFICE.

## Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 387 Press Mis.

137-38

Dated 7 2 1867.

***Not to be folded or roughly handled***

*Proceedings of the Madras Government, Public Works Department, 7th February* 1867.

No. 137. Read the following Proceedings of the Madras Government in the Military Department:—

Approving an estimate of Rupees 3,027 for putting up new tiled roofs to the cattle lines at Bellary. (Here enter 1st February 1867, No. 411.)

No. 138. ORDER THEREON, 7th February 1867, No. 387.

MILITARY WORKS, No. 7.

Communicated to the Superintending Engineer of the 3rd Division, who will submit an application for funds after the 1st April next.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
*Secretary to Government.*

To the Superintending Engineer, 3rd Division.
" Accountant General.
" Controller of Public Works Accounts.
" Military Department.

## MILITARY DEPARTMENT.

### *PROCEEDINGS OF THE MADRAS GOVERNMENT.*

Read the following papers :—

Memorandum from the Deputy Quarter Master General, Fort Saint George, 8th January 1867, No. 211; to the Secretary to Government, Military Department.

Forwarded to Government for sanction, with reference to paragraph 2 of Proceedings of Government, No. 2442, dated 13th July 1866.

2. The Commander-in-Chief recommends that funds may be appropriated for this work from savings, if available, in the budget of 1867-68.

---

From the Commissary General, Madras, 4th January 1867, No. 5364; to the Quarter Master General, Fort Saint George.

With reference to your endorsement, No. 6812, dated 8th August 1866, on the Proceedings of Government. dated 20th June 1866, No. 453, in the Public Works Department, I have the honor to forward, for the approval of His Excellency the Commander-in-Chief, an estimate for tiling the public cattle lines at Bellary, and to request that it may be included in your budget.

---

ESTIMATE of the probable cost of putting up a new tiled roof to the Commissariat bullock lines, in lieu of the present thatched one—*vide* Commissary General's letter, No. 246 of the 2nd November 1866.

| Description of work. | Length. | Breadth. | Depth. | Number. | Superficial area. | Cubical contents. | Rate. | | | Per | Amount. | | | Total. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | RS. | A. | P. | | RS. | A. | P. | RS. | A. | P. |
| Teakwood rafters, each 12×3×4 ..... | 1,152 | 3 | 4 | 96 | ... | 96 | | | | | | | | | | |
| Ridge pole ..... | 96 | 4 | 6 | 1 | ... | 16 | | | | | | | | | | |
| Bressummers ..... | 192 | 3 | 4 | 2 | ... | 16 | | | | | | | | | | |
| Teakwood wrought and put up ..... | ... | ... | ... | ... | ... | 128 | 4 | 0 | 0 | cubic feet. | 512 | 0 | 0 | | | |
| Roofing with bamboo reepers, mats and pot tiles... ..... | 96 | 24 | ... | ... | 2,304 | ... | 15 | 0 | 0 | square. | 345 | 9 | 7 | | | |
| 12 upright granite posts, each 10′ long ..... | ... | ... | ... | ... | ... | ... | 7 | 0 | 0 | each. | 84 | 0 | 0 | | | |
| | | | | | | | | | | | | | | 941 | 9 | 7 |
| Sundries at 5 per cent. | ... | ... | ... | ... | ... | ... | ... | ... | ... | ..... | ... | ... | ... | 47 | 6 | 5 |
| Removing the present old roof, &c..... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ..... | ... | ... | ... | 20 | 0 | 0 |
| Total estimate for one. | ... | ... | ... | ... | ... | ... | ... | ... | ... | ..... | ... | ... | ... | 1,009 | 0 | 0 |
| Do. for three. | ... | ... | ... | ... | ... | ... | ... | ... | ... | ..... | ... | ... | ... | 3,027 | 0 | 0 |

BELLARY, *15th December* 1866.

(Signed) T. MULLINS,
*Cantonment Overseer for Asst. Engineer.*

---

ORDER, No. 411, 1st February 1867.

Approved.

2. Funds will be provided in due course by the Public Works Department.

(True Extract.)

J. Marshall *Major General,*
*Secretary to Government.*

To the Quarter Master General.
" Commissary General.
" Public Works Department. With 20 spare Copies
" Controller of Military Accounts.

Exd. J. E. Cashart.

Lid

387

No 387

Command to the
Superintendent of the
3rd Div., who will submit
an application for funds
after the 1st April next.

Fort St George
7th May 1867

1 Lot 3 Div ✓
3 " Uy Bl ✓
1 " Centre Bl ✓
1 " Ring Dead ✓

30/5

Dup: 8/2/67