

(1) Number of pages 8

(2) Date of repair 12-3-63

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. <u>417</u>	Press ~~Mis.~~
<u>200-231</u>	
Dated <u>12-2-</u>	<u>18 64</u>

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
12th February 1867.*

No. 200. Read the following Proceedings of the Madras Government in the
Revenue Department :—

Approving of a revised estimate of Rupees 1,340 }
for additions to the Talook Cutcherry at Kist- } (Here enter 7th February 1867, No. 321.)
nagherry, in the Salem District.

No. 201. ORDER THEREON, 12th February 1867, No. 417.

CIVIL WORKS, No. 25.

Communicated to the Superintending Engineer of the 5th Division for information and guidance.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with one Specification.
.. Accountant General.
.. Controller of Public Works Accounts.

Exd. S. T. Augustin.

*Wm. W. ... Assistant Engineer
Superintending Engineer*

5th Division D.P.W. 3

Civil building New Work.

Salem District Post Range Kistingherry Taluk

Abstract Estimate No. _____

Work Extending and improving the Taluk Bazaar at Kistingherry

Quantities	Particulars of work	Per	Rate	Amount	Total
138 3/4	C. yds. of Brick work in Chumam	C. yd.	3 8	466 1/2	
5 7/16	do. Flat arch work in do.	do.	4	21 3	
38 7/100	Squares Plastering with 2 coats of do.	Sq.	2 8	95 12 8	
6	do. Flooring with brick jelly in do.	do.	2 8	15	
9 7/16	do. Terracing with brick on edge tiles, including plastering with Chumam, exclusive of wood work	do.	10	95 10	
15 1/4	do. feet — Jungle wood wrought and put up for beams, & joists	C. ft.	2	302 5	
1	Jungle wood pannelled Door in halves with iron hinges, bolts, lock &c. complete 4 1/2 x 7	each	24	24	
1	do. Door frame & door with iron bars do. do. 4 x 7	do.	30	30	
1	do. do. do. do. do. do. 3 x 6	do.	20	20	
1	do. do. do. do. do. do. 3 1/2 x 6	do.	20	20	
4	do. pannelled Windows with iron bars hinges, bolts &c. complete 3 1/2 x 5	do.	15	60	
8	do. Ventilators with iron bars &c. complete 3 x 4	do.	10	80	
9 1/4	Running feet of Cornice work in Chumam	R. ft.	3	17 12	
27 10/16	C. yds. Excavating foundations	C. yd.	1 2	27 15	
2 7/16	Squares of Kailas with palmurash &c. Record hall	Sq.	10	27	
	Sundries				
	Total Estimate Rs.			1270	

Rs. one thousand two hundred & seventy only

J. T. T. T. T. T.
Collector of Salem.

Post Range Office
Post 2nd November, 1886.

J. T. T. T. T. T.
Superintending Engineer.

35

**Proceedings of the Madras Government, Revenue Department,
7th February 1867.**

No. 73: Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Porto Novo, 24th January 1867, No. 165:—

1. With reference to G. O. No. 1,808, dated 8th June 1866, I have the honor to submit, for sanction, a revised estimate, amounting to Rupees 1,340, accompanied

by plan and specification, for additions to the Talook Cutcherry at Kistnagherry.

2. The estimate previously forwarded provided only for a tiled verandah in front of the building. This estimate provides for additional wards for prisoners, and a room for the Tahsildar.

3. The plan and estimate have been approved of by the Collector of Salem, and I request sanction for the work from the "Reserve" of next year under Civil Buildings.

—
Referred to the Revenue Department.

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government, P. W. D.

FORT SAINT GEORGE,
29th January 1867.

No. 74.

ORDER THEREON, 7th February 1867, No. 321.

Miscellaneous.

Approved.

(True Extract.)

Edmundston

Secretary to Government.

To the Public Works Department. *and also*
to the Board of Revenue.

Exd. S. T. Augustin.

Approved by Collector No. 1270

Estimate for extending and improving the City Cutcherry at Kistnagherry

Abstract

2/14/60
5-4/8
Salem District
Deputy Magistrate

20

Bill

417

210417

Commd to the July

Inspector of the S. & C.
for information and
guidance

to
J. G. T. Moorey
12th St. & 1st St. 1867

W. H.

to J. G. T. Moorey
210417
210417
210417

7th 1867 Dep^d
Pro: of Govt for February
No 453

Pro: of the Madras Govt
in the Revenue Dep^t

Of 7th
No 9th } Febry 1867

Ca: 3. No 321

1500000

Approving of a
revised estimate of Rs
1340 for additions to the
Taluk Cutcherry at
Thesuvagerry in the
Salem Dt.

No 417. 12th Feby 1867.

No 200-201

With an Order