M.R.O. 1—77,000—8-6-37.

(1) Number of pages 2

(2) Date of repair 23.12.37

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Courts DEPARTMENT.

G.O. No. 573 Press Mis.

434-435

Dated 22-2-1937.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 22nd February 1867.

No. 434. Read the following letter from the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department, dated Camp Madaveram, Adoni Taluk, 7th February 1867, No. 3,100:—

1. I have the honor, with reference to G. O. No. 3,670 of 17th November last, to submit, for the sanction of Government, plan, specification, and estimate amounting to Rupees (34,800) thirty-four thousand and eight hundred, for constructing ten new Wash-houses for the use of the European Regiment stationed at Bellary.

2. The plan on which these Wash-houses are to be built is the standard design forwarded with G. O. No. 2,982 of 17th September last.

3. The work is in progress, and it is fully expected that the amount, Rs. 15,000, allotted in the Budget of the current year will be worked up before the 31st March.

No. 435. ORDER THEREON, 22nd February 1867, No. 533.

MILITARY WORKS, No. 22.

1. In their Orders No. 2,952, dated the 14th September 1866, the Government approved of an estimate of Rupees 32,000 for the construction of ten Wash-houses for the European Regiment stationed at Bellary. Subsequently the Superintending Engineer of the 3rd Division was instructed to submit a fresh estimate for the work revised with reference to the standard plan circulated with G. O. No. 2,982, of the 17th September 1866, and in the letter above read Major Moberly complies with that requisition.

2. The Government sanction the estimate of Rupees 34,800 which is now submitted, and note that, in addition to the Budget allotment of Rupees 15,000,* a sum of Rupees 6,297 was granted for the Wash-houses in G. O. No. 398, dated the 8th February 1867.

* Item No. 2, Part II.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division, with one Specification.
,, Controller of Public Works Accounts.
,, Accountant General.
,, Military Department.

Exd. S. T. Augustin.

ABSTRACT ESTIMATE.

Ballary District.

Work. Constructing 10 T. iron Cranes for the Race of the Saw Pit Reservoir at Ballarat

Quantities.	Description of Work.	Rate.	Amount.	Amount of each part.
6956	Cft. Stone in Chunam	Cft. at	a 2 a	869 9 a	
478	Do. brick in Do.	do. at	a 3 a	95 5 8	
168	Sft. Dressing Cornice work	Sft. at	a 2 6	16 12 a	
76	Cft. Circular Arch work	Cft. at	a 4 a	19 a a	
69	Cft. Cornice work	Cft. at	a 4 a	17 12 a	
6185	Sft. of Plastering with 2 Coats of Chunam	Sqre. at	3 8 a	216 7 6	
78	Cft. Slabs 2 feet square	Cft. at	a 6 a	29 4 a	
18	Do. Slabs over Honeycomb arch	Do. at	a 3 a	3 6 a	
41	Do. Oval Reservoir of Building 3 feet	Do. at	a 8 a	20 9 a	
8	Cft. Steps	Do. at	a 11 a	2 11 a	
836	Sft. Flooring with Squared Deals	Sqre. at	8 8 a	71 a a	
2	Slabs for small Reservoirs	each at	4 a a	8 a a	
60	Cft. Slabs for Saw Stand Arches Stone	Cft. at	1 a a	60 a a	
2	Panneled Doors 4 x 8	each at	45 a a	90 a a	
4	Glass Windows 4/2 x 3	do. at	20 a a	80 a a	
7	Small Doors wooden frames with Canvass 2 x 6/2	do. at	15 a a	105 a a	
21	Sft. Gratings to Washhouse	Sft. at	1 a	21 a a	
65	Bags 2 feet in length	each at	a 8 a	32 8 a	
216-6-11	Cft. Fatwood	Cft. at	1 a a	866 4 11	
15	Iron Tie rods	each at	17 a a	255 a a	
4	Wooden Ventilators in Roof of bath Rooms Complete	do. at	20 a a	80 a a	
352	Sft. Roofing Rough Ventilators 3 Courses of Flat Tiles & Chunam Plaster	Sqre. at	17 a a	59 13 5	
	Carried forward			2298 5 6	

Qty.	Description of Work	Rate	Amount
	Carried forward		
1012	Sft. Roofing Tiles laid on Battens		
462	Sft. Roofing Tiles laid on Terrace Brick on edge Gutters		
	Coomes of Red Lime Concrete of Chunam		
21	Sft. 2 Gratings to Drain Channels		
2000	Sft. Wood Ceiling		
35	Rft. Drain Gutters on Chunam Plasters & Covers with granite Slabs		
2	Cisterns 4½ feet deep 6 feet Square Inside Chunam Plastered & fitted with Copper Taps complete		
85	Cyds. Ex Earthwork		
	Pillars in Plastered Chunam for Roofing		
	Total		
	Total for 10 Huts Each		
	Deduct for Huts not built		5400

Bellary
31st January 1867

Asst. Engineer

Asstt. Engr. 3rd Div.

Superintg. Engr. 3rd Division
Camp Madadevan
Colony Salem
Bellary District
4th February 1867.

No. 3100

From

The Superintending Engineer
3rd Division

To

The Secretary to Government
Public Works Department
Madras

Sir,

I have the honour with reference to C.O. No. 3670 of 17th November last, to submit for the sanction of Government, Plan, Specification and Estimate Amounting to Rupees (34,800) Thirty four thousand and Eight hundred) for Constructing 10 Ryl Hash Houses for the use of the European Regiment Stationed at Bellary.—

2,— The Plan on which these Houses are to be built is the Standard design forwarded with C.O. No. 2982 of 17th September last.

3,— The work is in progress and it is fully expected that the Amount Rs. 15000, allotted in the Budget of the current year will be worked upto before the 31st March.—

I have the honor &c.

A. Addy Major RE
Superintg. Engineer 3rd Div.

Public Works 1867 Department
Govt. of Govt. for February
Proc. No. 538

From The Superintg. Engineer
S. Division

To
The Secretary to Govt.
P. W. Dept.

Dated 7th February 67
Rec'd 15th do

No. 3100

Encl. 3

Forwards Plan, Specification and Estimate for Constructing 10 New Wash Houses for the use of the European Regt. stationed at Bellary amounting to Rs. 34,800-11-10

No 434

P.D. 533 - 22nd Feby 1867.

Public Works Dept

No. 539

Proceedings of the Madras Government

Under date the 2nd February 1867

Read the following

from the Superintending Engineer
of the 3rd Div.

Here under 7th February 1867
Fs 31001

In their orders No. 2952,
dated the 14th September 1866,
the Government approved of
an estimate of Rupees
32,000 for the construction
of ten wash-houses for
the European Regiment
stationed at Bellary—
Subsequently the Superintending
Engineer of the 3rd Division
was instructed to submit
a fresh estimate for the
work revised with reference
to the Standard Plan cir-
=culated with S. O. No. 2982,
of the 17th September 1866, and
in the letter above read

JP

WSH

Constructing 10 Wash
houses for the use of
European Regiment at
Bellary—

No 4634

Rs 32,000

Date 31st January 1867
Received

Rs 31001

Rs 539 dated 22nd February 1867

Major Moberly complies with the requisition —

The Government sanction the estimate of Rupees 34,800 which is now submitted, and note that, in addition to the Budget Allotment of Rupees 15,000, a sum of Rupees 6,297 was granted for the work Noted in G.O. No. 398 dated the 8th February 1867 —

Item No. 3
Part II

To the Sup[t] Eng[r] S. Div. with one Sketch
— c. Instructions of Govt.
— c. Account Samuel
— c. Military Dept.

Dept. 25/2/67

Pub: Works 1867 Depart.t

Pro: of Govt. for February

No. 533

Pro: of the Madras Govt.

Dt 22d. February 1867

The revised estimate of Rs. 34,850 for the construction of Bath-houses (5 in) for the European Regiment at Bellary, Sanctioned.

No 434-435