M.R.O. 1—77,006—8-6-37.

(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 254
523-524.

Press
~~Mis.~~

Dated 28—1— 1867.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
28th January 1867.

No. 523. Read the following letter from the Superintending Engineer, 6th Division, to the Secretary to Government, Department Public Works, dated Shealli, 16th January 1867, No. 1,201 :—

1. I have the honor to enclose a plan and estimate of the proposed alterations and improvements to certain out-buildings adjacent to the old Court-house, which has recently been converted into a Talook Cutcherry at Combaconum.

Enclosures two.

2. Accommodation is required for thirty prisoners, the number sometimes confined at Combaconum has risen to fifty, but this is exceptional.

3. The building will, at the ordinary rate of thirty prisoners, provide 47 square feet and 515 cubic feet per prisoner.

4. The approximate amount required for this building was entered as Rupees 1,240 in the list forwarded on the 5th December 1866, and Rupees 400 have already been allotted for the work in G. O. No. 4,025, dated 20th December 1866.

No. 1,055.

No. 524. ORDER THEREON, 28th January 1867, No. 257.

CIVIL WORKS, No. 104.

The Government sanction the estimate of Rupees 1,300 which is submitted with this letter for converting the out-buildings of the old Court-house at Combaconum into a temporary Subsidiary Jail. Rupees 400 have been allotted for this work in G. O. 4,025, dated 20th December 1866.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 6th Division.
„ Judicial Department.
„ Controller of Public Works Accounts.
„ Accountant General.

Exd. S. T. Augustin.

Brought forward ——— 83906

Civil Buildings. New Work.

Tanjore District

Coumbaconum Taluq

Abstract Estimate No 66-67

Work ——— Converting Old Civil Court (New Taluq Cutcherry) Out Buildings into Temporary Subsidiary Jail

Quantity	Description of Work	Rate	Amount	Amount of each part.
1333 1/2	C/f Demolishing old work per c/f	- - 4	27 12 6	
1070 1/4	Do Brick in chunam Do	- 2 -	133 12 6	
3200.	Sup[l]y/f Taking down and replacing roof including materials per Square	2 4 -	72 - -	
40.	New Palmyrah rafters 12' each	1 - -	40 - -	
500	Reepers 10' (per 100)	9 12 -	48 12 -	
48000	Pan tiles (per 1000)	2 - -	96 - -	
19000.	Flat tiles Do	1 8 -	28 8 -	
	Rafter and reeper nails		10 - -	
448.	Ridge Ventilator per Sq[e]	15 - -	67 3 2	
624	Sup[l]y/f/t Terracing Guard Room with Brick on edge jelly, 3 courses of flat tiles and 3 Coats of plastering including country wood joists 6"x3" per Square	22 8 -	140 6 4	
	Repairing floor wherever required		20 - -	
1000.	Sup[l]y/f/t Plastering round doors and windows and wherever required	2 - -	20 - -	
1360o.	Do Whitewashing per Sq[e]	- 4 -	34 - -	
4.	Teak wood Doors without battens but complete with hinges 6'x3 7x4	15 - -	60 - -	
	22 Maunds of 3/4" bar iron for above 2a. door 10 bars (per maund)	1 14 -	41 4 -	
	Brought forward		839 10 6	

	Carried Over				839	10	6
2.	Doors- Country wooden battens hinges &c complete ea 4x7 at	1	14	.	28	.	.
2	Do- Teak wood without batten but complete with hinges ea 7 3 x 6 at	12	8	.	25	.	.
7½	Maunds of 3/4" bar iron for above each 8 bars (per maund)	1	14	.	14	1	.
5.	Windows, Teak wood frames without batten ea. 4 x 6 ait	6	.	.	30	.	.
23	Maunds 3/4" bar iron for above each window 10 bar (per maund	1	14	.	43	2	.
12	Windows, Teak wood batten complete with hinges &c ea 3 x 4 ait	1	8	.	210	.	.
28 2/7	Maunds 3/4" bar iron for 11 of above ea 8 bars per maund	1	14	.	53	6	.
						1242	14 0
	Sundries and Contingencies					57	2 .
	Total Estimate Rupees					1300	. .

Combaconum
3d December 1866.

(Signed) George T. Walsh
Assistant Engineer

Supg. Engrs Office 6th Div.
Tanjore 5th January 1867.

H. F. Drake Captain R.E.
Supg. Engineer 6th Division Tanjore

Examined
Collector & Magistrate

No 1201.

Sup^t Eng^s Office 6^th D^n
Skeallie 16^th January 18

From,
Captain R. F. Baker R.E.
Sup^t Engineer 6^th D^n

To,
Colonel C. A. Orr R.E.
Secretary to Government &c.

Sir,

I have the honor to enclose a Plan & Estimate of the proposed alterations & improvements to certain out Buildings adjacent to the Old Court House which have recently been converted into a Sailing Catchery at Combaconnum —

Accommodation is required for 30 Prisoners; the number sometimes confined at Combaconnum has risen to 50, but this is exceptional

The Building will, at the ordinary rate of 30 Prisoners, provide 47 square feet and 515 cubic feet per Prisoner —

The approximate Amount required

required for this Building was
entered as Rs 1240 in the Sketch for
=warded on the 5th December 1866, of Rs 1055
Rs 400 have already been allotted
for the Work in S.O. No 4025, dated
20th December 1866 -

I have the honor to be
Sir,
Your most Obdt Servt
W. F. Baker Capt RE.
Supt Engineer 6th Div.

Ps. of Govt for Damp Proof 191
The Supt Engr
6th Div
To The Secretary
to Govt of B.P.W.
Dated 16th January 66
Recd 18th
No 1201 T.E.
Encl
Howard's Plan
& Estimate of the
proposed alteration
& improvement to
Certain out Buildings
adjacent to the
Salug Entrenchment
& Embarcoonum
etc, 25th - 28th Jany 1867

No 523

C. 23rd Jany 1867 R. 25th

Public Works Dept.

257

No. 257

Proceedings of the Madras Government

191

Under date the 28th January 1867

Read the following.

From the Supg Engineer
of the 6th Dist

(Store entry 16th January 1867
No 1201)

The Government sanction
the estimate of Rs 1300 which
is submitted with this letter
for converting the ant. building
of the old Court house at
Combaconum into a temporary
subsidiary jail. Rs 401 have
been allotted for this work in
G.O. 4025 d/ 20th Dec 66.

34

Dept 29th Jany 67

The Engr 6 Dist
Jude Depr
Controller
Asst Genl

Pub: Works 1867 Department

Pro: of Govt for January

No 257

Pro: of the Madras Govt

Dt 28th January 1867.

An estimate of

Rs. 1300 for the conversion

of the out-buildings of

Court-house (old) at

Combaconum into a tempora-

ry Subsidiary Jail, Sanctd

No 523-524

23rd Jany 1867 Cl. 25