

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 274	Press
531-532	Mrs.
Dated 27-1-	1868.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
27th January 1868.*

No. 531. Read the following Proceedings of the Madras Government in the
Judicial Department :—

Passing orders on certain proposals submitted by }
the Inspector General of Jails for the alter- } (Here enter 15th January 1868, No. 53.)
ation and enlargement of the Jail at Bellary. }

No. 532. ORDER THEREON, 27th January 1868, No. 274.

CIVIL WORKS, No. 70.

Communicated to the Superintending Engineer of the 3rd Division, who is requested to submit a revised estimate for the improvements to the Jail at Bellary, prepared with reference to the modifications sanctioned in the foregoing Proceedings.

1. Major Moberly will be careful to include the cost of quarters for a Dresser, and to provide for the isolation of civil from criminal prisoners in the manner indicated in paragraph 8. His attention will also be drawn to Proceedings No. 3,226, dated 18th October 1867, with regard to the extent of accommodation to be provided in the Jail Hospital.

2. Major Moberly will be careful to include the cost of quarters for a Dresser, and to provide for the isolation of civil from criminal prisoners in the manner indicated in paragraph 8. His attention will also be drawn to Proceedings No. 3,226, dated 18th October 1867, with regard to the extent of accommodation to be provided in the Jail Hospital.

3. Adverting to paragraph 9, it is observed that the expenditure on the Jail up to the 31st March last was Rupees 5,046, and that the allotments for it during the present and the ensuing official years are Rupees 10,394 and 20,000 respectively. The Superintending Engineer will report what additional sums he will be able to spend on the work during each of those years.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Judicial Department.

„ Superintending Engineer, 3rd Division.
„ Controller of Public Works Accounts.
„ Accountant General.

Erd. F. R. Bantleman.

3

Proceedings of the Madras Government, Judicial Department,
15th January 1868.

Read the following papers:—

No. 88. From Lieutenant Colonel W. J. WILSON, Inspector General of Jails, to the Chief Secretary to Government, Fort Saint George; dated Cuddapah, 6th December 1867, No. 139.

During my recent inspection of the District Jail at Bellary, I was shown the plan and estimates of the proposed extensions and improvements which were about to be forwarded to Government, and I have now the honor to submit the following observations thereon.

Judicial Department, 15th March 1867, No. 443.

2. *Old Court-house.*—The alterations in this building have been already completed, with the exception of raising the pillars of the verandahs as suggested in the remarks in Table C appended to the Sanitary Commissioner's letter published with the Proceedings above quoted. This may be done when the tiles are renewed, which will be necessary before long. I am informed that the slope of the roof does not actually require the alteration, but, as the expense will be small and accommodation for fourteen additional prisoners will be gained thereby, it will be advisable to carry it out. The building is now light and well ventilated, and as it stands on a high basement the wards are good.

Palisading.—The old wall in the centre has been replaced by a low wall surmounted by an iron railing which extends from the inner corner of the present latrine to the corner of the old guard-room close to the compartment for females.

Old Wards.—The solid wooden doors of those wards which it is proposed to retain have been replaced by iron grated doors.

Office.—This has been finished.

Guard-rooms.—A guard-room has been built on each side of the outer gate. One is for the men. The other is divided into two: one-half is occupied by the Officer in charge of the guard; the other is used for the Arms. Since I saw the original plan, four apertures, each measuring 3 feet by 1½ feet and within easy reach from the ground, have been made in the outer wall of the Jail against which the guard-rooms have been built. I am given to understand that this was done at the requisition of the Superintendent of Police, in order to enable the guard to command the interior of the Jail in case of a disturbance, but I am of opinion that the existence of four openings through which anything may be passed either into or out of the Jail is highly objectionable, and that they ought to be closed forthwith. When plans have been sent to me for remark and have been returned to the Public Works Department for execution, they ought not to be altered without reference, and without some explanation of the grounds upon which the change is proposed.

Condemned or Solitary Cells.—These have been built, but the doors have not yet been put up. Those provided are simple iron gratings, which defeat one of the principal objects sought to be attained, as a prisoner inside could with such doors see all that goes on in the yard. Fixed wooden venetians reversed, and screwed on to the outside of the frames of the present gratings, would probably answer the purpose. A space for floor ventilation should be left, and be protected by an ordinary weather-board.

3. A great improvement has been effected by the additions and alterations above described, and as they have cost upwards of 10,000 Rupees, the question raised regarding the erection of a new Jail may be considered at an end, and I, therefore, recommend the adoption, with certain modifications, of the measures detailed by Mr. Ellis in his letter above specified. If the walls of the existing buildings, which it is proposed to retain, are raised, and the partition walls removed as indicated in Major Moberly's plan, the accommodation, exclusive of that in the Hospital, will stand thus:—

Old Court-house.....	103
Old Jail.....	144
General Wards.....	36
Female Wards.....	36
Total... ..	319

This is considerably in excess of what will be required for short-sentenced and under-trial prisoners, the number of whom, including that of debtors, was estimated by Messrs. Rohde and Ellis at 275, and I do not think it likely to exceed that figure under ordinary circumstances. There has been considerable fluctuation; but, exclusive of lunatics and lepers, I would calculate the probable number of short-sentenced prisoners as follows:—

	Males.	Females.	Total.
Convicts, including security.....	200	14	214
Under-trial prisoners.....	30	2	32
Debtors.....	12	1	13
Total ..	242	17	259

The number of long-sentenced convicts is usually double that of the short-sentenced convicts, and when the Jail was crowded the number of the former bore a still higher proportion to that of the latter. On the 23rd November last there were 410 males and 27 females in Jail, 437 in all; of these 311 were in the wards, 99 in tents, and 27 in Hospital, of whom 21 were patients. Out of 381 male convicts, 266 had been sentenced for more than one year, and 115 for one year and under. Judging from the past, I believe that the present population of the Jail is rather less than it is likely to be on an average, and that provision should be made for about 450 prisoners of all classes, exclusive of debtors; for, although there may be accommodation in the Central Jail at Vellore for a certain number of convicts in addition to those sent from the Districts of North and South Arcot, Madras, and part of Nellore, it is not probable that all of the long-sentenced Bel-lary convicts could also be received. It is advisable, therefore, to enclose as much ground to the west and north of the present Jail as may be required for wards to contain 130 convicts, and for a latrine.

4. I will proceed to specify the modifications I propose.
Old Jail.—The floors of the wards are only a few inches above the level of the yard. There is no proper basement. The floors may easily be raised 8 or 10

inches; but, in order to preserve the allowance of cubical space, the walls should be raised in the same proportion.

General Wards.—I propose to assign these to the under-trial prisoners. The palisading forming the western enclosure of the compartment for females might be extended so as to divide the under-trial yard from the old Jail, but, as the separation so obtained would be imperfect, I do not think it advisable to incur the expense.

Compartment for Females.—Two sides of this compartment being formed of palisading, there will be a want of privacy to a certain extent, and I would, therefore, retain one of the old solitary cells, say that to the east, and fit it with a bathing cistern, where the women could wash themselves without being seen. Instead of the 12 feet of palisading abutting on the outer wall, and by which the compartment is to be separated from the under-trial yard, I recommend a wall of the same height as the outer wall. I have not proposed any separate accommodation for under-trial females. Their number has been very small, seldom exceeding one.

Hospital.—The pitch of the roof being so steep that the tiles are constantly slipping, the pillars of the verandah are to be raised. The cells immediately behind the building are to be demolished, and others erected at a greater distance, as shown in the plan, for lunatics, lepers, and patients suffering from contagious diseases. Nothing further appears to be required, with the exception of a dead-house, which may be built on the spot indicated on the plan.

Hospital for Females.—Female prisoners are general healthy. There have been no deaths amongst those in this Jail during the present calendar year, nor any case of serious illness. Two separate wards, each to contain two women, will, I think, be quite sufficient. This part of the plan should be revised in accordance with the 3rd paragraph of the Order of Government noted in the margin, wherein 54 superficial and 800 cubic feet have been approved of as the allowance of space for patients in Jail Hospitals. The dimensions shown in the plan would give 99 superficial and 1588 cubic feet per patient in one ward, and 101 superficial and 1616 cubic feet in the other.

Old Work Shed.—This is to be removed.

Granary.—This is much in want of ventilation, which may easily be afforded by common pot-ventilators in the roof. This will obviate the inconvenience at present experienced when the grain is being measured out.

Workshop.—It is proposed to make this 36 feet broad. I think 24 feet will be quite sufficient.

Cook-room.—This is too near the workshop, and ought to be removed 50 feet towards the west. I propose that the building should be 90 feet long and 22 feet broad, giving 8 feet inside the pillars, instead of 7 as at present, and which is scarcely sufficient. If the pillars in the centre are made 12 feet, and those at the sides 7 feet high, it will be enough. The food of all classes, with the exception of debtors and female prisoners, will be cooked here.

Outer Gate.—This is an iron grating much out of repair. The gateway is needlessly wide. I recommend that it should be narrowed by one foot on each side, and

that the present grating may be replaced by a solid wooden door of moderate thickness, with a wicket in one leaf, so that single men may enter, and the necessity of opening the main gate on every occasion may be avoided.

Palisades.—These are to abut against the outer wall in several places, which is objectionable as affording facilities for escape, but this cannot be avoided, except by carrying the palisading round the buildings parallel to the wall, which would be very expensive. A *cheval de frise* at each of the points in question would diminish the risk to some extent.

Latrine for Women.—The spot indicated in the plan is in the main yard near the office, which is not a convenient situation for a building of this nature. If it is placed in the north-eastern corner of the compartment, it will be very little nearer the wards than if built on the spot shown in the plan.

Jailer's Quarters.—These are in very bad repair. The Range Officer has been requested by the Superintendent of the Jail to state what is required to be done.

Dresser's Quarters.—The Dresser lives about $1\frac{1}{2}$ mile from the Jail, and is unable to procure a house nearer. There is a piece of ground adjoining the Jailer's quarters upon which a house may be built when funds are available. In the meantime he must sleep in the Hospital when such is necessary, or the room outside the gate, at present used for the arms of the guard, might be made over to him for that purpose. The ordinary arrangement is that the arms of a guard are kept with it, and not in a separate place.

Drainage.—Surface drainage is required, more especially in the main yard, which becomes flooded after rain.

New Wards.—The plan shows what has been proposed with regard to the new enclosure, and the buildings to be erected therein, viz., convict wards, workshop, and latrines. The arrangement of the wards appears to suit the ground, and I have no alteration to suggest regarding it; but the construction may be somewhat modified. One door for each ward is all that is required; it is inconvenient and objectionable to have more. The amount of ventilation given seems unnecessary. In addition to the ordinary doors and windows, and a ridge ventilator, it is proposed to have two windows in each gable, and five narrow windows near the top of the wall on each side. I would reduce the former to one in each gable, and the latter to three on each side. The night conveniences should be similar to those already introduced in the old Court-house wards, except that they should be open at one end, and that the bottom of the trough should be raised six or eight inches above the floor, so that the contents may be swept out into a basket or other receptacle. I annex a rough sketch of these troughs, and recommend their introduction into the wards of the new Jails, in preference to the Bangalore pattern, which is larger and intended both for faeces and urine; but, from what I have observed at Calicut and other Jails, I am in favor of separate urinals. These should be well tarred, and dry earth must be freely used; and, when this is done, either large earthen vessels or wooden tubs answer the purpose well. With regard to the materials of which the troughs should be made, stone is the best; but, at those places where stone is not to be had, bricks may be substituted without any evil effect, provided they are covered with mud to the thickness of several inches, and

plastered with cow-dung. Moreover, troughs made of such materials may be renewed by the convicts speedily and at a very trifling expense.

Workshop.—This should be built as shown in the plan.

Latrine.—I propose one general Latrine for the use of all male prisoners, debtors excepted. A building according to the standard plan, and 120 feet long, would accommodate 64 persons at one time. The outer enclosure should be formed by throwing out the Jail wall. The situation being public, palisades could not be used. The inner fence may be a low wall surmounted by rails similar to that in the centre of the Jail and to those by which it is proposed to separate the old from the new wards, and the latter from the Hospital, the eastern boundary wall of which is to be removed. A gateway, sufficiently wide to admit the passage of a cart, and fitted with a solid wooden door, should be made in the western end of the latrine enclosure. Two small doors will be required as entrances from the old and new Jails. It is immaterial whether they are made of wood or of iron grating.

Debtors.—The number of male debtors has varied very much. At the time of my inspection in November, there were 14 in confinement, but the average has been less than a third of that number. Female prisoners of this class at Bellary have been very rare. Two alternatives present themselves:—

(1). To give up the eastern verandah room of the old Court-house to the male debtors, making the present door a fixture, and providing a separate entrance in the eastern wall. A small cook-room and privy may be built in the south-eastern enclosure. When locked up they will be separate from the convicts, and when in the yard they will take care to keep themselves aloof. A small ward for female debtors, measuring 18×12 , may be built outside the compartment for females on the spot first proposed for a latrine.

(2). To erect a ward, measuring $32 \times 15 \times 15$, to contain 12 male debtors. This ward to be placed in an enclosure to be formed by throwing out the Jail wall on the eastern side; the yard to be separated from the rest of the Jail by a wall four feet high. The ward for female debtors to be provided as mentioned above. The second plan is, I think, the best, but the first is by far the least expensive.

5. If the proposal to enclose more ground, and to build new wards is approved of, that part of the work should be completed before the alterations in the old buildings are commenced.

6. On receipt of the Order first above quoted, I sent a copy thereof to the Superintendent, and requested him to furnish me with the data required in the 5th paragraph, but he replied that the records were so imperfect that he was unable to procure the information. I have now, however, obtained a statement of the average population for each month of the year 1865, and for six months of the present year, which I herewith enclose.

7. The plan to which I have alluded throughout is that furnished by Major Moberly, and the alterations suggested by me have been indicated thereon in red ink, but I herewith enclose a copy of the lithographed plan prepared in the office of the Sanitary Commissioner, which is clearer, as it only shows those buildings which it is intended to retain. The additional alterations now proposed have been entered in this plan also in red ink.

*Proceedings of the Madras Government, Judicial Department,
15th January 1868.*

STATEMENT showing the average number of all classes of prisoners in the District Jail at Bellary for each month of the year 1865, and from May to October 1867 inclusive.

From 1865, and from May to October 1867 inclusive.														
	Above one year.		One year and under.		Total.	Security.		Civil.	State.	Lunatic.		Under trial.		Grand Total.
	M.	F.	M.	F.		M.	F.			M.	F.	M.	F.	
1865.														
January.....	344	23	104	5	476	3	...	1	...	2	1	...	22	...
February.....	312	24	108	5	479	4	...	1	...	2	1	...	18	1
March.....	335	22	128	7	492	3	...	...	...	2	2	...	6	...
April.....	319	20	145	11	495	1	...	...	...	2	...	...	9	...
May.....	305	23	152	13	493	1	...	...	...	2	...	...	17	1
June.....	306	23	151	12	492	1	...	...	...	2	1	...	37	2
July.....	308	26	158	12	504	1	...	...	...	2	1	...	34	2
August...	310	29	157	16	512	2	...	2	...	2	2	...	15	...
September...	293	28	147	16	484	3	...	2	...	2	2	...	16	1
October...	268	27	134	16	445	3	...	6	...	2	...	...	11	1
November...	239	23	116	10	388	3	...	7	...	2	...	...	13	1
December...	224	23	121	12	380	3	...	8	...	3	...	...	21	1
1867.														
May.....	339	16	276	14	645	11	...	1	...	1	...	...	11	1
June.....	270	14	251	14	549	11	...	1	...	1	...	...	24	1
July.....	261	14	182	13	470	12	...	2	...	1	...	...	12	...
August...	253	15	127	12	407	11	...	2	...	1	...	...	4	1
September...	255	14	124	11	404	7	...	4	...	...	...	...	4	1
October.....	257	11	129	13	410	3	...	11	...	...	...	...	8	...
OFFICE OF THE Supt. OF JAIL PRISON														

OFFICE OF THE SUPT. OF JAIL, BELLARY,
30th November 1867.

(Signed) G. H. OAKES,
Superintendent of Jail.

No. 89. From Lieutenant Colonel W. J. WILSON, Inspector General of Jails, to the Chief Secretary to Government, Fort Saint George; dated Ootacamund, 19th December 1867, No. 145.

With reference to your Memorandum, No. 388, dated 11th instant, I have the honor to state that I prepared my report upon the Jail at Bellary with Major Moberly's plan before me, and was then informed that it was to be forwarded to Government immediately, together with the estimates. The usual course has been that, after the Superintending Engineer has sent his report, plans, and estimates to Government, they are referred to the Inspector General of Jails for remark; but, as I thought it would save such reference if I submitted my report at once, I did so. I have no plan of the Jail in its present state, and could not procure one for some time. I do not think there is anything in my report which cannot be understood from Major Moberly's plan, but, if so, I could supply the omission at once if the report were returned to me together with the plan.

No. 90. From the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department, Fort Saint George; dated Bellary, 17th December 1867, No. 2501.

With reference to G. O., No. 892, of 22nd March 1867, I have the honor to submit the plan and estimate, * &c., for improvements to the Jail at Bellary. The delay in the submission of this plan

* Rupees 16,050.

*Proceedings of the Madras Government, Judicial Department,
15th January 1868.*

and estimate has been caused by the carelessness and inattention of Mr. Claridge, the Supervisor in charge of the Bellary Range, whom I have had to severely reprimand, as he would not properly avail himself of my permission to prepare the plan and estimate in my office, with the assistance of my Draughtsman and Estimator.

2. The plan, &c., were received finally in my office on the 21st ultimo, and were detained in order that they might be shown to the Inspector General of Jails, who was at Bellary towards the end of November, and who has made some remarks in pencil on the plan. They were sent out to me in the end of November, but, from some mistake in the Post Office arrangements, did not reach me until my return to Bellary on the 14th instant.

3. Agreeably to G. O., No. 1173, of 16th April 1867, the cost of the Police guards has been included in the estimate.

Referred to the Judicial Department, with reference to the Order in that Department, dated 15th March 1867, No. 448.

Rupees 15,440 in all have been allotted for the proposed improvements to the Bellary Jail up to date, and provision to the extent of Rupees 20,000 has been made for the work in the outgoing Budget.

(Signed) C. A. ORR, Colonel, R. E.,
21st December 1867. Secretary to Government P. W. D.

No. 91. ORDER THEREON, 15th January 1868, No. 53.

In their Order, dated 15th March 1867, No. 448, the Government reviewed certain proposals made by the Inspector General of Jails and by the Sanitary Commissioner for the alteration and enlargement of the Jail at Bellary. There was some difference of opinion between the Sanitary Commissioner and the Inspector General of Jails; Colonel Wilson being of opinion that Mr. Ellis' proposals would entail so considerable an outlay of money that, if so large a number of prisoners as 452 were to be provided for at Bellary, it might be desirable to build an entirely new Jail on fresh ground. If the old Jail was to be retained, Colonel Wilson approved, with some slight modifications, of the proposal submitted to Government by the Sanitary Commissioner.

2. The Government, in their Order quoted above, required to be furnished with an estimate of the cost entailed by both the proposals, and further directed that more accurate data should be furnished for estimating the number of prisoners for which permanent accommodation would have to be provided in the District Jail at Bellary, on the understanding that all convicts from the Ceded Districts, whose sentences of imprisonment exceed one year are to be sent to the Central Jail at Vellore.

3. In the letter above recorded, the Inspector General of Jails submits the plans and estimates prepared in the Department of Public Works for providing accommodation for 450 prisoners at Bellary. Colonel Wilson states that, as a sum of Rupees 10,000 has already been expended in improving and altering the Jail at Bellary, he considers that his former proposal of building on fresh ground a new Jail should be abandoned, and that the plan proposed by the Sanitary Commissioner

should be adopted. The average number of long-sentenced prisoners in the Bellary Jail is shown by Colonel Wilson to be considerably in excess of the short-sentenced prisoners, and he does not consider that the Central Jail at Vellore, which receives prisoners whose sentences exceed one year from the Districts of North and South Arcot, Madras, and Nellore, would be able to accommodate the whole of the long-sentenced prisoners from the Bellary District.

4. Under these circumstances, it is proposed, by building additional wards, to increase the accommodation in the Bellary Jail, so as to provide for 450 prisoners of all classes, exclusive of debtors. To afford suitable sites for the new wards it will be necessary to enclose ground to the west and north of the present Jail at Bellary. Five new wards, each capable of containing 30 prisoners, will be required. The plan and estimates for these alterations and additions are now submitted by the Inspector General of Jails. The total estimated cost for providing accommodation for 450 prisoners is Rupees 61,048 12-0, and, deducting for convict labor and value of old materials, the estimate amounts to Rupees 52,860, of which Rupees 10,000 have been already expended.

5. Under the explanation afforded by the Inspector General of Jails of the number of prisoners of all classes requiring accommodation, and the insufficiency of the Central Jail at Vellore to meet the requirements of the Bellary District, the Government approve of the recommendations made by the Inspector General of Jails as shown in the plan which has been prepared in the Public Works Department, with the following modifications which are suggested by Colonel Wilson.

The old Court-house.—The alterations in this building have been completed, and, as suggested, the pillars of the verandahs will be raised when the tiles of the roof are renewed.

Guard-rooms.—The apertures made in the outer wall of the Jail against which these rooms are built, which might afford means of passing things in and out of the Jail, should, as suggested, be closed.

Solitary Cells.—Fixed wooden venetians reversed, and screwed on the outside of the present gratings, should be supplied, so as to prevent prisoners in these cells looking out into the Jail yard.

Old Jail.—The floors of the wards should be raised 8 or 10 inches, the walls being raised in the same proportion.

General Wards.—The palisading alluded to in connection with these wards, and which would involve a considerable expense, is unnecessary.

Compartment for Females.—The retention of one of the old solitary cells as a bathing place for the female prisoners, and the construction of a wall, instead of the 12 feet palisading abutting on the outer wall, are approved.

Hospital.—The dead-house will be erected on the site selected by Colonel Wilson. Two separate female wards, each to contain two women, will, as suggested, afford sufficient accommodation. The attention of the Department of Public Works is directed to Colonel Wilson's remarks as to the superficial area and cubical capacity prescribed for hospital wards in G. O., 8th October 1867, No. 1596, Judicial Department; the space indicated in the plan being in excess of what is necessary.

Granary.—Ventilation will be supplied by the addition of pot-ventilators to the roof of this building.

Workshed.—The width of this workshed will be reduced from 36 to 24 feet.

Cook-room.—This building, as shown in the plan, is too near to the workshed, and will be removed 50 feet from it in a westerly direction. The proportions for this building as detailed by Colonel Wilson are approved.

Outer Gate.—This entrance is shown to be unnecessarily wide, and a solid wooden door should be substituted for the proposed grating.

Palisades.—The *chevaux de frise* proposed should be added to the palisades when these abut on the outer wall.

Latrine for Women.—The site proposed and indicated on the lithographed plan will be substituted for that originally selected.

Dresser's Quarters.—A plan and estimate for these quarters, to be erected on the site selected, will be prepared in the Department of Public Works.

Drainage.—Complete surface drainage will be provided for the entire area of the Jail.

New Wards.—A single door will be sufficient in each of these wards, and the ventilation will be reduced as suggested by the Inspector General of Jails. The modification proposed in the night conveniences of the wards will also be adopted, and separate urinals will be provided according to the design which will be furnished by Colonel Wilson.

Latrine.—This will be constructed as proposed.

6. *Civil Debtors.*—It only remains to notice the question raised by Colonel Wilson as regards the accommodation to be provided for this class of prisoners, who have hitherto been confined in the Jail at Bellary with scarcely any separation from criminals.

7. The Inspector General of Jails proposes two alternatives: to give up the eastern verandah of the block described as the old Court-house to male debtors with a separate entrance in the eastern wall, and to build a small ward for female debtors outside the compartment for female prisoners, as shown at *N* in the lithographed plan; or to erect a ward, measuring 32×15×15, to contain male debtors, providing for the female debtors as above described.

The new ward for the male debtors would be placed as shown in the lithographed plan at *S* near the prison gate.

8. The Government are of opinion that the additions which are necessary at the Bellary Jail afford a proper opportunity for isolating civil prisoners, such as debtors, from criminal prisoners, as much as is possible with due economy of guarding. They resolve, therefore, to sanction the construction of the small Debtors' Jail as indicated in the lithographed plan at *S*, but they direct that a small ward, capable of containing three or four female debtors, be added in the manner indicated in pencil on the plan (*S a*) as an addition to, but separated from, the male debtors' ward.

9. Plans and estimates for these buildings will be prepared in the Department of Public Works with as little delay as possible. Should funds not be available in the Budget for the alterations and additions required for the Jail at Bellary, an

Proceedings of the Madras Government, Judicial Department,
15th January 1863.

application will be made to the Government of India for a special grant for this Jail, and for the Subsidiary Jails in certain Districts of this Presidency which have been recently sanctioned by the Government.

(True Extract).

P. W. M.

Chief Secretary.

To the Inspector General of Jails.
" Public Works Department, with six enclosures.
" Sanitary Commissioner.

Exd. J. H. Burns.

W. H. Burns

J. H. Burns
Superintendent of the

22nd March / 64
 No. 892.

1st W 1868 21st Jan
 Pro of Genl for January
 No. 246

No. of the Masses sent
 Judicial Dept

Of 15th { January / 60
 No 21st

3rd Placed to the 1st 30th
 No. 7. 3rd Placed to the 1st 30th

No. 274. 27 January / 65
 Papering orders on
 certain proposals submit-
 ted by the Inspector
 General of Sails for the
 alteration and enlarge-
 ment of the Sails at
 Bellary.

No 531

Statement Shewing the average number of all classes
 of Prisoners in the District Jail at Bellary for each
 Month of the year 1865. And from May to October
 1867 inclusive.

	alone one year			Security			Civil			State Lunatic			Under trial				
	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	1 year	Grand	Total
	be	&	be	&	Total	be	&	be	&	be	be	&	be	&	Grand	Total	
1865																	
January	344	23	104	5	476	3	1	2	1	22			505				
February	342	24	108	5	479	4	1	2	2	18	1		507				
March	335	22	128	7	492	3		2		6			503				
April	319	20	145	11	495	1		2		9			507				
May	305	23	152	13	493	1		2	1	17	1		515				
June	306	23	151	12	492	1		2	1	37	2		535				
July	308	26	158	12	504	1	2	2	2	34	2		547				
August	310	29	157	16	512	2	2	2	2	15			535				
Sept	293	28	147	16	484	3	2	2	2	16	1		510				
October	268	27	134	16	445	3	6	2		11	1		468				
Novem.	239	23	116	10	388	3	7	2		13	1		414				
Decem.	224	23	121	12	380	3	3	3		21	1		411				
1867																	
May	339	16	276	14	645	11	1	1		11	1		670				
June	270	14	251	14	549	11	1	1		24	1		587				
July	261	12	182	13	470	12	2	1		12			497				
August	253	15	127	12	407	11	2	1		4	1		426				
Sept	255	14	124	11	404	7	4			4	1		420				
October	257	11	129	13	410	3	11			8			432				

Office of the Super of Jail
 Bellary 30 November 1867

[Signature]
 Superintendent of the Jail

Redemptory

Remuneration

11 24 600

State is not allowed
to extract his share
from the 1000 in the
or rather taking the
the 1000 to the
the 1000 in the

General Abstract showing the amount of deductions for Convict Labour and Old materials and Cost of Police Guards for the additions gr. to the Jail at Bellary.

Quantities	Description of work	Actual Cost	Convict Labour
6 112.50	Square feet Dismantling Roof (tiled)	Per ft. 1 31 13 1/2	1 31 13 1/2
36 40.00	do do do	2 35 13 1/2	2 35 13 1/2
16 470.50	do do do (terraced)	4 41 29 1/2	4 41 29 1/2
32 00.00	do do do	4 6 10 8	4 6 10 8
9 24.00	Endive feet do Pump roof	3 14 7 1/2	3 14 7 1/2
9 1985.25	do do do Walls	3 53 38 1/2	3 53 38 1/2
29 948.50	Excavating Foundations	1 155 15 8	1 155 15 8
29 143.84	Grilling pavement	2 282 11 1/2	2 282 11 1/2
19 231.25	Spone in clay	1 14 35 15	1 14 35 15
125 505.62	Spone in Chinam	2 15688 32	2 15688 32
1537.00	Flat Arch work	2 226 24	2 226 24
109 419.33	Painting	1 8 1641 47	1 8 1641 47
1796.00	do do floor	1 17 15 1/2	1 17 15 1/2
18 230.45	do do Plastering	3 8 638 12	3 8 638 12
95 242.25	do do Whitewashing	2 6 148 13 9	2 6 148 13 9
10 287.45	do do Flooring with Granite slabs	9 925 16 1/2	9 925 16 1/2
1023.00	Running feet Coping with glass fragments	6 31 15 6	6 31 15 6
350.00	Running feet Cornice work	4 87 8	4 87 8
Total carried over to		21461 11 6	41338 5 17328-3-7

Quantities	Description of Work.	Actual Cost		Committed Salary		Balance.
		Spent	Spent	Spent	Spent	
Total Brought Over Pages						
2223.25	Square feet flagstone doors and windows	Per sq ft 4	555 13	4133 5	1728 37	555 13
4192.50	Roofing verandahs	Per sq ft 64	262 6	426 310	10 78	257 810
3552.00	Roofing with flat and flat tiles, chimney borders	Per sq ft 12	426 310	1 3	42 210	286 1
27809.50	Bengal stone	Per sq ft 14	1727 910	1 8	117 23	16310 77
8060.00	Verandah with bamboo mat, 3' jolly and 2 coats of plaster	Per sq ft 15	1206	1 8	120 97	1085 65
232.00	Verandah with bamboo mat, 3' jolly and 2 coats of plaster	Per sq ft 25	63	2 3	5 82	57 710
120.00	6 ft 6 inch prof	Per sq ft 4	30	1 2	8 12	21 4
4040.86	Spoke wood wrought and put up	Per sq ft 4	16163 59	1 2	8 12	21 4
52969.69	8' 39' wrought and put up	Per sq ft 3 41	6897 16	1 2	252 810	15910 12 11
39	Couples altered to quit proposed slopes	Each 1	29	2 1	245 11	6621 3 5
8	Doors 6' x 8' half pannelled, half paneled	Each 40	320	39	320	39
2	Doors 6' x 7' do do	Each 35	70	320	320	320
7	Doors 6' x 8' half pannelled shutters	Each 32	226	320	320	320
40	Doors 6' x 8' iron barred	Each 36	1660	320	320	320
9	Doors 6' x 7' do do	Each 31	283 8	320	320	320
1	Window 6' x 5' with glass shutters inside and outside	Each 50	50	320	320	320
8	Windows 6' x 5' half pannelled, half paneled with iron bars	Each 30	240	320	320	320
13	do do with battened shutters	Each 25	325	320	320	320
68	do do without frames	Each 20	1360	320	320	320
131	other windows 6' x 2' do do	Each 6 8	851 8	320	320	320
16	do do 6' x 2' with glass panes	Each 12	168	320	320	320
4	Gratings 6' x 2' iron barred	Each 10	40	320	320	320
1	Digging aperture and building a chimney	Each 4	4	320	320	320

Product on account of payments 57207 13 11
 Total for Detail Abstract 57207 10 11

Sundries at 5% Cont		2362 6 8	2362 6 8
Total Estimate Rs		60070	5266 5 11
Recoveries from old materials			51941 47
91985.6 ft stone from dismantled walls			5266 5 11
Other old materials such as old beams, roofs, doors etc.			5266 5 11
12 months cost of Police Quarters 50 Comicks		at per month 49 8	594
12 do do 25 Comicks		do 32 1	386 12
Total			61048 12
Total			8188 12
Total			52860

Billary Range Office No 2.
 11th August 1907
 11th August 1907

Supervisor D. P. W.
 Billary Range

Civil

Abstract Estimate
Bellary District - Bellary

New Work

Work & Additions and Alterations to the Jail at Bellary
vide G. O. No. 2644 dated the 22nd August 1866.

Quantities.	Description of Work.	Rate.	Amount.	Amount of each Part.
-------------	----------------------	-------	---------	----------------------

Additions and Alterations to the Old
Court House vide Para III of the Sanitary
Commissioner's Report.

1270.	00. Sq. ft. Dismantling Tiled Roof in the Western end of the Old Court House per Sq. ft.	1	6	9 10
5489.	25. Left. Dismantling Walls per 27. Left.	3	3	2 10
651.	25. Rebuilding D. Stone in Chimney per Sq. ft.	2	81	6 6
1283.	25. Sq. ft. Plastering with 2 Coats per Sq. ft.	3	8	4 14 7
9286.	78. lbs. Iron Work per hundred	3	4	1 12 09 3 5
24.	Left. Teak wood for Trusses per Left.	4		9 6
2042.	50. Sq. ft. Dismantling Tiled Verandah per Sq. ft.	1	10	10 2
426.	24. Left. Teak wood to Verandah per Left.	4		17 0 15 1
4192.	50. Sq. ft. Re-roofing Verandah with 1/2 inch pol. tiles per Sq. ft.	6	4	2 62 6
55.	Run 2 feet Cornice and filling Rafter holes per Rft.	1	13	12
640.	50. Sq. ft. Flooring with Granite Slabs per Sq. ft.	9		57 10 3
12345.	00. White washing (2 Coats) per Sq. ft.	2	6	19 4 7 35 09 10

Dismantling Work Shed and Wall
Connecting the Store Room to the Old Court
House and the Male Hospital vide Para IV.

9678.	00. Left. Dismantling Walls per Left.	3	5	9 7
3200.	00. Left. Dismantling Terrace per 10 Sq. ft.	4	6	10 8 12 4 3

Carried Over 3521 1/3

General Abstract
showing the amount of
Expenditure for
Carpet, Scur and Old Material
and Cost of Police Guards
for the additions to the
Jail at Bellary.

123 24 00
123 24 00
123 24 00

Quantities.	Description of Work.	Rate.	Amount.	Amount of each Part.
-------------	----------------------	-------	---------	----------------------

Brought Over _____ 3521. 14 3

Removing the Cells to the West ward
of the Male Hospital except 6 and
adapting that for a Cook Room.

Nickel Parado V and XI

975.	00.	Sq. ft. Dismantling Terrace — per Sq. ft.	4	2	7	
924.	00.	Left — D ^o Bomb Roof — per Sq. ft.	3	14	7	
13071.	75.	— " — D ^o — Walls — per Sq. ft.	3	7	9	
70.	0.	— " — Stone in Chumaw to Live place — per Sq. ft.	2	8	12	
		Digging Apertures and building Chimney etc.	4	4		37 3
		Altering the Slope of the State Hospital				
		providing Ridge Ventilators vide Para V to X.				
3440.	00.	Sq. ft. Dismantling Tile Roof — per Sq. ft.	2	35	13 1/2	
1994.	00.	Left Stone in Chumaw Raising walls. per Sq. ft.	2	24	9 4	
39.		Couples with 2 Sollar pieces provided to				
		cut the altered Slope of Roof — each	1	39		
56.	87.	Left Teak wood for Ventilator — per Sq. ft.	4	22	7 8	
3360.	00.	Sq. ft. Bengal Terrace — per Sq. ft.	17	57	1 3 2	
2131.	00.	— " — Plastering with 2 Coats — per Sq. ft.	3	8	74 9 4	
751.	50.	— " — Pointing walls — " —	1	8	11 4 4	
7770.	25.	— " — White washing 2 Coats — " —	2	6	12 2 3	
1796.	00.	— " — Pointing Floors — " —	1	17	15 4	
		Window 4 x 5 to Surgery, glass shutters				
		inside and Outside Pannell'd each		50		
		including Dismantling wall to fixing above				
28.		Left Rebuilding Sides Stone in Chumaw — per Sq. ft.	2	3	8	
50.		Sq. ft. Plastering (2 Coats) — per Sq. ft.	3	8	1 12	1293 15 5

Removing present Look Room and
Dead House vide Parto XI.

267 75. Sgriff. Dismantling Terrace — 10.8
894 00. Left. Di. Walls. — 8.3

Carried Over _____ 4854 3/4

<i>Quantities.</i>	<i>Description of Goods.</i>	<i>Rate.</i>	<i>No. Amount.</i>	<i>Amount. per Cent.</i>

Brought Over _____ 4854 3 7/8

Constructing Hospital for Female
Prisoners with Extracting and Parad XII

1390.	00.	Best Excavating Foundation—per Cft.	1	9	13	6
5821.	50.	— " — Stone in Churns — " —	2	7	27	11
144.	—	— " — Lumber in Churns — " —	2	4	21	—
45.	—	— " — Lumber in Churns — " —	4	—	11	4
216.	14.	Best Kato wood — per Cft.	4	—	8	64
2305.	00.	Longest Banga & Churned — per Cft.	17	—	39	13
3754.	00.	— " — Plastering 2 Coats — " —	3	8	13	6
940.	00.	— " — Painting — " —	1	8	14	1
4694.	00.	— " — Whitewashing 2 Coats — " —	2	6	7	5
1447.	00.	— " — Flooring with Granite Chalks — " —	9	—	13	3
4.	—	Don't / Cemented 2 1/2" Ventilation 4x8 each	40	—	1	60
8.	—	— " — 2 1/2" x 1/2" Show bars 4x5 — " —	30	—	2	40
2212.	—	Best Filling Basement 6 — per Cft.	2	23	—	8

Pring

337.	50.	Cost.	Excavating Foundations—per ft.	1.	12.	
1066.	50.	—	Stone in Mud.	14.	88.	14.
44.	00.	Amount.	Coaling Nails—per 100 lbs.	6.	1.	6.
616.	00.	Cost.	Coaling Nails—per 100 lbs.	8.	9.	3 10
			Palisading			
2114.	00.	Cost.	Stone in Churnam—per ft.	2.	26.	4
1481.	00.	Cost.	Coaling—per 100 lbs.	8.	22.	3 5
8595.	10.	lbs.	Spruce wood—per 1000 lbs.	3	4	1 119. 3 1.
762.	00.	Cost.	Excavation—per ft.	1.	3.	15 6. 4243 24
						138

Constructing New Grounds for Lunatics. vide Part XII

1020.	00.	Ceiling Diamonding Walls.	per Sq. Ft.	3	9	5	✓
1140.	00.	Excavating Foundation.	per Sq. Ft.	1	5	15	✓
3963.	03.	Stone in Chimney		2	49	8	6
62.	00.	Sq. ft. Plaster over Doors and Windows	per Sq. Ft.	4	15	8	✓
87.	99.	Ceiling Oak Wood	per Sq. Ft.	4	35	15	4
1197.	00.	Sq. ft. Bengal Teraco	per Sq. Ft.	17	203	7	10
2184.	00.	Plastering 2 Coats		3	8	76	7

Carried Over

1149. 47. 9097 511

Quantities	Description of Work	Rate	Amount	each	Part
1057.00	Sq. ft. Pointing	Brought Over	1149.47	9097.51	
32.00	Rough Pl. Larnico at Gables	per Sq. ft.	1.8	15.13	8
3241.00	Sq. ft. White washing	per Sq. ft.	4	8	
3	Doors with Battens and Shutters 4x8 each	per Sq. ft.	2.6	5.1	
3	Windows sash Barred with Shutters 4x5	per Sq. ft.	32	96	
495.00	Sq. ft. Flooring with Granite	per Sq. ft.	25	75	
752.50	Sq. ft. Filling Basements	per Sq. ft.	9	44.89	
			2	7.13	5.1401.95

Constructing 2 Wards for Contagious Cases
Vide Para XII

576.00	Sq. ft. Dismantling Walls	per Sq. ft.	3	5.41	
828.75	Excavating Foundations	per Sq. ft.	1	4.5	
2788.25	Stone in Chumam	per Sq. ft.	2	318.86	
36.00	Sq. ft. Flags for lintels and sills	per Sq. ft.	4	9	
61.89	Sq. ft. Seal wood	per Sq. ft.	14	247.811	
832.50	Sq. ft. Bangab Terrace	per Sq. ft.	17	141.84	
1478.50	Plastering 2 Coats	per Sq. ft.	3.8	51.11	
878.50	Pointing	per Sq. ft.	1.8	13.210	
32	Rough Pl. Larnico at Gables	per Sq. ft.	4	8	
2	Doors Battens and Shutters 4x8 each	per Sq. ft.	32	64	
2	Windows sash Barred with Shutters 4x5	per Sq. ft.	25	50	
333	Sq. ft. Flooring with Granite	per Sq. ft.	9	29.156	
481.75	Sq. ft. Filling Basements	per Sq. ft.	2	5.3	973.27

Constructing 2 Wards for Lepen Cases vide Para XII
As per 2 Wards for Contagious Cases

4101.75	Sq. ft. Dismantling Walls	per Sq. ft.	3	2.511	
142.50	Excavating Foundations	per Sq. ft.	1	11.10	
351.00	Stone in Chumam	per Sq. ft.	2	43.14	
276.00	Sq. ft. Pointing	per Sq. ft.	1.8	4.22	
3547.12	Stone work	per Sq. ft.	3.41	461.1310	512.159
	Enclosing some of the Waste ground lying to the West of the Jail vide Para XIII and XIV				
5400.00	Sq. ft. Excavating Foundations	per Sq. ft.	1	28.2	
23971.50	Stone in Chumam	per Sq. ft.	2	2996.7	
599.00	Rough Pl. Larnico at Gables	per Sq. ft.	6	18.11.6	

Carried Over 3043 4 6 12958 4 3

Quantities	Description of Work	Rate	Amount	each	Part
16500.00	Sq. ft. Pointing Walls	Brought Over	3043.46	12958.43	
	Dismantling Boundary Walls between the Hospital and Enclosing Palisade separating the Hospital from the two Wards vide Para XIV		217.8	3290.12.6	
4549.00	Sq. ft. Dismantling Walls	per Sq. ft.	3	2.10.1	
2745.00	Excavating Foundations	per Sq. ft.	1	14.49	
4042.75	Stone in Chumam	per Sq. ft.	2	555.56	
3750.00	Sq. ft. Pointing	per Sq. ft.	1.8	56.4	
9643.81	Stone work	per Sq. ft.	3.41	1255.11.3	1834.37

Dismantling one of the existing shed building over light to roof over the remaining half and erecting a new shed on site of the dismantled portion vide Para XV and XVI

2629.00	Sq. ft. Dismantling tiled Roof	per Sq. ft.	1	13.11.1	
330.75	Sq. ft. Dismantling Walls	per Sq. ft.	3	3	
204.75	Stone in Chumam	per Sq. ft.	2	25.96	
112.25	Seal wood	per Sq. ft.	4	449.1.11	
1736.00	Sq. ft. Bangab Terrace	per Sq. ft.	17	295.1.11	
728.00	Pointing	per Sq. ft.	1.8	10.14.8	794.10.1
1856.25	Excavating Foundations	per Sq. ft.	1	9.10.8	
3332.25	Stone in Chumam	per Sq. ft.	2	416.8.6	
356.41	Seal wood	per Sq. ft.	4	1425.10.2	
4100.00	Sq. ft. Bangab Terrace	per Sq. ft.	17	697	
2952.00	Pointing Pillars	per Sq. ft.	1.8	44.4.5	2593.19

Dismantling Boundary Walls between the old Jail and the other Blocks vide Para XVII

8889.50	Sq. ft. Dismantling Walls	per Sq. ft.	3	5.2.3	
607.50	Sq. ft. Terrace	per Sq. ft.	4	1.8.3	
380.25	Stone in Chumam	per Sq. ft.	2	47.8.6	
14338.89	Stone work	per Sq. ft.	3.41	1567.8	
1008.00	Sq. ft. Pointing to Pillars	per Sq. ft.	1.8	15.1.11	

Carried Over 23407 5 9

Quantities	Description of Work.	Rate.	Amount.	Amount of each Part.	Quantities	Description of Work.	Rate.	Amount.	Amount of each Part.
Brought Over					Brought Over				
23407 59					28176 14 4				
Removing Cells on the northern face of the Quadrangle Block V raising the Walls of the Eastern and Western Halls to 18 feet providing Ventilation by attics and re. Roofing the same and adapting the 2 nd Halls facing north for Juveniles Vide Paras XIX and XX.					Dismantling Roof and Partition Walls of the Block VI Raising Halls to 18 feet re. Roofing and providing Attic Ventilation Vide Para XXII				
8328.	00. Sqrft. Dismantling Terrace—per Sqr.	4	20	131	2244.	00. Sqrft. Dismantling Terrace—per Sqr.	4	5	99
11120.	00. Sqrft. 8" Walls—per Sqr.	3	6	7	2808.	00. Sqrft. 8" Walls—per Sqr.	3	1	10
780.	00. Excavation—per Sqr.	1	4	1	4360.	00. Stone in Chimney—per Sqr.	2	545	
19544.	00. Stone in Chimney—per Sqr.	2	2443		1410.	00. Sqrft. Terracing with Bamboo Mats			
21228.	00. Sqrft. Pointing—per Sqr.	18	318	68	Brushwood 3" Jilly & 2 Coats Plaster—per Sqr. 15				
21228.	00. White washing—per Sqr.	26	33	28	4562.	00. Sqrft. Pointing—per Sqr.	18	68	610
14.	Iron Barred Doors 4x8—each.	36	504		4562.	00. White washing 2 Coats—per Sqr.	26	7	2
9.	8" Windows 4x5—per Sqr.	20	180		6.	Iron Barred Doors 4x8—each.	36	216	
32.	Attic Windows 4x2—per Sqr.	68	208		2.	8" Windows without frames—per Sqr.	20	40	
666.	Sqrft. Slabs for Lintels—per Sqrft.	4	166	8	10.	8" Attic Windows Complete 4x8—per Sqr.	68	65	
21.	66. Sqrft. Teak wood—per Sqrft.	4	86	102	216.	Sqrft. Granite Slabs for Lintels—per Sqrft.	4	54	1214 47
5250.	00. Sqrft. Terracing with Bamboo Mats				Dismantling Roof and Partition Walls Raising the Halls to 18 feet and re. Roofing Substituting barred opening for present windows, and surrounding the building by building on South wall, West, and East and erecting a Verandah at the East end of the Women's Halls for Work Shed.				
Brush wood 3 inches jilly and 2 Coats of Plaster—per Sqr. 15					Vide Paras XXIII, XXIV, & XXV				
7878					1700.	00. Sqrft. Dismantling Terrace (Roof)—per Sqr.	4	4	4
4758 87					1120.	00. Sqrft. 8" Walls—per Sqr.	3	10	8
Dismantling the 2 cells between the Quadrangle and the Boundary Walls (North) Vide Para XXI.					5100.	00. Sqrft. 8" Walls—per Sqr.	2	637	8
1963.	50. Sqrft. Dismantling Terrace—per Sqr.	4	4	146	80.	00. Stone in Chimney—per Sqr.	4	320	
10532.	50. Sqrft. 8" Walls—per Sqr.	3	6	16	1380.	00. Teak wood—per Sqr.			
11					Sqrft. Terracing with Bamboo Mats Brush wood 3" Jilly & 2 Coats of Plaster—per Sqr. 15				
Carried Over					6.	Iron Barred Doors with frames complete	318	189	
28176 14 4					7.	4x7 Windows without frames—per Sqr.	20	140	
					Carried Over.				
					1498 6 8 29391 2 11				

Quantities	Description of Work	Rate	Amount	Amount of each Part
	Brought Over		1498	6 8 29.
16.	Attic Windows	each	6 8	104
192. 00	Sq. ft. Granite Slabs for lintels	per Sq. ft.	4	48
367. 50	Excavating Foundations	per Cft.	1	14 7
630. 50	Stone in Chimney	"	2	78 13
39. 90	Teak wood	"	4	159 9 7
476. 00	Sq. ft. Banga Terrace to Veranda	per Sq. ft.	17	80 14 8
4700. 00	Painting to Walls and Veranda Pillars	"	1 8	70 8
8652. 00	White washing	"	2 6	13 8 3
3153. 00	Cft. Dismantling Walls	per Cft.	3	1 13 2
171. 00	Sq. ft. D. Tile Roof	per Sq. ft.	1	14 3
150. 00	Excavating Foundation	per Cft.	1	12 6
423. 00	Stone in Chimney to Palisading	"	2	52 14
450. 00	D. D.	"	2	56 4
1109. 00	Sq. ft. Painting	per Sq. ft.	1 8	16 10
1280. 14	Iron work	per man	3 4 1	166 10 11
384. 75	Sq. ft. Dismantling Terrace Roof	per Sq. ft.	4	15 4
3828. 75	Cft. D. Walls	per Cft.	3	2 3 5
	<u>Lathings for Internal Prisoners</u>			<u>2354 12 4</u>

Vide Para XXXVI.

532. 50	Cft. Excavating Foundations	per Cft.	1	2 12 4
1864. 25	Stone in Chimney	"	2	233 6
15. 00	Sq. ft. Granite Slabs Over Openings	per Sq. ft.	4	3 12
1424. 00	Sq. ft. Painting	per Sq. ft.	1 8	21 5 11
70.	Cft. Coping with glass fragments	per Cft.	6	2 3
				<u>263 1 9</u>

Dismantling the Present Latrine and Constructing One in Line on the site proposed

Vide Para XXXVII.

10247. 00	Cft. Dismantling Walls	per Cft.	3	5 14 8
2772. 00	Excavating Foundations	per Cft.	1	14 7
11757. 00	Stone in Chimney	"	2	1469 10
7440. 00	Sq. ft. Painting Walls	per Sq. ft.	1 8	111 9 7
310.	Cft. Coping	per Cft.	6	9 11
10472. 00	Cft. Filling Basements	per Cft.	2	109 1 4
7440. 00	Sq. ft. White washing	per Sq. ft.	2 6	11 10
				<u>1731 15 7</u>

Carried Over 33741 0 7.

Quantities	Description of Work	Rate	Amount	Amount of each Part
	Brought Over			33741 0 7.
	Constructing 52 Nos. Walls 5'3" x 18' x 18'			
	<u>Vide Para XXXVII.</u>			
1110. 00	Excavating Foundations	per Cft.	1	5 12 6
5059. 75	Stone in Chimney	"	2	632 7 6
297. 18	Teak wood	"	4	1188 11 6
1908. 00	Sq. ft. Banga Terrace	per Sq. ft.	17	324 5 9
5068. 00	Painting	"	1 8	76 3
5068. 00	White washing 2 Gate	"	2 6	7 14 8
189. 00	Cft. Flat Arch work	per Cft.	2 4	27 9
4.	Doors Iron Bars 4' x 8'	each	36	144
10.	Windows D. 4' x 5'	"	20	200
14.	Attic Windows 4' x 2'	"	6 8	91
168.	Sq. ft. Granite Slabs over Opening	per Sq. ft.	4	42
954.	Sq. ft. Flooring with Granite slabs	per Sq. ft.	9	85 13 9
1670.	Cft. Earth filling Basements	per Cft.	2	17 6 4
				<u>2843 1 3</u>

Ditto for 4. Other Walls Pickets
Constructing Police Yard Gates at the Entrance of the Jail Vide Para XXX.

2199. 00	Cft. Excavating Foundations	per Cft.	1	11 7 3
8811. 50	Stone in chimney	"	1 4	734 4 8
1149. 25	Stone in Chimney	"	2	143 10 6
448. 00	Flat Arch work	"	2 4	65 5 4
120.	Cft. Carried Work	per Cft.	4	30
462. 47	Teak wood	per Cft.	4	1849 14
3552. 00	Cft. Coping with flat and Pickets and Chimney Border	per Sq. ft.	12	426 3 10
4599. 00	Plastering 2 Gats	"	3 8	160 15 5
3711. 00	Painting Walls	"	1 8	55 10 7
1670. 00	Flooring with Granite Slabs	"	9	150 4 9
130. 25	Slabs to Basements & Pillars	per Sq. ft.	4	32 9
4.	Doors 1/2 Panmiller and 1/2 Functions with frames 4' x 8'	each	40	160
4.	Windows D. 4' x 5'	"	25	100

Carried Over 39205 4 47956 6 10

Quantities.	Description of Work.	Rate.	Amount.	Amount of each Part.
-------------	----------------------	-------	---------	----------------------

Brought Over 3920 5 4 47956 6 10

4.	Iron Barred Gratings 4x2	each 10	40	
12.	Attic Windows with glass panes 4x2	12	144	
3228.00.	Left Filling Basements	per cft. 2	33 10	4137 15 4

Constructing a Jail Office and Condemned Cells Vice Para XXX

3062.25.	Left Stone in mud	per cft.	1 4 255 3	
412.00.	Stone in Chumam	"	2 " 51 8	
34.	Left Larnico Work at Gable	per cft.	4 " 8 8	
30.	Sqft. Slabs to Pillars Heads	Sqft.	4 " 7 8	
249.70.	Left Teak wood	per cft.	4 " 998 12 9	
940.50.	Sqft. Bengal Terracing	per sq. 17	" 159 14 1	
2.	Doors 1/2 Pan. 1/2 Windows 4x7	each 35	" 70	
2.	Windows 2x4x5	" 25	" 50	
2.	Attic Windows Glazed 4x2	" 12	" 24	
507.00.	Sqft. Flooring	per sq. 9	" 45 10	
1272.50.	Plastering	" 3 8	" 44 8 7	
1354.50.	Pointing	" 1 8	" 20 5	
993.75.	Left Excavation	per cft.	" 1 5 2 9	
725.37.	Filling Basements	" 2	" 7 8 10 1748 9	
2508.00.	Stone in mud	" 1 4	" 209	
192.00.	Stone in Chumam	" 2	" 24	
3.	Doors Iron Barred with Frames 4x7 each	31 8	" 94 8	
3.	Attic Windows with Iron Barred 4x2	6 8	" 19 8	
285.60.	Left Teak wood	per cft.	41 " 114 6 5	
252.00.	Sqft. Terracing with Brick on edge 3" jilly	per sq. 25	" 63	
2540.25.	Sqft. Pointing with Chumam	per sq. 1 8	" 38 17	
630.00.	Left Excavating Foundation	per cft.	" 1 3 4 6	
441.00.	Filling Basements	" 2	" 4 9 6 570 6	

Constructing Work Shed on the site of the Latrine for New Wards and putting up Palisading Vice Para 14 of Colonel Wilson's Letter of 12/4.

1316.50.	Left Stone in Chumam	per cft.	2 " 164 9	
1587.00.	Sqft. Pointing	per sq. 1 8	" 23 12 10	
Carried Over			188 5 10 54413 5 2	

Quantities.	Description of Work.	Rate.	Amount.	Amount of each Part.
-------------	----------------------	-------	---------	----------------------

Brought Over 188 5 10 54413 5 2

6277.55.	Left Iron Work	per hand 3	41 817 6 2	
268.90.	Left Iron Work	per cft. 4	" 1075 9 7	
2490.00.	Sqft. Terracing Bengal	per sq. 17	" 423 4 9	
131.60.	Left Stone in Chumam	per cft.	" 2 16 7 2	
1116.00.	Sqft. Pointing	per sq. 1 8	" 16 11 10	
24.00.	Left Excavating Foundation	per cft.	" 1 2 2537 15 4	

Constructing a Tower at the West end of Jail.

1783.00.	Left Stone in mud	per cft.	" 1 4 148 9 4	
376.00.	Stone in Chumam	" 2	" 47	
120.00.	Bamboo Roof	" 4	" 30	
1491.08.	Sqft. Pointing	per sq. 1 8	" 22 5 10	
92.25.	Fllooring	" 9	" 8 4 10	
18.00.	Left Excavating Foundation	per cft.	" 1 16 256 5 6	

Structures at 5 per cft. 2862 6 57207 10

12	Months. Cost of Police Guards over 50 convicts	594	
12	do over 25 convicts	384 12	978 12
Total			61048 12

Recoveries from old materials

91985	Left Stone from dismantled walls etc - 57 6 ft	2393 14 1	
	Other old materials such as old beams, reused doors etc	528 8	
Convict Labour.		5206 5 11	8188 12
Amount of Convict Labour as per statement			

Balance Estimate Rupees 52860

Bellary Range Office No. 2
 Bellary Range
 Supervisors D.H.
 Bellary Range

Report to accompany the Estimate for Additions and alterations to the Jail at Bellary vide G.O. No 2646 dated 22nd August 1866.

(2) Amount of Estimate Rs (52860-0-0) comprising the following items:-

6112.50	Sqft Dismantling Roof (tiles) — @	1 Sft	31 13 4
3440.00	— — — — —	2	35 13 4
16670.50	— — — — — (terrace) —	4	41 2 9
3200.00	— — — — —	10 Sft	6 10 8
926.00	C. ft. — — — — —	3 Sft	14 7
9195.25	— — — — —	3 Sft	53 3 8
29918.50	— — — — —	1 Sft	155 15 8
27143.87	— — — — —	2	282 11 11
17231.25	— — — — —	14	1435 15
125505.62	— — — — —	2	15688 3 2
1537.00	— — — — —	24	224 2 4
109419.33	Sqft Pointing — — — — —	18	1641 4 7
1796.00	— — — — —	1	17 15 4
18230.45	— — — — —	38	638 1 2
95272.25	— — — — —	26	148 13 9
10287.75	— — — — —	9	925 14 4
1023.00	— — — — —	6 Sft	31 15 6
350.00	— — — — —	4	87 8
2223.25	Sqft. — — — — —	4	555 12
4192.50	— — — — —	64	262 6
3552.00	— — — — —	12	426 3 10
27009.50	— — — — —	17	4727 9 10
3040.00	— — — — —	15	1206
252.00	— — — — —	25	63
120.00	— — — — —	1	30
4040.86	— — — — —	400	264 16 13 5 9
39	— — — — —	1	39
8	— — — — —	40	320
2	— — — — —	35	70
7	— — — — —	32	224
10	— — — — —	36	1140
9	— — — — —	31.8	283 8
1	— — — — —	50	50
52969.69	the Iron wrought and put up — @	3 1/2	372 6897 1 6

Abstract Estimate.

Work additions and

alterations to the Jail at

Bellary vide G.O. No

dated the 22nd August 1866

A. J. S. 1867. 1/17

1867-68

175440/100

175440/100

8	Windows	4'x5' 1/2 Pan half ventilator with	30	each	240	..
13	Windows	4'x5' Iron framed with				
		lathwood shutters				
68	Windows	4'x5' do without frames	20		325	..
131	altic Windows	4'x2' do do	6	8	857	8
116	do do	4'x2' with glass panes	12		160	..
4	Gratings	4'x2' Iron framed	10		40	..
1	Digging aperture and building a chimney	4			4	..
Sundries @ 5% Cent						
Total Estimate Rupees						60070
12	Months Cost of Police Guards	one 50 Consts @ 49 1/2 3 mont.	594	..		
12	do do	over 25 Consts @ 32-1-0 3 mont.	386-12-0		978	12
Total						61048 12
Recoveries from Old Materials						
9185	6 ft Stone from dismantled walls	3000 - 5.76 ft.	2393-14-1			
	Other old materials, such as old beams,					
	peepers, doors &c.		528-8-0			
Convict Labour						
Amount of Convict Labour as per Statement						5266-5-11 2188 12
Balance Estimate Rupees						52860-0-0

(3) No 1. The Old Court House.

The western Verandah rooms are to be removed and 4 windows are to be opened out in the wall, thus exposed to admit ventilation; the outer walls in the north and south verandahs are to be pulled down and the spaces thus exposed are to be filled in with iron lathed frames; the roofing of the Verandahs are to be pulled down in consequence of the bad state of the wooden rafters and reconstructed; the estimate also provides for flooring this building with granite slabs.

No 2. Removing the Workshops. These buildings are badly open sheds; the roof of which is composed of mud and Chumam plastering; the rafters are composed of old Palmyrah and other decayed timber and is therefore irreparable; the high wall connecting the old Court House with the Hospital is also to be removed to secure a thorough inflation of air.

No 3. The bells westward of the old Hospital are to be dismantled in consequence of its impeding the ventilation of the hospital.

No 4. The roof of the hospital has to be pulled down in consequence of its having too great a slope; the tiles of which it is composed are constantly slipping and not being

can keep them in their places; thus there is a constant demand for repairs; the estimate provides for altering the slope to one fourth. The span and putting up a Bengal Terraced Roof.

No 5. The present Cook Room and Dead House are to be removed as they are not adapted for the purposes for which they are used.

No 6. Constructing a Hospital for female prisoners.

The building is to be raised on a basement of 2 feet in height above foundations which are to be sunk 3 ft; the principal walls are to be 15 ft high and the Verandah Pillars 8 feet.

The building is to contain 2 Rooms.

No 1 Room 26 1/2 x 15

No 2 Room 13 1/2 x 15

Surrounding entirely excepting at the northern and southern ends by open Verandah 8 feet broad; the roof is to have a pitch of one fourth. The span and is to be Bengal terraced.

The whole building is to be partitioned off by iron lathed plastering 9 ft high.

No 7. New Wards for Lunatics.

This building is to be raised on a basement 2 ft in height above foundations which are to be sunk 3 feet; the principal walls are to be 13 ft high and the Verandah pillars 8 feet; the building is to contain 3 Rooms each 11 feet by 9 feet; an open Verandah is to be put up on its Western face 6 feet broad.

No 8. Constructing 2 Wards for contagious cases.

The building is to be raised on a basement 2 ft in height above foundations which are to be sunk 3 feet; the principal walls are to be 13 ft high and the Verandah pillars 8 feet.

The building is to contain 2 Rooms each 11 x 9 feet and open Verandah is to be constructed on its western face 6 feet broad.

No 9. Constructing 2 Wards for Lepers and No 8.

No 10. The estimate also provides for enclosing more ground to contain the wards for Lunatics, Contagious

Cases and Seps together for the construction of 5 New Prison Rooms each $53' \times 18' \times 16'$

No 11. The wall on the Northern side of the hospital is to be dismantled and substituted by palisading to secure thorough inflation of air.

No 12. The present Cook shed is a low badly ventilated building; the Estimate provides for dismantling the roof, raising Pillars to 4 and 5 feet and putting on a Bengal Terraced Roof.

No 13. Constructing a New work shed. The pillars are to be raised on foundations which are to be sunk 3 feet; the Centre pillars are to be raised 14 feet in height and the side pillars to 8 feet covered over with a Bengal Terraced Roof.

No 14. The wall between the old Jail and the blocks No 1 to 4 is to be dismantled and substituted with palisading to insure more inflation of air.

No 15. The Estimate provides for removing the bells on the northern face, of the quadrangle formed by the old Jail, raising the walls of the remainder prisons to 10 feet and securing additional ventilation by substituting iron barred doors for the present battened doors putting up 9 new windows and 32 attic windows.

No 16. The two cells lying between the old Jail and Jail wall are to be dismantled as from their position, there is no means of ventilating them.

No 17. This Estimate provides for certain alterations to block No VI; that is removing the 2 Cells in the Eastern end, raising the roof to 10 feet and improving the ventilation of the block by substituting iron barred doors for battened doors, fixing 2 Iron barred windows and providing 10 attic windows.

No 18. Female prisons.

The Estimate provides for removing the partition walls raising roof to 10 feet, substituting 6 Iron barred door for battened ones, fixing 7 Iron barred windows and 16 attic windows.

No 19. Constructing an open Verandah on the Eastern end of Female prison to serve as a work shop 8 feet broad.

No 20. Constructing a Latrine for female prisoners. The walls are raised on a basement 2 feet in height above foundations which are sunk to 3 feet; the walls are to be raised to 8 feet in height and covered with a coping of glass fragments; a

Scum wall is also provided to prevent exposure, 5 ft high.

No 21. The present Latrine being situated on the windward side of some of the prisons, the Estimate provides for removing it and constructing a new one on the northern end. The walls to form the new Latrine is to be constructed 12 feet high on a basement of 2 feet; the foundations are sunk to 3 feet in depth; the walls are covered over with a coping of glass fragments.

No 22. Constructing 5 New Wards.

These buildings are raised on a basement 2 ft in height above foundations, which are to be sunk 3 feet. The principal walls are to be 10 feet high each to contain 1 room $53' \times 18'$. The roof is to be Bengal Terraced, provided with ridge Ventilation. Doors and windows and all openings are to be Iron barred.

No 23. Constructing Police Guard Rooms at the entrance of the Jail. These buildings are to be raised on a basement 2 feet in height above foundations, which are sunk 3 feet. The principal walls are to be 10 feet high and the Verandah Pillars 7 feet.

These buildings are to contain 3 Rooms.

One Room 36×18

Do 12×18

Do 16×18 .

An open Verandah is provided for the Eastern side 7 feet broad. The roofing is to be of flat and pot tiles and furnished with carriers provided with both haw and Ridge Ventilation.

No 24. Constructing a Jail Office and condemned Cells. The Jail Office is to be raised on a basement of 2 feet in height above foundations which are to be sunk 3 feet; the principal walls are to be raised 14 feet high and the Verandah Pillars 10 feet.

The building is to contain 2 Rooms, each measuring 12×12 with an open Verandah facing west $6\frac{1}{2}$ feet broad. The roof is to be Bengal Terraced provided with ridge ventilation. Condemned Cells are to be raised on a basement 2 feet in height above foundations which are to be sunk 3 feet; the walls are to be $12\frac{1}{2}$ feet high; the building is to contain 3 Cells each $12' \times 7'$. The roof is to be terraced with pitch on edge in Chumond style.

No 25. Constructing a Work Shed.

The pillars and pole raised on a basement 2 ft in height above foundations which are pole sunk 3 ft. the Centre pillars are pole raised to 13 ft and the side pillars 10 ft. covered over with Bengal terraced Roof.

No 26. Constructing a Tower for the use of the Police.

This building is raised on a foundation which is sunk to 3 ft in depth; the walls are pole raised to 14 1/2 ft high above which a masonry Sentry Box is pole constructed, the wall of which is pole raised 4 ft and covered over with Bomb roof. The tower is also provided with steps on the outside of the boundary wall of the Jail.

Samuel Masinde

Superintendent Charge
Bellary Range

Bellary Range Office No 2.

Camp Kenchengode. 21st October 1864

A. M. Masinde
Superintendent Charge

Public Works Department
 No 2747
 Proceedings of the Madras Government
 Under date the 27 January 1868
 Read the following

Pro. of the Madras Govt. } H.E. No 53 Dated 15th Jan 4/68
 Judicial Dept.

Communicated to the
 Superintending Engineer of
 the S. D., who is requested
 to submit a revised estimate
 for the improvements to the
 Jail at Bellary, prepared
 with reference to the modifi-
 cations sanctioned in the
 foregoing Proceedings.

Major Moberly will
 be careful to include the
 cost of Quarters for a Super,
 and to provide for the iso-
 lation of civil from
 criminal prisoners in

27/24/68
 Survey Dept. 1868/53

~~27/24/68~~

In fact no cost at all

Report to accompany
 the Estimate for
 alterations and
 additions to the Jail
 at Bellary No 53
 No 20416 dated 22nd
 August 1866—

the manner indicated in

P. W. 186 . Department.

Para 8. His attention will

No.

also be drawn to Pro. 16

of 18 October 1867,

PROCEEDINGS OF GOVERNMENT.

with regard to the extent

of accommodation to be

provided in the Jail Hospital.

Dated

Adverting to Para

9, it is observed that the ex-

penditure on the Jail up

to the 31 March last was

Rs. 5046, and that the allot-

ments for it during the

present & the ensuing official

years are Rs 10,916 & 20,000

respectively. The Super-

intending Engineer will

report what additional sum

he will be able to spend

on the work during each of

those years.

[Signature] x To The Just Dept.
3 Clause of the Bellay " 1 Engr 3rd Du
Jail sent to the " Controller
S. Ry 12/3/68. " Acct Genl
and memo. Dec 18/68

33/532
the
Pa
ad
with
of
p
9
p
to
a
3
1
A
5318 532

Pub. Works 1868 Septth

Pro. of Gov^t. for January

N^o 274

Pro. of the Madras Gov^t.

D^y 27th January 1868

Instructing the Sup^r Secy^r
of the D^y to submit a revised &
Estimate for carrying out the
improvements proposed by the
Inspector Gen^l of Sails to Sails
at Bellary.