

(1) Number of pages 141

(2) Date of repair 13/1/1868

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 331	Press
646-47	Mis.
Dated 30	1868.

Not to be folded or roughly handled

10

*Proceedings of the Madras Government, Public Works Department,
30th January 1868.*

No. 646. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Department Public Works, dated Virdachellam, 18th January 1868, No. 209:—

1 Plan.
1 Abstract Estimate.
1 Specification.

1. I have the honor to forward, for the sanction of Government, an estimate of Rupees 250, accompanied by plan and specification, for construct-

ing parapet walls and platform round the well, and also a cistern and two drains, for the troughs at the Karkhana Lines at Bangalore.

2. The plan and estimate have been approved by His Excellency the Commander-in-Chief.

No. 647. ORDER THEREON, 30th January 1868, No. 331.

MILITARY WORKS, No. 30.

The estimate of Rupees 250 submitted with this letter is approved, and the Superintending Engineer of the 5th

Division is authorized to proceed with the work if he can provide the requisite funds.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with one Specification.

„ Accountant General.
„ Controller of Public Works Accounts.
„ Military Department.

Exd. F. R. Bantleman.

Military

Bangalore

New works.

Abstract Estimate for 1867-68.

Work—Constructing parapet walls and platform around the well, also a cistern and 2 Drains for the trenches at the Karkhanah lines at Bangalore.

Quantity	Description of works	Rate	Per	Amount	Total
324	Cubic feet of Excavation	"	1 6 $\frac{1}{2}$	2	
324	— Do — of Foundation Stone in Chumam	"	2 6 Do	51	
373	— Do — of Superstructure Brick in Chumam	"	2 9 Do	64	
7 $\frac{82}{100}$	Squares of Plastering with Hydraulic Cement	3 8	" 1 $\frac{1}{2}$	27	
3 $\frac{87}{100}$	— Do — of Paving with cut Stone in Chumam	10	" Do	39	
135	Square feet of Flag Stone for bottom of Channel				
	4" thick	"	2 6 1 $\frac{1}{2}$	21	
111	Cubic feet of Dismantling	"	3 6 $\frac{1}{2}$	2	
55	Running feet of stone coping	"	8 " 1 $\frac{1}{2}$	28	
1	Bottom stone for Channel to the cistern 5 $\frac{1}{2}$ x 3 $\frac{1}{4}$ x $\frac{1}{2}$	2	" each	2	
1	Stone underneath the above 4 x 2 x $\frac{3}{4}$	1	" Do	1	
	Leveling the ground	"	" " "	2	
				239	
	Sundries at 5 pice cent			11	

Total Rupees 250

Rupees two hundred & fifty only.

For: Engrs Office Bangalore
28th November 1867

/s/ J. B. Mead Captain R.E.
Executive Engineer Bangalore

By Order

All And Subd. P.E.

No 331

The estimate of Rs 250 submitted with this letter is approved, and the Supy Engineer of the S.D. is authorized to proceed with the work if he can provide the requisite funds -

20 SE 5 Da with one spec
4- 1/8
4- Carterhead / Grant St. George
Miss Dept / 30 Jan 1868
Recd 31/1/68

Division of City

23. June 1891

12/22/88

Michael. Toronto

and the same, made with one
of the same, round and flat,

also a Northern and two Chinese

for the concentration of his mind

Wilmington, Delaware.

Amount of Balance \$ 250.00

