

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.**Government of Madras.***Public works* **DEPARTMENT.**

G.O. No. 3627	Press
393-74	Mis.
Dated 19-11-	1868.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department
19th November 1868.

No. 393. Read the following letter from the Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Dowlaishweram, 27th October 1868, No. 145 —

1. I have the honor to submit for sanction the accompanying estimate, amounting to Rupees 115, for providing shutters to two windows and a new beam in the roof of the Principal Sudder Ameen's Court at Vizagapatam.
2. The estimate has been countersigned by the Civil Judge of Vizagapatam, at whose request it was prepared by the Executive Engineer of the Vizagapatam Range.
3. In the event of the proposed being sanctioned for execution, the necessary funds can be appropriated from the current year's grant* for Minor New Works, Civil Buildings, Vizagapatam.

* Rupees 700—G O, No 3,950, of 20th December 1867, and No 2,392 of 27th July 1868

No. 394. ORDER THEREON, 19th November 1868, No. 3624.

CIVIL WORKS, No. 58.

Sanctioned.

(True Extract.)

Colonel, R. E.,

Secretary to Government.

To the Superintending Engineer, 1st Division.
" Controller of Public Works Accounts
" Accountant General.
" Judicial Department.

Exd. F. R. Bantleman.

Department Judicial. Chapter VIII, para 8. In Revenue
 No II of VIZAGAPATAM RANGE
 Detailed Estimate of the Probable expense of providing shutters to two windows &
 a new beam in the roof of the Principal Gudam Ameen's Court, Vizagapatam

Number	Measurements			Supl contents		Particulars of Work	Rate	Per Item	Amount.	Total.
	Length	Breadth	Height	Square	Feet					
1	5	5				Batten Teakwood shutters for windows with hinges & fastenings complete	19	Emb	38	✓
1	21	7 1/2	15			16.5 Cft of Teakwood beam roughed & put up	3 8	Cft	57 74	✓
						Taking down the old beam & putting up new one including scaffolding			12	✓
									107 74	✓
						Deduct probable value of old beam which is very much decayed			18	✓
									105 15 1/4	✓
						Contingencies	5	100	6	8 ✓
						Superintendence	2 8	50	3	✓
						Total Rupees			115	✓

Vizagapatam
 Band Comt
 12 October 1868
 Band Comt

Vizagapatam
 Ec. Engrs Office
 Thalbain
 25th September 1868

Accepted by the
 Executive Engineer
 Vizagapatam

H. R. C. S. S. S.
 S. S. S. S. S.

Superintending Engineer's Office
1st Division Cochin
27th October 1868

No 145

To
Captain J. G. Rogers R. E.
Superintending Engineer
1st Division

Colonel C. J. P. R. E.
Secretary to Government
D. P. Works
Madras

I have the honor to submit for sanction
the accompanying Estimate amounting to
Rs 115 for providing shutters to two windows
and a new beam in the roof of the Prison.
The Sanctioning Officer at Vizagapatnam.

The Estimate has been countersigned
by the Civil Judge of Vizagapatnam at whose
request it was prepared by the Executive
Engineer of the Vizagapatnam Range.

In the event of the proposed being sanctioned for execution the necessary funds can be
appropriated from the current year's grant for Prison
new works. Civil Buildings Vizagapatnam.

I have
Capt
Superintending Engineer

1. Estimate
2. Estimate
3. Report

* Rs 100
* Rs 103.50 of
23 December 1867
No 1392 of 27th
12.1868

10/4/288/160

Detailed Estimate
of the probable necessary
providing shutters to two
windows & a new beam
in the roof of the Prison
Civil Buildings
Cochin & Vizagapatnam

C. 9742-186802-16

No 3624. 19-10-03/88
with an order

Successor's work

Supervising Dept

Recd 20/10/88

CC

Govt. of 1868 ^{Ans 4288} Madras.

PUBLIC WORKS

To The Superintending Engineer
1st Division
do, do, do

Dated, th

1868

G O, 19th Nov 1868, No 3624

Nos. 393 & 394

Principal Sudder Ameen's Court
at Vizagapatnam. Estimate of
Rs 115 for providing shutters
to two windows and a new
beam on the roof of the Prin-
cipal Sudder Ameen's Court
at Vizagapatnam, Sanctioned.

Handwritten signature

Handwritten signature