M.R.O. 1—77,606—8-4-37.

(1) Number of pages.....

(2) Date of repair.....

(3) Initials of the Reformer.....

MADRAS RECORD OFFICE.

Government of Madras.

Public (Misc.) DEPARTMENT.

G.O. No. 2075 Press — Mis.

526-70-75

Dated 25 — 6 — 1869.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
25th June 1869.

Read the following letters :—

No. 576. From the Acting Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Dowlaishweram, 2nd June 1869, No. 921.

In lieu of the estimate returned with your Memorandum, No. ——, dated the 27th ultimo, I have the honour to forward a revised one for constructing a Dead-house at the Hospital at Chetterpore, amounting to Rupees 790.

1 Abstract Estimate.
1 Specification.
1 Letter.

No. 577. From the same Officer, dated Dowlaishweram, 3rd June 1869, No. 926.

In accordance with paragraph 2 of G. O., No. 1,698, of the 25th May 1869, I have the honour to forward the estimate* for constructing a Dead-house at the Civil Dispensary of Vizagapatam duly revised, and request that the sanction of Government may be obtained for the same with an appropriation of funds.

1 Abstract Estimate.
1 Specification.
* Rupees 1,107.

2. I beg to explain the eave ventilators can hardly affect the air in the space above them and immediately below the roof of the building, the heated air must then come down to get away, and, with people breathing in the room, is as likely to be inhaled by them as to escape by the ventilators; I proposed, therefore, to let this vitiated air have free egress, as I had found in many instances it greatly improved the quality of the air in any buildings with these pitched roofs.

No. 578. Order thereon, 25th June 1869, No. 2,075.

CIVIL WORKS, No. 86.

		Rs.
*1.	For a Dead-house at Chetterpore ...	790
2.	Do. do. at Vizagapatam	1,107

The Government approve of the estimates* submitted with these papers, but they are unable to allot any funds for the proposed buildings during the current official year.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 1st Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Judicial Department.

Exd. S. T. Augustin.

No 926 Superintending Engrs Office 1st Dr
Darlaiewaram 3d June 69

From Captain J. F. Fischer RE
Ag. Superintending Engr 1st D.

To Colonel C. A Orr RE
Secretary to Government P.W.D.
Madras

Sir, In accordance with para 2
of G.O. No 1698 of the 25th May 1869
I have the honor to forward the Estimate
for Rupees 1107 for constructing a Dead House at the
Civil Dispensary of Vizagapatam duly
revised, and request that the sanction
of Government may be obtained for
the same with an Appropriation of Funds
2 Beg to explain the cane ven-
tilators can hardly affect the air in
the space above them and immediately
below

Carried over

below the roof of the building the heated air must then come down & get away and as with people breathing in the room is as likely to be inhaled by them as to escape by the ventila-tors. I proposed therefore to let the vitiated air have free egress as it had formd in many instances it greatly improved the quality of the air in many buildings with these pitched roofs.

I have the honor to be

Sir

Your most Obt Servt

Wm H Richm Captain RE

A.E. Superintending Engineer

1st Division

DEPARTMENT Medical — CHAPTER XXIV PARA — New Work 73

ABSTRACT ESTIMATE

TALUQ Vizagapatam

DISTRICT VIZAGAPATAM

WORK. Constructing a Road house at the Civil Dispensary of Vizagapatam prepared in accordance with the Standard Plan sanctioned with G.O. No 2905 dated 19th March 1873.

Quantity or Number.	Discription of Work.	Rate.	Per Item.	Amount.	Total.
80 5/17	Cft. of Rubble Masonry in Chunam	1 12 -	Cft.	140 5 2	
4 1/3	Do of Arch work (brick) in Chunam	4 13 -	Do	20 13 8	
19 4/5	Sqr. of plastering & white washing with 2 Coats of Chunam	2 6 -	Sqr.	47 - 4	
2 4/25	Do of Flooring with Rubble 3/4 inch thick over a bed of jelly in Chunam & pickers thick	18 - -	Do	38 14 1	
28.163	Cft. of Cajan wood wrought and fixed	2 8 3	Cft.	70 13 6	
6 21/25	Sqrs. of Roofing with Cajan wood Couples, Rafters, Laths & pan tiles & Chunam borders & Coverings complete	34 4 -	Sqr.	234 4 3	
1	Pair of Cajan wood 4/5 panelled & Glazed doors with frames & iron fixtures Complete	50 - -	Each	50 - -	
3	Do windows with swinging glazed shutters, frames & iron fixtures &c Complete	35 - -	Do	105 - -	
8	Swinging Ventilators with glazed shutters, frames & iron fixtures &c Complete	24 - -	Do	192 - -	
	Carried Over			899 3 -	

Estimate Rs. 899-3-0

Approved

Superintending Engineer

Estimate Rs.

Under Secretary to Govt.

Public Works Department

Madras

Dated 30th April 1873.

No. 976

Superintending Engineer's Office

Vizagapatam 25th June 1873

Approved

Executive Engineer

Vizagapatam Div.

Dated 26th June 1873.

No. 1127

Dated 27th June 1873

Executive Engineer

Vizagapatam Div.

Brought Down 1098 3 -

Contingencies — 5% - Rs 69 13
Superintendence — 2 8 - Do 32 - -

Total Rs 1200 - -
Deduct the cost of furniture and Establishment as may will be employed by the Engineer Officer in charge of the Works 93 - -
Total Rs 1107

Excepting Engineer
Officer in charge
28th April 69.

Executive Engineer

Brought Down 899 3

Masonry Tank, with trough 9" inches deep, lined with lead & also a Cistern (1¼ ft diameter) outside for the supply of water through a pipe with stop Cock opening over the tank — 1 — 20 — Each 20 — —

1 Teakwood Shoemaker on descending table with a slight incline from the edge to the centre to have a hole in centre lined on top with lead — 70 — Do 70 — — X

1 — do — do — with ordinary Cane bottom — 25 — — Do 25 — —

1 — do — do — shelves for instruments &c — 10 — — Do 10 — —

— do — do — washing stand and towel stand — 15 — — Do 15 — —

1 Writing table & chairs — 20 — — Do 20 — —

Trestles for supporting Coffin — 10 — X

Wedges & blocks to steady the body — 6 — —

One Set of Tables & weights for ¼ in Mortar for proof & Teakwood pegs for Clothes — 10 — —

10 One do Bucket with iron straps — 2 — —

Excavating foundation and filling basement — 3 — — X

Carried Down 8 — —

10983 —

Exd DR

Executive Engineer
Postmaster Dun

Sch.g Engineers Office 1st Div.
No 630 Dated Chicacolum 15th May 1869

From Captain J. F. Fischer R.E.
Actng Exty Engineer 1st Div.

To Colonel C. A. Orr R.E.
Secretary to Government
P.W.D. Madras.

Sir,

In Continuation of my letter No 483 dated 6th instant I have the honor to forward for the sanction of Government an Estimate and Specification amounting to Rs: 800 for constructing a Dead House at the Police Hospital at Chittivoor prepared in accordance with the standard Plan circulated with G.O. No 905 dated the 19th March 1869 and request that the requisite funds may be granted from the Reserve of the Current Year with a view to the work being carried out at an early date.

I have the honor to be
Sir,
Your most obdt Servant

Wm. H. Fischer Capt. R.E.
A.F. Schg Engrs 1st Division.

Enclosure as
letter No 483 dtd 6/5/69
Dead House
Schg Engrs Office
Chicacolum
15th May 1869
Capt. Fischer
Actg Exty Engrs
1st Division
Ganjam
Rec'd 24/5/69

3 Gr. Stand. Slope all round the buildings 8 - 0 Cy 1 0 0 / 1765 7 6

Asst. Engineer's Office, 2nd Div.
No 921 Dalhousie, 2nd June 1869.

From

Captain A. T. Fraser R.E.
Actg. Chief Engineer & Sec.

To

Colonel Civil Dept.
Secretary to Government
of India.

Sir,

I have the honor to forward Estimate & Plan—dated the 26th May 1869, for a Dead House at the Lunatic Asylum, Dhurmsala, with a Mortuary & Dissecting room attached, at the Hospital at Chittagong, to accommodate 24 Patients.

I have the honor to be,
Sir,
Your most obdt. Servant
Lieut. R.E.
Asst. Engr. & Secy. to Committee.

P.P. 1869 Vol. 52 630

From No 2157

The Secretary to Government of India

To

The Secretary to Government of Madras

Dated 15 May 9
Read 17 do
Received 25 — 3 Enclosures

P.C. 24/5/69.

Forwarded and returned for communication to Rs 500 for constructing a Dead House at the Hospital at Chittagong for sanction.

NEW WORK.

DEPARTMENT Imperial

ABSTRACT ESTIMATE No.

TALUQ Berhampoor

DISTRICT Ganjam

WORK. County a Road Bungalow at Police Hospital at Chatterpoor prepared in accordance with the Standard Plan received with G.O. No 905 dated 19th March 1872 -

Quantity or Number.	Description of Work.	Rate.	per Item.	Amount.	Total.
		Rs. A. P.		Rs. A. P.	Rs. A. P.
22 5/8	Cgr Rockstone in chunam	1 13 -	Cft	41 6 2	
44 9/27	Do Brick in chunam	2 12 -	Do	121 13 -	
1 1/27	Do Cuttack work for steps	7 - -	Do	7 4 2	
4 5/8	Do Arch work in Chunam	3 8 -	Do	15 2 8	
19 5/8	Sqr Masoning & white washing with 2 coats chunam	1 12 -	Sqr	35 2 5	
2 4/27	Do Flooring with Asphalt 3/4" thick over stone jelly in chunam 6 thick	18 - -	Cft	38 14 1	
28.163	Cft Sawed wrought & pentup-	2 12 -	Cft	77 7 2	
7 46/100	Sqr Roofing with Couple Rafters,	-		128 3/4 11 4	
6 21/24	purlins, hearts, flat & pantiles, Chunam	18 - -	Sqr		
	hoodes & Iron hooks & five cummers				
	at end of Eaves for Complete				
1	Pair of Teakwood 4/5 panelled & 1/5	50 - -	Each	50 - -	
	glazed door with frames & iron fixtures				
	for complete 5×8				
3	Do Windows with Louvre glazed	30 - -	Do	90 - -	
	shutters weather boards, frames,				
	iron fixtures for Complete 5×3 -				
8	Louvre Ventilators with Glazed	8 - -	Do	64 - -	
	shutters, frames & iron fixtures for				
	Complete 2½×1½				
1	Masonry sink with trough 9" deep	" - -	-	20 - -	
	lined with lead & also a Cistern				
	(1½ ft diameter) out side for the				
	supply of water through a pipe with				
	stop Cock opening over the sink -				
1	Teakwood (post mortem) or dissecting	- - -	-	40 - -	X
	table with a slight inclines from the				
	edge to the centre to leave a hole				
	in centre lined on top with lead	- - -	-	15 - -	
1	Do Cut ordinary Construction for	- - -	-	10 - -	
1	Do Shelves for instruments &c	- - -	-	12 - -	Deduct 5 Rs. for Beam 3 X
1	Do Washing stand with Marble	- - -	-	1 8 -	
	& round towel stand				
3	Cgr Gravel Slope all round the building	8 - -	Cft	1768 7 9	

Forwarded a revised Estimate amounting to Rs 1768 for Construction of a Road Bungalow at Chatterpoor

No. — dated 27 May 1873

Rs 1873-25-9

Rs 5976

C. 12 dated 8th Jan. 1874

Copy forwarded to the Executive Engineer Ganjam Division

Copy forwarded to the Executive Engineer Ganjam Division

Copy forwarded to the Executive Engineer Ganjam Division

1	Writing table & Chair				768	7	2
	Trestles for supporting coffin				17	-	-
	Wedges & blocks to steady the body				5	-	-
	One set of scales & weights for Post Mortem purposes				5	-	-
10	Teakwood pegs for Clothes				10	-	-
	One Wo Bucket with iron stirrups				2	-	-
	Evacuating foundation & filling basement				5	-	-
	Contingencies				5	-	-
		5	-	Pr.	49	8	3
							86
	I request the cost of furnitures marked thus x as they will be supplied by the Magistrates of the Districts [illegible] Para 6 of Rev. Sr. Order printed in G.O. No 1329 of 22d April 1869						67
					Total Rupees		79

Supg Engr Office 1st Div
Draughtsman's Office
11th February 1870

[illegible]
Actg Supg Engr 1st Div

Public Works Department

No 2075

Proceedings of the Madras Government

Under date the 25th June 1869

Read the following

From The Supg Engineer 1st & 2nd/ H.E. Ct No 921 d/ 2nd June 1869

From The Actg Supg Engr 1st Div/ H & Ct No 926 d/ 3rd June 1869

The Government to approve of the Estimates submitted with these papers, but they are unable to allot any funds for the proposed buildings during the Current Official year.

No. Fra Road House at Chittapore - Rs 790.
2. Do — Do — Vizagapatam " 1107

Sd

Supg Engr 1st Division
4 Conductors
3 Accountants
4 Draftsmen

Sd

Cuz 2413 & 2416

Govt. of {1869} Madras.

PUBLIC WORKS.

To The Superintending Engineer
1st Division

Dated

Read. No. 3

G. O. 7th June 1869, No. 2075.

Nos. 577 & 578

Head Draws at Cuttlepore & Vizagapatam Estimates amounting to Rs. 1897 for Head Sluices at Cuttlepore and Vizagapatam, approved.