M.R.O. 1—77,006—9-5-37.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2102 Press / Mis.

629-30

Dated 29-7- 1869.

Not to be folded or roughly handled

"Military" "New work"

3

1

Proceedings of the Madras Government, Public Works Department,
29th June 1869.

No. 629. Read the following letter from the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department, dated Bellary, 12th June 1869, No. 802 :—

I HAVE the honour to forward, for the sanction of Government, the accompanying plan, specification, and estimate, amounting to Rupees 2,700, for constructing a latrine for the Royal Horse Artillery at Bellary.

1 Plan.
1 Estimate.
1 Specification.

2. The work is entered as Item No. 10 in the current year's Budget, with an allotment of Rupees 4,000.

3. I have not sent the papers for the approval of His Excellency the Commander-in-Chief, as the building is to be on the standard plan.

No. 630. ORDER THEREON, 29th June 1869, No. 2,102.

MILITARY WORKS, No. 33. SANCTIONED.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

"Military"

"New work"

3

Rec'd 10/
Vch 100

ABSTRACT ESTIMATE.

Bellary District

Work for Constructing a Latrine for Royal Horse Artillery at Bellary. Vide Budget 1869-70.

Quantities.	DESCRIPTION OF WORK.	Rate.	Amount.	Amount of each part
2357.6	C. H. Foundation & basement stone in Chunam	" 2 3	331 8 4	
3208.9/12	Superstructure "	" 2 3	451 3 8	
37.6	Brick in Chunam "	" 3/4	7 .. 6	
70.5	" Circular arch work "	" 4	17 10	
68.	R. H. of Slabs "	" 6	25 8	
11	" of Steps "	" 10	6 14	
77 - 5/12	" Jackwood wrought "	4	308 2 3	
77 - 5/12	" " fixing up	" 8 "	38 8 3	
1900	R. H. of Reepers "	" 7	69 4 4	
126	" of Cane boards "	" 1 "	7 11 ..	
912.	S. H. Bengal Terrace Rs.	18	164 2 7	
171	" Pucka " "	25	42 12 ..	
4644.5/12	" Painting "	2 8 ..	116 1 9	
123.1	" Stoney Coomb work S. H.	" 8 "	23 1 8	
125	" Plastering to pcares Rs.	4	5	
639	Flooring with Rs. Slabs "	10	63 14 8	
160	Yard pavement well rammed "	" 8 "	4 12 10	
94.	R. H. of Cornice R. H.	" 6 "	35 4 ..	
2.	Battened Doors	25	50	
2.	"	19	38	
1.	" window	5	5	
1.	" Door	70	70	
1385.	S. H. of Wood piling Rs.	2	27 11 2	
58 7/27	Cyds. Excavation Cyds.	" 8 6	12 12 ..	
12.	Spring Seats Complete	35	420	
10.	Partition Planks.	15 .. "	150	
2.	" at Ends	2	4	2496 1 6.
	Deduct for Old Materials		50	
			2446 1 6.	
	Sundries and Superintendence & other Charges		253 14 6.	
	Total Estimate Rupees		2700	

Bellary 29th May 1869.

Major R.A. Superintendg. 3rd Div.

Lt. Col. Executive Engineer D.P.W.

1869-70

From,

The O'Kleen

In charge Bellary Range

Bellary District.

To,

The Superintending Engr.
3rd, Division.

No.

Dated 24th May 1869.

Received ——— 186

ABSTRACT.

Estimate amounting to Rs 2700

of the Probable Cost of Constructing a Latrine for the use of the Royal Horse Artillery at Bellary.

No. 802.

Supg. Engr. Office 3d Div.
Bellary 12th June 1869.

From

The Supg. Engr.
3d Division

To

The Secretary to Government
P.W.D.

Sir

I have the honor to forward for the sanction of Government the accompanying Plan, Specification and estimate amounting to Rs. 2700 for constructing a Latrine for the Royal Horse Artillery at Bellary.

2. The work is entered as Item No. 10 in the Current year's Budget with an allotment of Rs. 4000.

3. I have not sent the papers for the approval of H.E. the Commander in Chief as the work does not be on the Standard Plan.

I have &c.

A. Kilburn Major R.E.
Supg. Engineer 3d Div.

Enclosures 3
Plan
Estimate
Specification

Returned by the Chief Engr. for the 4 urgently required.

P.W. 1869-70. Dept.

(4) No. 2,502

Comdt's

From

The Supdg. Engineer
3rd Division

To The Secy. to Govt.
P.W.D.

Dated 12th June 69

Rec'd 16th "

I.C. Rec'd

No. 802.

Ens. 3.

Forwards for sanction an Estimate No. 2700 for a Latrine for the Royal Horse Artillery at Belgaum.

No. 2102-29th June 69.

Sanction is ordered

Work

Estimate

No. 2102

Sanction

Ex. 3 Sheets

No. 2102

Estimate for a Latrine for the Royal Horse Artillery at Belgaum

Rupees 249-15-0

C. 195 June 1869 A. 215

P.W. 1869-70. Dept.

Ac. 2502

Govt. of {1869} Madras.

PUBLIC WORKS.

To The Superintending Engr.
3rd Division

&c., &c., &c.

Dated

Recd. *Encl.* 2

G. O. 29 June 1869, No. 2102.

Nos. 629-630

Latrine Estimate of Rs 2700 for a latrine for the Royal Horse Artillery at Bellary, sanctioned.