M.R.O. 1—77,006—8-6-37.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2114 Press / Mis.

653-54

Dated 30 [illegible] 1859.

Not to be folded or roughly handled

No. 653. Read the following letter from the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department, dated Bellary, 12th June 1869, No. 800 :—

I HAVE the honour to forward, for the sanction of Government, the accompanying plan, specification, and estimate, amounting to Rupees 11,550, for constructing three Harness-rooms for the use of the Royal Horse Artillery at Bellary.

1 Plan.
1 Estimate.
1 Specification.

2. This work, entered as Item No. 8 in the Budget for the current year, was struck out agreeably to G. O., No. 1,196, of 12th April 1869. I therefore request permission to bring the entry forward in my Divisional Budget for 1870-71.

3. As the building is to be constructed on the standard design of May 1864, I have not considered it necessary to send the papers for the approval of His Excellency the Commander-in-Chief. I would, however, beg to observe that it is proposed not to build these Harness-rooms in continuation of the Carpenters' and Collar-makers' Workshops, which were sanctioned in G. O., No. 3,807, dated 29th November 1866, and completed in August of the year following in one block.

No. 654. ORDER THEREON, 30th June 1869, No. 2,114.

MILITARY WORKS, No. 35.

THE Government approve of the estimate of Rupees 11,550 for the construction of Harness-rooms for the Royal Horse Artillery at Bellary, and authorise the entry of the work in the Divisional Budget for 1870-71.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Military Department.

Exd. F. R. Bantleman.

Military "New work"

2

ABSTRACT ESTIMATE.

Bellary District

Work For Constructing 3 Harness Rooms for the use of Royal Horse Artilleny at Bellary. Vide Budget 1869/70.

Quantities.	DESCRIPTION OF WORK.	Rate.	Amount.	Amount of each part.
3350.	C.H. Stone in Chunam foundation and basement	" 2. 3	471. 1. 6	
5733½	" Stone in Chunam	" 2. 3	806. 4. 4	
270.	" Circular arch work brick in Chunam	" 4. 3	71. 11. 6	
2.	King post trusses for 20' span	75. ..	150. ..	
145. 5.	" Jakwood wrought	4. ..	581. 10. 8	
145. 5"	" " for putting up	" 8. ..	72. 11. 4	
3400.	R.T. Jakwood reepers	" .. 4	123. 15. 4	
180.	" Eave boards	" 1. ..	11. 4. ..	
94½	" 2" broad slabs	" 8 "	47. 4 "	
1522.	S.H. Bengal Terrace Sq.ft.	18. ..	273. 15. 4	
462.	" Terracing to verandah "	25. ..	115. 8 "	
68½	R.H. Cornice R.ft.	" 8 "	34. 4 "	
10.	" of Steps "	1. ..	10.	
3302.	S.H. Plastering (2 Coats.) Sq.	4. ..	132. 1. 5	
3829½	" Pointing "	2. 8 "	95. 11. 9	
1298.	" Flooring "	10. ..	129. 12. 10	
3.	Strong battened Doors 4½ x 8. Each	40. ..	120. ..	
8	Fixed Iron barred Ventilators 5 x 1½ "	10. ..	80. ..	
2320.	Wood ceiling Sq.ft.	2. ..	46. 6. 5	
66.	Saddle racks Each	1. 8 "	99. ..	
66.	Accoutrement pegs "	" 4. ..	16. 8. "	
85 20/27	C.yds. Excavation C.yds.	" 3. 6.	18. 12. 1	
	Total for one			350. 11. 4
	do for Three			1052. 11. 0
	Sundries & Superintendence			1026. 4. 8
	Total Estimate Rs.			11550. .. ..

R. Weber Major R.E.
Supt. Engr. 3rd Div.

Bellary. —
29th May. 1869.

Wallace Lt. Colonel
Executive Engineer S.P.W.

Sup.g Engr's Office 3d Div.
Bellary 12th June 1869.

No. 800.

From

The Superintending Engineer
3d Division

To

The Secretary to Government
P. W. D.

Sir

I have the honor to forward for the sanction of Government the accompanying Plan, Specification and Estimate amounting to Rs. 11,650 for constructing three Barracks Rooms for the use of the Royal Horse Artillery at Bellary.

2. The work, entered as Item No. 8 in the Budget for the current year, was struck out agreeably to G. O. No. 1196 of 12th April 1869. I therefore request permission to bring the entry forward in my Divisional Budget for 1870/71

3. As the building is to be constructed on the Standard design of May 1864, I have not considered it necessary to send the papers for the approval of H. E. the Commander in Chief. I would however beg to observe that it is proposed not to build these Barracks Rooms in continuation of the Carpenters' and Collarmakers' workshops, which were sanctioned in G. O. No. 3807 dated 29th November 66 and

The book is entered in the Com-in Chief's list as being "very much required"

Enclosures
Plan
Abstract
Specification

From,
The Officer
In charge Bellary Range
Bellary District.

To,
The Superintending Engr.
3rd, Division,

Dated 29th May 1869
Received 186

1869/12.

ABSTRACT.

Estimate amounting to Rs. 11650
of the Probable Cost of Constructing
3 Barrack Rooms
for the use of Royal
Horse Artillery.

and completed in August of the year following
in one block.

I have &c.

R. S. Williams Major R.E.
Supg. Engineer 3d Dn.

P. W. Dept

No 2114 5

Proceedings of the Madras Government
Under date the 30th June 1869.
Read the following

From the Supt Engineer
3rd Dn

Forwarded 12th June 1869

The Government approve of the estimate of Rs 11,550 for the construction of Harness rooms for the Royal Horse Artillery at Bellary and authorize the entry of the work in the Divisional Budget for 1870-71.

6 D. Engr 30 Dr with specifn
4 " Contractor of pw accts
3 " Accts Genl
15 " Mily Depts
Depr 1869.

39/5

The Supt Engineer
3rd Division

Dated 12th June 1869
Rec'd 19th "
No 800

Secy: to Govt
Mily Dept

Forwards for sanction plan, Estimate Rs 11550 for 3 Harness Rooms for Royal Horse Artillery

No 2114-30th June 69.

MB 6SB

c. 19th June 1869 R. 2/at

Cue 2501

Govt. of {1869} Madras.

PUBLIC WORKS.

To The Superintending Engr.
3rd Division

Dated

Rcvd. Encl. 2

G. O. 30 June 1869, No. 2114

Nos. 653-654

Harness rooms for the Royal Horse Artillery at Bellary Estimate Rs 11530 for the construction of Harness rooms for the Royal Horse Artillery at Bellary approved