

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.**Government of Madras.***Justice* **DEPARTMENT.**

G.O. No. 260	Press
521-22	~~Mis~~
Dated 28	1867.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
23th January 1869.*

No. 521. Read the following letter from the Officiating Superintending Engineer, 8th Division, to the Secretary to Government, Public Works Department, dated Palamcottah, 23rd December 1868, No. 2,181.—

1. With reference to G. O, No. 2,214, of the 10th July 1868, I have the honor to submit for sanction—
2 Abstract Estimates.
2 Specification Reports.

Estimate for constructing a new Jail and Cutcherry on	RS.
Standard plan No. 2, at Mudukulatoor, in the	
Madura District	10,100
Do. do. at Tiroochuli	10,500

2. Orders have been given for the commencement of these buildings on the authority given in G. O, No. 3,798, of the 5th December 1868.

No. 522. ORDER THEREON, 28th January 1869, No. 260.

CIVIL WORKS, No. 71. The Government sanction the estimates of Rupees 10,100 and 10,500 respectively for a new Jail and Cutcherry at Mudukulatoor and Tiroochuli in the Madura District.
(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 8th Division
" Controller of Public Works Accounts
" Judicial Department
" Accountant General.

Exd. S. T. Augustin.

Govt. of Madras.

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER,

Sth Division

&c, &c, &c

Dated January, 28th.

Recd

Encl.

G O, 28th January 1869, No 260

JANUARY.

Nos. 521-522

Jail and Cutcherry — Estimates of Rupees 10,100 and 10,500, respectively, for a new Jail and Cutcherry at Mudukulatoor and Thoochuli, in the Madura District, sanctioned.

N. 2181

Superintending Engineer's Office S. D.
Palamcottah 23. December 1868

From
Captain C. S. Sandercock
Off. Superintending Engineer
Sth Division

To
Colonel C. A. P. R.
Secretary to Government
Madras

Enclosures 4
2 Abstracts
Estimates
Specification
Reports

Sir, With reference to G. O. No. 2211 of the 10th July 1868, I have the honor to submit for sanction.

Estimate for constructing a new Jail and Cutcherry on standard plan No. 2, at Mudukulatoor, in the Madura District. Rs. 10,100

Do. Do. at Thoochuli Rs. 10,500

2 Orders have been given for the commencement of these buildings, on the authority given in G. O. No. 3798 of the 5th December 1868.

I have &c
Wm Sandercock Captain R.
Superintending Engineer Sth D.

Abstract Estimate No. of 1865-69
District Madurai
W. P. — Constructing Subsidiary Jail and Submagis-
trate Cutcherry at Udumalathoor

Quantity	Description of Work	Rate	Amount	Amount of each part
	<u>Main Building</u>			
525 ⁵⁵ 1132	Crd. of Bricks in Churnam	5	"	2625 10 2
96618 ² 2503 ⁷ / ₄	Square feet plastering	3	"	289 7 3
	Sq. of flooring with Square bricks	7	"	175 4 2
815 ⁵ / ₈	Crd. feet of wrought wood and put up	3	"	2446 14 "
6678	Square feet of roofing with reapers, nails flat and pan tiles with Churnam borders &c. Complete	18	"	1202 " 7
720	Square feet of flooring with asphalt	3 1/2	"	246 12 9
"	Doors half panelled half recessed shutters with frames, hooks, hinges &c. Complete 4 x 8	36	"	396 " "
4	Doors with Iron gratings frames Complete 4 x 8	40	"	160
2	Iron gratings	42	"	84
1	Door for Treasury Vault	25	"	25 " "
9	Ventilators with Iron gratings	15	"	135 " "
110	Running feet inner Cornice to rooms	"	4	27 8 "

26th Jan 1890. D. 192
 No 260. 28th Jan 1869.

125 1/2

110 1/2

153	Running feet Exterior and dentils	6	"	5	1	6	"		
	Excavating foundation (scaffolding)								
	hire & Sundries			331	1	1			
	Totals Rs.							3200	

Hospital

65 1/2	6 1/2 yds of brick in clay	3	8	"	22	9	5	"	
14 1/2	Square feet of plastering	3	"	"	1	3	5	14	
33 1/8	D. of flooring with square bricks	7	"	"	2	3	6	2	
47 1/4	6 1/2 feet of wrought wood & put up	3	"	"	14	3	7	8	
74 7	Square feet of roofing with Palmaria rafters reapers, nails flat & pan tiles, Chumam borders & Complete	25	"	"	18	6	12	"	
	Excavating foundation & Sundries				23	"	11	10	
	Totals Rs.							650	

Booth Room

32 1/2	6 1/2 yds of brick in clay	3	8	"	11	2	12	5	
69 1/2	Square feet of plastering	3	"	"	2	0	14	10	
106 7/8	D. of flooring with square bricks	7	"	"	7	7	8		
13 7/2	6 1/2 feet of wrought wood & put up	3	"	"	3	9	4	8	
277 1/2	Square feet of roofing with Palmaria rafters collar pieces reapers nails flat and pan tiles Chumam borders & Complete	25	"	"	6	9	6	"	
	Excavating foundation (scaffolding) hire & Sundries				10	2	5		
	Totals Rs.							260	

Well

11 15 3/16	6 1/2 yds of brick in Chumam at	5	"	"	5	1	13	"	
------------	---------------------------------	---	---	---	---	---	----	---	--

3 3/4	Square feet of plastering per Square	3	"	"	4	9	9		
6 1/4	6 1/2 yds of Earth hauling at	3	"	"	7	9	3		
	Total Rs.							70	"

Latrine

6 1/2	6 1/2 yds of brick in clay	3	8	"	19	8	9	3	
231	Square feet of plastering	3	"	"	3	6	14	10	
220	So of flooring with asphaltos	34	"	"	7	4	12	9	
520	Square feet of roofing with Palmaria Couples reapers								
52	* nails flat & pan tiles and Complete	25	"	"	1	3	0	"	
96	Excavating foundation (scaffolding) hire & Sundries				17	"	11	2	
25	Totals Rs.							458	"

	Grand Total Rupees							9638	"
	Extra Establishment							162	"
	Total Estimate Rs.							10100	"

Andrews

Captain R.E.

Sup^g Eng^g 8th Durin

Sup^g Engrs Office
 (23 December 1868)

15 1/2
65 1/2
144 1/2
33 1/2

The following is a list of
 items from the District
 of Madras District
 for the year 1888-89
 and the amount of
 the same is
 Rs. 10,100
 Rs. 30,444/18
 and the amount of
 the same is
 Rs. 10,100
 Rs. 30,444/18

Abstract Estimate No. of 1888/89
 District Madras
 Work Inspecting. Subsidiary Jail and Sub-Magistrates
 Cutchery at Tiruchchully

Quantity	Particulars of work	Rate	Amount	Amount of each part	
Main Building					
525 ⁵⁵ / ₄₃₂	Cy. of Brick in chumam @	5	2625	10	2
9648 ¹ / ₂	Square feet of Plastering	3	289	7	3
2503 ³ / ₄	Sq. of flooring with square bricks	7	175	4	2
815 ⁵ / ₈	Cubic feet of wrought wood put up	3	2446	14	
6678	Sq. feet of Roofing with reapers, nath slat and pan tiles and chumam borden & complete per sq.	18	1202		7
720	Sq. feet of flooring with asphalt	34	244	12	9
11	Doors half panelled, 1/2 Venetian, shutters with frames, hooks, hinges & complete - 4x8	36	396		
4	Doors with iron gratings, frames complete 4x8	40	160		
2	Iron gratings	42	84		
1	Door for Treasury Vault	25	25		
9	Ventilators with iron gratings 5x2 @	15	135		
110	Running feet inner cornice to rooms	" 4	27	8	
153	Do. Exterior do. out dentils	" 6	57	6	
	Excavating foundations scaffolding line & sundries		331	1	1
Total Rupees			8200		
Hospital					
65 ¹⁴ / ₂₇	Cubic yd. of Brick work in clay	3 8	229	5	
1444 ¹ / ₂	Square feet of Plastering per sq.	3	43	5	4
334 ¹ / ₈	Sq. of flooring with sq. Bricks	7	23	6	2
47 ¹¹⁹ / ₁₄₄	Cubic feet wrought wood & put up @	3	143	7	8

9
 3
 1681
 of
 ctive.
 la.

153
169
197

747	Sq: feet of Roofing with Palumahu rafters, reapers, nails, flat and pantiles and chunam borders & complete	25	186	12	
	Excavating foundations & sundries		23	11	10
	<u>Total Rupees</u>				650
	<u>Cook Room</u>				
32 $\frac{6}{7}$	Cy: of Brick work in clay	@	3	8	112 12 5
697 $\frac{7}{2}$	Sq: feet of Plastering		3		20 14 10
106 $\frac{7}{8}$	Sq: of flooring with sq: bricks		7		7 7 8
13 $\frac{7}{2}$	Cube ft: of wrought wood & put up		3		39 4 8
277 $\frac{7}{2}$	Sq: ft: of Roofing with Palumahu rafters, collar pieces, reapers, nails, flat & pantiles, chunam borders & complete	25	69	6	
	Excavating foundation scaffolding line & sundries		10	2	5
	<u>Total Rupees</u>				260
	<u>Well</u>				
5 $\frac{1}{2}$	Cy: of Brick in chunam	@	5		57 13
123 $\frac{3}{4}$	Sq: feet of Plastering		3		4 9 9
40 $\frac{1}{9}$	Cy: of Earth & Bailing		3		7 9 3
	<u>Total Rupees</u>				70
	<u>Lathrine</u>				
56 $\frac{20}{7}$	Cube yd: of Brick work in clay		3	8	198 9 3
1231	Sq: feet of Plastering		3		36 14 10
220	Sq: feet of flooring with asphalt		34		74 12 9
520	Sq: ft: of Roofing with Palumahu rafters, reapers, nails, flat & pantiles & complete	25	130		
	Excavating foundation, scaffolding line & sundries		17	11	2
	<u>Total Rupees</u>				458
	<u>Grand Total Rupees</u>				9638
	<u>Extra Establishment at 5 per cent</u>				487
	<u>Value of land</u>				375
	<u>Total Estimate Rupees</u>				10500

Total Estimate Rupees 10500

116

Am. Lieutenant Captain J.B.
Off: Superintending Engineer 8. 8. 8.

Superintendent
Palumahu
23rd Dec 1868

5
1681
active
la.

Rec'd 29/1/65

12. 6. 1959

166

Cu 5044

Cert. of 1869 Madras.

PUBLIC WORKS.

The Superintending Engineer
8th Division

Dated

Recd

2 ✓

G O 28th Jan'y 1860 No 260

Nos. 521-522

Jail and Cutcherry Estimates
of Rs 10,100 & 10,500 respectively
for a new Jail & Cutcherry
at Muddakulath & Tiruchuli
in the Madras District, Secunderabad

11/12/1900