M.R.O. 1—77,006—8-6-37.

(1) Number of pages 16

(2) Date of repair 4-1-84

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 3446 Press ~~Mis.~~

533-34

Dated 26. 10 1869.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 26th October 1869.

No. 533. Read the following letter from the Superintending Engineer, 2nd Division, to the Secretary to Government, Public Works Department, dated Bezwarah, 1st October 1869, No. 93 :—

I HAVE the honour to submit, for the sanction of Government, an estimate, amounting to Rupees 530, for the relaying of the floor of, and for certain slight improvements to, the cell for male prisoners in the Talook Cutcherry at Ongole. The necessity of the work was fully described in my letter, No. 19, dated 27th April 1869, recorded in G. O., No. 1,772, dated 31st May 1869. I believe the present estimate provides for all that is necessary to put the building into thorough order, with the exception of leaks in the roof, which must stand over till the wood has taken its bearing.

1 Detailed Estimate.
1 Abstract do.
1 Specification Report.

2. If the estimate is sanctioned, I propose to defray the cost from the funds at my disposal for "Civil Buildings" "Minor New Works" in Nellore district.

No. 534. ORDER THEREON, 26th October 1869, No. 3,446.

SANCTIONED.

CIVIL WORKS, No. 68.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 2nd Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Revenue Department.

Exd. S. T. Augustin.

NELLORE DISTRICT,

No 4 or Northern Range

DETAILED ESTIMATE NO. of 1869-70

Work Repairing New Taluq Kutchery at Ongole

Relaying floor of the new Taluq Kutchery and making certain improvements to the cell for State Prisoners

PARTICULARS.	MEASUREMENTS. Number.	Length.	Breadth.	Height.	Superficial Contents.	Cubical contents.
Flooring with Square Bricks and Flat stone						
Southside Hall & Verandah	X	52½	23	"	1207½	
Tahasildars Kutchery	X	18½	14	"	259	
Portion of West Verandah	X	27	7½	"	202½	
do East Do	1	29	7½	"	217½	
Entrance	1	15½	8	"	124	
Do	1	1¾	6	"	10½	
Police Guard Room	X	18	14	"	252	
Police Constables Room	1	18	6¼	"	112½	
Post Office Room	1	14	7	"	98	
Cashiers and Stamps Office	1	18	6¼	"	112½	
East side Record Room	1	14	14	"	196	
Tahasildars Room	1	14	14	"	196	
West side Record Room	1	33½	14	"	469	
Male Prisoners under short sentence	1	24	14	"	336	
Female do Police Suspectors & Female Prisoners under enquiry	3	14	14	"	588	
Male Prisoners under enquiry	1	22	14	"	308	
Solitary Cell	1	14	6	"	84	
North Verandah	1	52½	7½	"	393¾	
East Verandah portion	1	19½	7½	"	146¼	
West Do	1	21½	7½	"	161¼	
Entrances	10	3½	1½	"	52½	
Do	6	4	1½	"	36	
				Carried over		5562¾

Brought forward					556 2¾
Treasury Room	1	12½	6	"	75
do	1	6	6	"	36
	1	5	5	"	100
	4	1½	½	"	3
Towers	4	1½	6		36
	4	2	⅜		5
Total					581 ¾
Deduct Pillars	27	1½	1½	"	60¾
Balance Superficial Flooring					57.57
Demolishing old Concrete floor Measurements as above to a thickness of 6"				Cubic yards	167/27
Brick Chunam					
Building walls for recesses of Towers on Police side	2	3½	1½	12⅜ "	129 15/16
One Course of Brick in Chunam along the edge of Verandah below floor level	1	163	⅜	¼ "	15 9/32
Total Cubic feet					145 7/32
Deduct for 2 feet Square head doorways	2	2½	1½	6½ "	48¾
Do for Pillars	14	1½	⅜	¼ "	1 31/32
Total deductions					50 23/32
Balance Cubic feet of Brick in Chunam or Cubic yards of Do					94 1/2
					3 1/2
Plastering					65
Walls for recesses in Towers	4	2½	6½	"	6¼
Do	2	1¼	2½	"	47
Do	2	4	5⅞	"	35¼
Do	2	3	5⅞	"	158½
Total Superficial					

NELLORE DISTRICT,

No 4 or Northern Range

DETAILED ESTIMATE NO. of 1869-70

Work Repairing New Jail Cutchery at Ongole (Continued)

Particulars.	Measurements. Number.	Length.	Breadth.	Height.	Superficial Contents.	Cubical contents.
Concrete under floors						
Police Constables, Cashiers and Stamps Rooms	2	18	6¼	¼	"	56¼
Post Office	1	14	7	¼	"	24½
Jahasildars Room	1	14	14	¼	"	49
East side Record Room	1	14	14	¼	"	49
West side do	1	33½	14	¼	"	117¼
Male Prisoners under short sentence	1	24	14	¼	"	84
Female do do	1	14	14	¼	"	49
Solitary Cell	1	14	6	¼	"	21
Female Prisoners under enquiry and Police Inspectors Rooms	2	14	14	¼	"	98
Male Prisoners under enquiry	1	22	14	¼	"	77
North Verandah	1	37½	7⅛	¼	"	66 51/64
do	2	7½	7½	¼	"	28⅛
Portion of East Verandah	1	19½	7⅛	¼	"	34 37/64
Do West do	1	21½	7⅛	¼	"	38 19/64
Entrances	10	3½	1½	¼	"	13⅛
Do	6	4	1½	¼	"	9
Treasury Room	1	12½	6	¼	"	18¾
Do	1	6	6	¼	"	9
	6	4	5	¼	"	20
	4	1½	½	¼	"	3¼
Towers	4	6	1½	¼	"	9
	4	2	⅝	¼	"	1¼
Total Cubic feet						878 53/64
Deduct under Pillars	9	1½	1⅛	¼	"	3 51/64
Balance Cubic feet of Concrete or Cubic yards of Do						874 1/32 32 27
Teak wood beam to be placed in lieu of the existing Cracked one	1	15½	⅝	⅔	-	6 11/24
					Total Cft. of teak wood	6 11/24

Weather Boards with frames &c complete for Ventilators in all Prisoners Rooms and Treasury Room	10	"	"	"	"	"
Removing and rebuilding roughstone revetment of well	1	23½	1½	7½	"	264 3/8
Total Cubic yards of Roughstone						9 3/4
Brick in Chunam to Wells						
Taking down & rebuilding Parapet walls	1	21	3/4	5	"	78 3/4
Total Cubic yards						2 2/9
Plastering						
Parapet walls of well	1	21 1/4	8 3/4	"	"	185 15/16
Total Squares						1.86
Sand laid under portion of Flooring in Head of Concrete			Candies			15½
Pointing Floor						
Measurements as those of Flooring with Square bonds and flat			Square feet		5757	
Pointing Brickwork along the edge of Drains	1	162	3/8	"	60 3/4	
Total Squares					58 3/17	
Doors.						
Two feet Square head doors 6'×2' each for recesses of Towers on Police side	2					
Repairing the existing ladder to make it moveable to get ouro of Clearing Silt from well and fixing a Couple to facilitate the drawing of wa li	1					
Strutting Cross beam in room of Male Prisoners under short sentences						
Superintendence & Sundries						

4th Range Office
Camp Cottapatam
17th September 69

Jno Hall Lieut
Officer in charge No 4 or
Northern Range Nellore

(7)

NELLORE DISTRICT,

No 4 or Northern Range

ABSTRACT ESTIMATE NO.

Work Repairing New Tank Catcherry at Ongole

Repairing Side of the new Tank Catcherry at Ongole

Quantity.	Description of Charges.	Rate.	Amount.	Total.
57.57	Squares of Flooring with Square bonds	5 6	309 7	
106 16/27	Feet flat Stones @	" 2	13 5 2	
3 1/2	Cubic yds of Demolishing old Floor @	4 5	15 1 6	
1.63½	Do of Brick in Chunam @	3 "	4 9 8	
32 11	Squares of Plastering @	2 4	72 4 8	
6 11/24	Cubic yds of Concrete under floors @	3 "	19 6 "	
10	Cft of Teakwood @	3 8	35 " "	
9 3/4	Weather Boards with frames &c	" 8	4 14 "	
2 8/9	Cubic yds of Rebuilding revetment of well	4 5	12 7 4	
1.86	Do of Brick Chunam to Delta	3 "	5 9 3	
15½	Squares of Plastering do	1 "	15 8 "	
58 3/17	Candies of Sand laid under floor of Catcherry	2 4	130 14 4	
2	Squares of Pointing Do floor	12 "	24 " "	
1	Two feet Square head doors stone 6'×2' each for recesses of towers	2 8	2 8 "	
1	Repairing the existing Ladder Hire for Clearing Silt from well & fixing a Couple to facilitate the drawing of wa li	6 "	6 " "	
1	Strutting Cross beam in room of Male Prisoners under short sentences	8 "	8 " "	
	Superintendence & Sundries @	5 "	3,5 7 1	
	Total Estimate Rupees		715 " "	
	Deduct amount already sanctioned		185 " "	
	Balance Estimate Rupees		530 " "	

Jno Hall Lieut

4th Range Office
Camp Cottapatam
17th September 69
10th October 69

Officer In charge No 4 or Northern Range, Nellore District.
Jno Hall Lieut & Asst Engr
Superintending Engineer 2nd Class

Rs 93

Superintg. Engr's Office 2nd Dn.
Bezwada 1st October 1869
Desp. 4 do

From

Lieut-Colonel F. J. Roberts R.E.
Superintending Engineer.
2nd Dn.

To,

Colonel C. A. Orr. R.E.
Secretary to Government
D. P. W.
Madras.

Enclosures
1 Detailed Estimate
1 Sketch do
1 Plan
3

Sir,

I have the honor to submit for the sanction of Government an Estimate amounting to Rs. 530, for the relaying of the floor of, and for certain slight improvements to the Cell for male prisoners in the Taluq Cutcherry at Ongole. The necessity of the work was fully described in my letter No. 19 dated 27th April 1869 recorded

From,
The Officer in charge
of No. 4 Range,
Nellore District.

To
The Superintending Engineer,
2d Division.

Dated 1st October
Received } 1869

P.P. 4246/69
Rs. as "Estimate" in Dy No 93

Relaying floor to the Reverberatory Range
Estimate for Taluq Cutcherry at Ongole. Nine Cells & Verandah Improvements

Rs 530

Printed at the Asylum Press, by W.M. THOMAS—1869.

recorded in G.O. No. 1772 dated 31st May 1869. I believe the present Estimate provides for all that is necessary to put the building into thorough order, with the exception of leaks in the roof, which ~~must~~ stand over till the wood has taken its bearing.

2. If the estimate is sanctioned, I propose to defray the cost from the funds at my disposal for "Civil Buildings" "Minor New Works" in Nellore District.

I have the honor to be
Sir.
Your most obedient Servant.

Signed by
Lt. Colonel R.E.
Superintending Engineer 2nd Div.

P.W. 1869 Dept.
No 939
No 4276.

From The Supdg Engineer
2d Division

To The Secretary to Govt
P.W. Madras

Dated 1st October 1869

Rd 11" " "

Exd: 2.

Submits for the sanction of
Govt an Estimate amounting
to Rs 530 for the relaying of
the floor of, and for certain
slight improvements to the
Cell for male prisoners in
the Taluq Cutchery at Anjar
vu

No 3646 - 26: Octr 69.

With an order

C. 13th Octr 1869 R. 23rd

(4)

3446

Civil Dept (18)

No 3446
Sanctioned.

Fort St George
26: Octr 1869.

45=
5=

To
6 S. Engr 2d Dn with Specifn
4 Controller
3 Accts Genl
21 Rev Debtt

Desp. 27/10/69.

Enc 4276

Govt. of {1869} Madras.

PUBLIC WORKS.

To The Superintending Engr.
2nd Division

Dated

Rec'd.

End 1

G. O. 26 Oct 1869, No. 3446

Nos. 533-534

Taluq Cuttalurry at Bryole

Estimate of Rs 1530 for ear-
-th work in repairing bunds
for Rain Prisoners in the Ta-
-luq Cuttalurry at Bryole, Nellu
-re Dt. sanctioned -