M.R.O. 1—77,006—8-6-37.

(1) Number of pages 2

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 3460 Press ~~Mis.~~

560-61

Dated 27 10 1961.

Not to be folded or roughly handled

B

No. 560. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Salem, 25th September 1869, No. 112 :—

1 Plan.
1 Estimate.
1 Specification.

With reference to G. O., No. 1,825, of the 3rd June 1869, I have the honour to forward, for the sanction of Government, for entry in the next year's Budget, a revised estimate of Rupees 7,000, accompanied by plan and specification, for two Staff Serjeants' quarters for the Commissariat Department at Bangalore.

2. A terraced is proposed instead of a tiled roof, as good tiles are difficult to be got, and the thickness of the walls has been reduced from 2 to 1½ feet, as the latter is considered quite sufficient. The size of the cook-room, of which there will be one for each quarter, has been reduced to that provided for an Assistant Apothecary's quarter. In other respects the plan now submitted, which has been approved by His Excellency the Commander-in-Chief, is strictly in accordance with the standard design for Staff Serjeants' quarters (class A.) circulated with G. O., No. 1,836, of the 1st July 1865.

No. 561. Order thereon, 27th October 1869, No. 3,460.

MILITARY WORKS, No. 19.

The Government sanction the estimate of Rupees 7,000 for the construction of two Staff Serjeants' quarters for the Commissariat Department at Bangalore, and will endeavour to provide for the buildings in the out-going Budget.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 5th Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Military Department.

Exd. S. T. Augustin.

Military — 5th Division D. P. W. — New Work

Bangalore

Abstract Estimate of 1869/70.

Work; Constructing two Staff Serjeants Quarters for the Commissariat Department Bangalore.

Quantities	Description of Work	Rate	Per	Amount	Total
3318	Cft. of Excavation	"	" 1	Cft. 17	" "
3318	Do. of Foundation Stone in Chunam	"	26	" 518	" "
1740	Do. of Basement Do.	"	26	" 272	" "
6232	Do. of Superstructure brick in Do.	"	29	" 1071	" "
516	Do. of Arch work Do.	"	4	" 129	" "
322	Rft. of Cornice work	"	12	" Rft 242	" "
108 78/100	Sqrs. of Plastering two coats of Chunam	2	8	" Sqr. 272	" "
80.09	Do. of whitewashing two coats	"	3	" " 15	" "
28.69	Do. of Bluewashing Do.	"	4	" " 7	" "
247 525/576	Cft. of Teakwood wrought and put up	3	8	" Cft. 868	" "
50	No. of Nails 7" long	"	" 7	2	" "
4	Do. of Stone Plates under beams	"	4	" " 1	" "
23.49	Squares of Terracing with brick on edge, Jelly 3" thick, 3 Courses of flat tiles & 3 coats of Chunam	27	8	" Sqr. 646	" "
2.75	Squares of Semi terracing with four courses of flat tiles 3 coats of plaster and plained				
	reepers	19	"	"	52 " "
	Carried Over				4,112 " "

Quantities	Description of Work	Rate	Per	Amount	Total
	Brought Over				4,112 " "
28.73	Sqrs. of Wood oiling two coats	2 " "	Sqr.	57 " "	
3526	Cft. of Filling in basement	" " ½	Cft.	9 " "	
18.76	Sqrs. of Flooring with Stone Slabs set in Mortar and pointed with lime putty	15 " "	Sqr.	281 " "	
2.00	Do Do with asphalte	20 " "	"	40 " "	
198	Rft. of Stone Slabs tread for Steps	" 3.	Rft.	37 " "	
252	Do of Zinc Spouts 4" diameter including iron clamps	" 9 "	"	142 " "	
4	Nos. of Stone Pillars 10 × 1¼ × 4½	3 " "	E	12 " "	
4	Pairs of half Pannelled and half glazed door 4×8 with frames and iron works Complete	36 " "	E	144 " "	
2	Pairs of half Pannelled and half Venticed doors 4×8 with frames and iron work Complete	42 " "	"	84 " "	
4	Pairs of Pannelled door with frames and iron works Complete 4×8	40 " "	"	160 " "	
2	Pairs of battoned door 4×8 with frame & iron works Complete	32 " "	"	64 " "	
4	Do Do 3×6 Do	18 " "	"	72 " "	
12	Glazed Swing windows with frames and iron works Complete 3×1½	7 " "	"	84 " "	
4	Pairs of Pannelled Shutters for Almirah with frames and iron works Complete 5×6½	37 " "	"	148 " "	
	Carried over				5,646 " "

Quantities	Description of Work	Rate	Per	Amount	Total
	Brought Over				5,446 " "
7.52	Squares of Verdigris green painting two Coats	5 " "	Sqr.	38 " "	
1	Marking Board	5 " "	E	5 " "	
2	Inventory Do	" 12 "	"	2 " "	
					5,491 " "
	Sundries				259 " "
	Total Rupees				5750 " "

Out Houses-

759	Cft. of excavation	" "	1 Cft.	4 " "	
759	Do of Foundation Stone in Chunam	" 26 "		119 " "	
476	Do of Basement Do	" 26 "		74 " "	
1909	Do of Superstructure brick in Do	" 29 "		328 " "	
89	Do of Archwork Do	" 4 "	"	22 " "	
142	Rft. of Cornice work	" 12 "	Rft.	107 " "	
41.84	Sqrs. of Plastering two coats of Chunam	2 8 "	Sqr.	105 " "	
12.95	Do of Whitewashing 2 coats	" 3 "	"	2 " "	
28.89	Do of Bluewashing 2 Do	" 4 "	"	7 " "	
22.47/96	Cft. of Teakwood prepared and put up	3 8 "	Cft.	79 " "	
3.19	Sqrs. of Terracing with brick on edge fully 3" thick. 3 courses of flat tiles & 3 coats of Chunam	27 " "	Sqr.	88 " "	
1.56	Sqrs. of wood oiling two coats	2 " "	"	3 " "	
83	Cft. of Filling in basement	" " ¼	Cft.	1 " "	
	Carried Over				939 " " 5750 " "

Quantities	Description of Work	Rate	Per	Amount	Total
	Brought Over				939 " "
2 1.38	Squares of Paving Stones set in Mortar & pointed with lime putty	15 " "	Sqre	21 " "	
1 .72	Do of Flooring with clay & Sand	4 " "	"	3 " "	
6	Pairs of Battened doors with frames and iron works &c. complete 3½×6	18 " "	E	108 " "	
2. 4	Pairs of Battened Windows with frames & iron works &c. complete 3½×3	9 " "	"	36 " "	
2	Do of battened Shutters for Almirah with frames & iron works &c. complete	12 " "	"	24 " "	
4.87	Sqres of Red painting two Coats	2 " "	Sqre	10 " "	
2	Nos of Privy Seats &c. complete 2½×2½	3 8 "	E	7 " "	
2	Iron Chimneys &c. complete	20 " "	"	40 " "	
				1188 " "	
	Sundries			62 " "	
	Total Rupees				1250 " "
	Grand Total Rupees				7000 " "

Executive Engrs Office
Bangalore
2d July 1869

Dy W. W. Wood Capt. R.E.
Ex: Engineer Bangalore

By order
Dy W. R. Freeham Major
by Asst Dy Mr Genl

Ed Ward Coll R.E.
Supg Engineer 5th Div

5th Division D.O.P.W.

Bangalore.

P.P. 4212/69

G.O. 27-10-69-34

From 27th October 69 to 2.5

Abstract Estimate for Constructing two Staff Serjeants Quarters for the Commissariat Department Bangalore

Amount of Estimate Rs.

Superintending Engineer's Office,
Salem, 25th September 1869.
Despatched 5th October 69.

No. 112.

From

The Superintending Engineer,
5th Division.

To

The Secretary to Government,
P. W. D.

Enclosures 3.
1 Plan
1 Estimate
1 Specification

Sir,

With reference to G.O. No. 1825 of the 3rd June 69, I have the honor to forward for the sanction of Govt. for entry in the supplementary Budget, a revised Estimate of Rupees 7000, accompanied by Plan and Specification, for two Staff Serjeants Quarters for the Commissariat Department at Bangalore.

2. A Verandah is proposed instead of a tiled roof, as good tiles are difficult to be got; and the thickness of the walls has been reduced from 2 to 1½ feet, as the latter is considered quite sufficient. The

size of the Cook room, of which there will be one for each quarter, has been reduced to that provided for an Assistant Apothecary's quarter. In other respects the plan now submitted, which has been approved by His Excellency the Commander-in-Chief, is strictly in accordance with the Standard design for Staff Regimental quarters (Class A), circulated with G.O. No. 1836 of the 1st July 1865.

I have the honour to be
Sir,
Your Most Obedient Servant
Edward Colomb R.E.
Superintending Engineer.

Public Works Department

No. 3469 3460

Proceedings of the Madras Government

Under date the 27th Octr 69.

Read the following

From The Supt Engineer 5th D./H. E. No. 1129/25th Septr 1869

The Government sanction the estimate of Rs. 7000 for the construction of two Staff Serjeants Quarters for the Commissariat Departt at Bangalore, and will endeavour to provide for the building in the outgoing Budget.

WOM

A/A.

40/5

To Supt Engrs 5th D. with the specifications

Contd Nov

Accts Genl

Mily Depts

Desp. 28/10/69

To The Secretary to Govt
Mily Dept

Dated 25th September 1869

Sir,

I have the honor to forward a revised Estimate for erection of quarters for Staff Sergeants at Bangalore, in accordance with the sanction conveyed in your letter No. 3469 dated 27th Octr 1869.

2. The Government sanction the estimate for Rs. 7000 for the construction of two Staff Sergeants Quarters for the Commissariat Department at Bangalore, and will endeavour to provide for the building in the outgoing Budget.

3. The Government also sanction the employment of Contract Labour for the work.

4. The Government also sanction the employment of Contract Labour for the work.

I have the honor to be
Sir
Your most obedient
humble Servant
[illegible]
Supt Engr
5th Division

Dated 25th September 1869

To The Superintending Engineer
5th Division
Bangalore

Govt. of {1869} Madras.

PUBLIC WORKS.

To The Superintending Engr.
5th Division

Dated 1

Recd. Encl. 2.

G. O. 27-Oct. 1869, No. 3465

Nos. 560-561

Staff Sergeant 2n. Estimate
& Rs 7000 for two Staff Serjeants
2n. Letter Commissariat Office
at Bangalore, Sanctioning the
Remarks-