MRO I—77,006—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 1870	Press / Mis.
170-71	
Dated 8. 6	1869.

Not to be folded or roughly handled

No. 170. Read the following letter from the Superintending Engineer, 3rd Division, to the Chief Engineer for Irrigation, dated Bellary, 13th May 1869, No. 462:—

I HAVE the honour to submit, for the sanction of Government, from the allotment Minor New Works, "Agricultural," in the Bellary District, the accompanying comparative statement for constructing a calingulah in the Raggy Moosulwada Tank in the Hurpanhully Talook, Bellary District.

2. The construction of this calingulah was sanctioned in G. O., No. 189, of 20th January 1868; the extra sum of Rupees 225 now applied for is for removing a quantity of earth, which will interfere with the free discharge of the calingulah, and which Mr. Supervisor Vardon had omitted to include in his original estimate. The item is a large one for such a purpose, but, as the material is hard, it will be necessary to remove it instead of leaving it for the water to carry it away as leaving it might cause damage to the work.

No. 171. ORDER THEREON, 8th June 1869, No. 1,870.

IRRIGATION, No. 6.

THE Government sanction the supplemental estimate of Rupees 225 for the calingulah of the Raggy Moosalwada Tank, for the construction of which an estimate of Rupees 3,165 was sanctioned in the Order of the 20th January 1868, No. 189. The application should have been accompanied by sections, showing the position and extent of the earth obstructing the water-way of the new calingulah; and it is observed that, had the intended arrangements been put on paper in the first instance, the omission of the work now sanctioned would have been avoided.

2. The sum of Rupees 225 will be charged against the allotment for Minor New Works under "Agricultural" in the Bellary District.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division.
" Controller of Public Works Accounts.
" Accountant-General.
" Revenue Department.
" Chief Engineer for Irrigation.

Exd. E. C. Shunker.

Bellary District
Roads & Bridges
From Lt. Col. [illegible]
To [illegible]
Dated 1869-70

No. 462

Superintending Engrs office, 3rd Dn
Camp Jonnigeramanhulu Bellary District
the 15th May 1869

From,
The Superintending Engineer
3rd Dn

To,
The Chief Engineer
for Irrigation.

Sir,

I have the honor to submit for the sanction of Govt, from the allotment Minor Works "Agricultural" in the Bellary District the accompanying comparative statement for constructing a Calingulah in the Raggy Morsul ward Tank in the Hosapanhulley Taluk, Bellary District.

2. The construction of this Calingulah was sanctioned in G.O No 189 of 20th January 1868: the Extra sum of Rs 225 now applied for is for removing a quantity of earth which will interfere with the free discharge of the Calingulah, and which the Supervisor Pardon had omitted to include in his original estimate. The item is a large one for such a purpose, but as the material is hard, it will be necessary to remove it instead of leaving it for the water to carry it away as leaving it might cause damage to the work.

I have &c &c

[signature] Major R.E
Superintending Engineer 3rd Dn.

Bellary Division

Gospelt Range

From Asst. 1st 4th 3/4/69-70

Chief Supervisor in charge

1/416/69 of

Gospelt Range

To The Superintg Engr.

P.W. 2243/69. 3rd Division

Dated 3rd May 1869

Received.

Comparative Statement

Shewing the original

Estimate Quantities

& Rates for Constructing

Calingulah to the

Raggy Moosulwood ah

Tank in Kurpunahully

Taloob &c. vide Supdtg

Engrs. Docket No. 86 Dy

4 Abstracts

Dy No. 1865 to Docket No. 86 of 1869

From Asst. 1st 4th Class

The Supdtg. Engineer

Bellary.

Sir,

The Chief Engineer

for Irrigation

Madras 13th May 1869

Received 20th " "

Regd. 28th " No. 402. 1865

Dear Sir,

Forwards a Comparative

Statement for Estimate

& Calingulah in the Raggy

Moosulwood Tank Kurpunahully

Taloob &c.

Yours &c. 1870 Superintg Engr.

Head Quarters Madras

Dated 1st June 1869

Ag 1/70

Ca 29th May 1869 A. Higgins

Comparative Statement shewing the Original Estimates Quantities, and Rates for Constructing a Calingulah to the Raggymoodelwadah Tank in Kurpumahulley Talook and work remaining to be done and Excess or Saving upon each item of Original Estimate vide Superintendg Engineer's Docket No. 86

Dated 8th April 1869

Estimate Sanctioned by Government					Work done			Work remaining to be done					Comparison between the amounts in Columns 5 & 14		Explanations of differences & Remarks
Quantity	Description	Rate	Amount	Total	Quantity	Rate	Amount	Total	Quantity	Rate	Amount	Total	Total of Columns 9 & 13	Excess over Estimate	Saving upon the Estimate	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
14-4.10	Cubic yards of earth work	. 1 8	119 3 8	119 3 8	114-4.10	0 1 8	119	3 5/8 119	3 5/8 205.10	. 1 8	214 3 8	214 3 8	333 7 1/4	214 3 8	. . .	This is necessary on account of a large quantity of earth obstructing the waterway of the new Calingulah & appear of it which must be removed in order to allow a free passage for the water passing over the Calingulah during the Monsoons - If it be not taken away it will cause damage to the work now in progress. The Shutters will be ready by end of May 1869.
26	——do—— Tamping	" " 3	12 4 6	12 4 6	4.6.826	" " 3	12	4 6	12 4 6	"	. . .	. . .	12 4 6	. . .	. . .	
52-12	——do—— Rough Stone do	" 6	" 282 4 6	282 4 6	282.4.6752.12	" 6	" 282	4 6	282 4 6	"	. . .	. . .	282 4 6	. . .	. . .	
5439	Cft Stone in Chunam	. 24	2257 8 4	2257 8 4	15439	. 24	2257	8 4	2257 8 4	.	. . .	. . .	2257 8 4	. . .	. . .	
1019	Sft of Pointing	2 8	" 252 15 7	252 15 7	1019	2 8	. 252	15 7	252 15 7	"	. . .	. . .	252 15 7	. . .	. . .	
1812	——do—— Plastering	4	" " 72 7 8	72 7 8	1812	4	" " 72	7/8	72 7/8	"	. . .	. . .	72 7/8	. . .	. . .	
2	Burnt Stone 2 Cross Stones for each Tamboghee	1	" " 4	4	" " 2	1	. 4	"	4	"	. . .	. . .	4	. . .	. . .	
4 2/3	Cft of Teakwood wrought for 6 Shutters for 2 Do Sluices at 5 per Cent	4	" " 18 10 8	18 10 8	" " 5	. . .	. . .	. . .	4 2/3	4	" " 18 10 8	18 10 8	18 10 8	. . .	. . .	
		5	" "	150 15 6			150	15 6	150 15 6		10 12 4	10 12 4	161 11 10	10 12 4	. . .	
				3165 . .			3146 5 4	3146 5 4			243 10 8	243 10 8	3390 . .	225 . .	. . .	

Gospette Range Office
Camp Hoodeglee
2nd May 1869.

P.W.D. Dept.
Rec'd 6th June 1869
From Supt Eng. No. 2265
The Supg Engineer
3 Dn.

The Chief Engineer
for Engalim.

Dated 13 May 1869
Recd 20 " "
Ack. 28 " No. 469 D/5

Ent.
Forwards a Comparative Statement for Constructing a Calingulah in the Raggy Moodelwadah Tank for Sanction.

No. 1870 8 June 69
Hd
Superintg Engineer
Chingleput

No 1170
C 29 May 1869 R 4 June

P. W. D.

No. 1870

Proceedings of the Madras Govt.
Under date the 8th June 69
Read the following

From the Superintendg Engr 3d Dn C.P.W. No 462 dd 13 May 69

The Government
sanction the supplemental
estimate of Rs. 225. for the
Calingulah of the Rassoy
Moosalivada Tank, for
the construction of which
an estimate of Rs. 3165,
was sanctioned in the
order of the 20th January
1868. No 189. The application
should have been accom-
panied by sections, show-
ing the position and ex-
tent of the earth obstructing
the waterway of the new
Calingulah; and it

is

is observed that, had the intended arrangements been put in paper in the first instance, the omission of the work now sanctioned would have been avoided.

2. The sum of Rs. 225 will be charged against the allotment for Minor New Works under "Agricultural" in the Bellary District.

GAB

47/6

1/ To Superintendent 3rd Div ✓
2/ Controller, V.P. Accts ✓
3/ " Asst. Genl ✓
4/ Revenue Dept. ✓
5/ Chief Engr for Irrign ✓

Dept. 9/6/09

Rec 2245

Govt. of {1869} Madras.

PUBLIC WORKS.

To The Superintending Engr.
3rd Division

Dated

Rec'd Encl /

G O 8th June 1869, No. 1870

Nos. 141-141

Cuddapah supplemental Estimate for Rs 225 for the Cuddapah & the Rayadroog Anicut in the Bellary Dt, sanctioned with remarks.