

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 2149	Press Mis.
43-44	
Dated 2 7	1857.

176
Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
2nd July 1869.*

No. 43 Read the following Proceedings of the Madras Government in the
Revenue Department :—

Custom-house at Mulky in South Canara —
Estimate for its construction ordered to lie
over till next year. Board directed to instruct
Collector to hire a small building at Mulky, if
the present one cannot be occupied with safety. (Here enter 24th June 1869, No. 1,794.)

No. 44. ORDER THEREON, 2nd July 1869, No. 2,149.

CIVIL WORKS, No. 8.

COMMUNICATED to the Superintend-
ing Engineer of the 7th Division.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division, with Estimate.
.. Controller of Public Works Accounts.

Ed. S. T. Augustin.

Govt. of 1869 Madras.

PUBLIC WORKS.

THE SUPERINTENDING ENGINEER,

7TH DIVISION.

&c. &c. &c.

Dated July, 2nd

Recd

Encl

G O, 2nd July 1869, No. 2,149

JULY.

Nos. 43-44

Custom-house at Mulky — Proceedings Revenue Department on an estimate for the erection of a Custom-house at Mulky in the South Canara District, communicated to the Superintending Engineer of the 7th Division

15/11/69

No. 5 of 1863/69

Abstract Estimate for Constructing Sea Custom House at Mulky. T. Canara -

Quantity	Description of work	Rate	Amount	Total
4427 2427 5	Cubic feet of Lathum in Chumam per 100 @ 19	19	841 31	
110 1/4	D: of Flat Arch work per sq —	21	23 2 9	
2919 1/2	Square feet of plastering with 2 coats of Chumam for square feet —	4	116 12	
1078 1/2	D: of flooring with Lathum & jelly in Chumam for square —	4 8	48 8 6	
1564 1/2	D: of roofing with 3 feet of plaster, rafters, & supports Machine Lath Chumam borders 8" for square —	28	439 7 4	
30	Cubic feet good junglewood for Arch joist	2	100	
1	1 Battened Door with iron hinges Cross bolts with padlocks complete —		15	
1	D: Iron banded window with frame, iron hinges and bolts complete —		14	
5	D: battened window with iron hinges 8" Complete each —	8	40	
8	100 feet of junglewood railing for the Office Room —	5	40	
2822	Cubic feet earth work for 100 Cubic feet —	12	28 10 7	
	Landre and Superintendence —		78 6 9	

At Mangalore Office of

T. Canara

Mangalore 20th August 1868

Mathew

at Mangalore

Total Charges

186 1/2

at Mangalore

Execution Engineer

at Mangalore

Exd. F. R. Bantleman.

Edward Everett

Mr. Brewster
Chestnut St. at Penn.
Oct 1860

11th 1869
 Cont. of 1869 *Madras*
1869-70
 REVENUE.

THE BOARD OF REVENUE,
 &c. &c.

Dated June, 21st.

Recd. " 28 "

1

G. O. 24th June 1869, No 1,794.

JUNE

Nos. 532-533.

2149-2284/69

Custom-house at Mulky in South Canara -
 Estimate for its construction ordered to be over-
 full next year Board directed to instruct Collector
 to hire a small building at Mulky, if the present
 one cannot be occupied with safety.

vide an Order

2149
2149
2149

*Communicated to the
 Superintendent Engineer
 for the 1st Division*

2149-2284/69

2149

7th 1869
1869-70
1869-70

22
3

2149-2284/69

2646
Govt. of {1869} Madras.

PUBLIC WORKS.

To *The Superintending Engrs*
7th Division

&c, &c, &c

Dated

Recd

Encl 1

G O *2-10-69* 1869, No *2149*

210 Nos. *113-114*

Custom House at Mulky.
Prr. Rev. Dept on an
estimate for the erection
of a Custom-house at
Mulky in the South
Canara Dist. Comd to
the Super. Engrs of the
7th -