M.R.O. 1—77,006—8-6-37.

(1) Number of pages 16

(2) Date of repair 23.11.43

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 2213 Press Mis.

168-69

Dated 8 7 1869.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
8th July 1869.

No. 168. Read the following letter from the Acting Collector of Nellore, to the Chief Secretary to Government, Fort St. George, dated Nellore, 15th June 1869, No. 1,129:—

WITH reference to Proceedings of Government, No. 545, of 5th April 1869, I have the honour to forward, countersigned, for the sanction of Government, an estimate,* prepared agreeably to the Standard plan, received with the Proceedings above quoted.

* Amounting to Rupees 1,130.

2. The Superintending Engineer of the 2nd Division states that the work cannot be proceeded with until funds be placed at his disposal, as no provision is made in the current year's Budget for the work in question.

TRANSFERRED to the Public Works Department, with reference to the Orders in that Department, dated the 19th March 1869, No. 905, and No. 1,329, dated 22nd April 1869.

(Signed) H. E. STOKES,
Acting Under Secretary to Government.

23rd June 1869.

No. 169. ORDER THEREON, 8th July 1869, No. 2,213.

CIVIL WORKS, No. 27.

THE Government approve of the estimate of Rupees 1,130 for the construction of a Dead-house for the Hospital at Nellore, but as no funds are available, the execution of the work must be deferred.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Collector of Nellore.
,, Superintending Engineer, 2nd Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Judicial Department.

Exd. S. T. Augustin.

Nellore Collector's Office
15th June 1869.

From

R. I. Melville Esqre
Acting Collector of
Nellore.

To,

The Honorable R. S. Ellis C.B.
Chief Secretary to Government,
Judicial Department,
Fort Saint George.

Sir

With reference to Proceedings of
Government, No 545, of 5th April 1869,
I have the honor to forward countersigned
for the sanction of Government, an estimate
prepared agreeably to the Standard Plan,
connected with the Proceedings above
quoted.

2. The Superintending Engineer of
the 2nd Division states, that the, Work
cannot be proceeded with, until
funds be placed at his disposal,
as no provision is made in the Current
Year's budget, for the work in question.

I

* Amount is
Rs 1150-- --

1-

Henry Le Hunte Esq.
Sir,
Your most Obedt Servt.
Executive
Engineer

Corrected by
Exc. I.G.
16/6/69.

DETAILED ESTIMATE No. 7 of 1869/70

Nellore District

Work

Constructing a Dead house for Hospital at Nellore

Particulars.	Number.	Measurement. Length.	Breadth.	Height.	Cubical Contents.
Concrete under foundations	1	66	3½	1	231
Total cft of concrete					231
Brick in Chunam					
Foundations of Walls	1	66	2½	2	330
Basement of Do	1	66	2	2	264
Superstructure of Do	1	66	1½	15+14	1435½
Intervals	1	66	1½	5/2	41 3/12
Cistern	1	6	2	2	24
Steps	1	8⅔	⅓	3	8⅔
Total Cubic feet					2106 11/12
Deduction for Doors & Windows &c.a					
Door	1×5×1½×8 = 60				
Windows	3×5×1½×3 = 67½				
Ventilators	8×2½×1½×1½ = 45				
					172½
Total Cubic feet of Brick in Chunam					1934 5/12
or Cubic yards					71 7/9
Plastering in 2 coats of Chunam					
Outside of the Room including basement & offsets	"	72	"	16½	1188
Inside of the Room	"	60	"	15	900
Sink of the room	"	17⅓	"	3	52
Sides of steps	2	3	"	1⅓	8
cistern	"	5	"	3	15
Over steps	1	6	"	5	30
Total Square feet					2193
Deduction for Plastering					
Door	1×5×8 = 40				
Windows	3×5×3 = 45				
Ventilators	8×2½×1½ = 30				
					115

Particulars.		Number.	Measurement. Length.	Breadth.	Height.	Cubical Contents.
Total Superfeet						2078
or Squares						21
White washing in 2 coats of Cluman Squares						21
Asphalte flooring 1st Story		1	18	12		216
Total Superfeet						216
or Squares						2 1/8
Roofing						
Front	31 1/2 × 13 1/2 / 2	1	17 1/4	"	13 1/2	232 7/8
Rear	29 1/2 × 10 1/2 / 2	1	14 3/4	"	10 1/2	154 7/8
Ends		2	19 1/4		2 1/2	96 1/4
Do			18		11	189
Total Superfeet of Roofing						673
Teakwood work						
Wall plates			68	5/12	1/4	7 1/12
Ridge piece		1	6	1/4	5/12	5/8
Struts for bottoms sides & front		14	5	1/4	1/3	5 5/6
Do for Corner		2	6 1/2	1/4	1/3	1 1/12
Purlin on Struts			71	1/4	1/3	5 11/12
Rafters in front		5	13 1/2	1/4	5/12	7 1/32
Do in Rear		5	10 1/2	1/4	5/12	5 15/32
Hip Rafters in front		2	13 3/4	1/3	1/2	4 7/12
Do in Rear		2	17 3/4	1/3	1/2	5 11/12
Jack Rafters in front & 2 Ends		6	11 3/4	1/4	5/12	7 11/32
Do in Do & Do		6	10	1/4	5/12	6 1/4
Do in Do & Do		6	8 1/4	1/4	5/12	5 5/32
Do in Do & Do		6	6 1/2	1/4	5/12	4 1/16
Do in Do & Do		6	4 3/4	1/4	5/12	2 31/32
Do in Do & Do		6	3	1/4	5/12	1 7/8
Do in Do & Do		4	1 1/4	1/4	5/12	25/48
Do in Ends		2	13 1/2	1/4	5/12	2 13/16
Jack Rafters in Rear		2	8 3/4	1/4	5/12	1 79/96
Do in Do		2	7	1/4	5/12	1 11/24
Do in Do		2	5 1/4	1/4	5/12	1 3/32
Do in Do		2	3 1/2	1/4	5/12	35/48
Do in Do		2	1 3/4	1/4	5/12	35/96
Whether boards		3	5 1/2	3 1/2	1/12	4 13/16
Total Cubic feet						84 13/16
Excavating & filling in Cyes						30
Gravel to spread outside all round near the Walls Cyes						11
Panelled Door		1	5	"	8	
Glazed Windows		3	5	"	3	
Do Ventilators		8	2 1/2	"	1 1/2	
Sundries & Superintendence at 5 percent						

(Sd) Alex. D. Clay Major
Executive Engineer at D—

Sub Dist Offices &c
Camp Masulipatam
25th May 1869

S. Mudeley
Superintending Engineer D &c

Lieut Col RE &c.

ABSTRACT ESTIMATE No. 7 of 1869/70

DISTRICT. Nellore

Work.

Constructing a Dead house for Hospital at Nellore

Quantity.	Description of Charges.	Rate.	Amount.	Total.
231	C.ft of Concrete @	a 1 9	254 3	
1934	C.ft. of Brick in Chunam @	a 2 6	302 3 a	
21	Sq.rs of Plastering with 2 coats of Chunam @	3 a a	63 a a	
21	D° of Whitewashing	a 4 a	5 4 a	
2 1/5	D° of Asphalte floor @	25 a a	55 a a	
7	D° of Roofing with Teak wood Rafters nails flat & pointed & Chunam Borders @	15 a a	105 a a	
85	C.ft. of Teakwood Wrought & put up	3 8 a	297 8 a	
30	C.rs of Earth Work @	a 1 a	1 14 a	
11	D° of Gravelling @	a 1 3	7 11 9	
1	Paunelled Door		60 a a	
3	Glazed Windows each	30 a a	90 a a	
8	D° Ventilators D	7 8 a	60 a a	
	Superintendence Establishment at 5 per cent		57 3 a	
	Total Estimate Rupees			1130 a a

(Sd) Alex. Dallas Major
Executive Engr. &c &c

Supd Engr's office 27th
Camp Masulipatam
25th May 1869

Sd/ J. Thuberty
Lieut. R.E.
Superintending Engineer 2d Div.

Rec'd

Civil Works

Pub Works Departt

No 2213

13

Proceedings of the Madras Government

Under date the 8th July 1869

Read the following

From the Secty Collector of Nellore, F. & E. No 1129 dt 15th June 1869.

The Government approve of the estimate of Rs 1130 for the construction of a Road Horse for the Hospital at Nellore, but as no funds are available the execution of the work must be deferred.

To

The Collector of Nellore

S. Engr 2nd Dn

Cuddapah & PO Accts

Accts Genl

Judicial Dpttt

Dept 9/7/69.

Rs 1130 Estimate for Road Horse for Hospital at Nellore

Transferred to the Public Works Department with reference to the orders in the Despatch dated the 19th March 1869 - G. Gos. No 829-69.

22nd April 1869.

Fort St. George
23rd June 1869

By Order
&c
&c

Transferred to the Public Works Department.

Under Secy to Govt

Rs 1130 Estimate for Road Horse for Hospital at Nellore

Dept Sanction dated 26th June 1869 R. 2213 dated 8th July 1869

Forwarded

The Chief Secretary to Govt

dated 15.6.69

dupt 16.6.69

Forwarded

Engr 2nd Dn

dated 1129

Forwarded countersigned an estimate for Rs 1130 for the construction of a Road Horse for the Hospital at Nellore and requesting that the work may be carried out with funds at present available with the Local Fund Committee of that Station

Executive Engineer

No 2213 - 8 July 1869

Examined

Asst Engr

Enc 2618

Govt. of {1869} Madras.

PUBLIC WCRKS.

To The Collector of Nellore

Dated

Read Encl 2

G. O. 8 July 1869, No. 2213

Nos. 168-169

Dead House Estimate Rs 1130 for the construction of a dead house for the Hospital at Nellore, approved with remarks-

Enc 2618 Encl 169 Rs 2 [illegible]

To the Public Work Department. Asst Engr Supt