M.R.O. 1—77,006—8-6-37.

(1) Number of pages 4

(2) Date of repair 22.11.43

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 2243 Press ~~Mis.~~

228-29

Dated 10. 7 1869.

Not to be folded or roughly handled

Cy

No. 228. Read the following letter from the Superintending Engineer, 6th Division, to the Secretary to Government, Public Works Department, dated Tanjore, 28th June 1869, No. 408 :—

I HAVE the honour to submit, for sanction, estimates for two dead-houses prepared in accordance with the standard plan received with G. O., No. 905, of the 19th March 1869.

2 Abstract Estimates.
1 Plan.

2. One of these buildings is to be attached to the Civil Dispensary at Combaconum* and the other to that at Tranquebar.† Lead sheeting has been provided for the floor ; this adds considerably to the estimate. Furniture has been provided for in the respective estimates.

* Rupees 1,480.
† ,, 1,560.

3. The sites selected being Government property, no compensation for land is required.

No. 229. ORDER THEREON, 10th July 1869, No. 2,243.

CIVIL WORKS, No. 35.

THE estimates are approved, but, as no money is available, the construction of the buildings must be deferred.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 6th Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Judicial Department.

Exd. F. R. Bantleman.

Govt. of (1869) Madras.

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER.

6TH DIVISION

&c &c, &c.

Dated July, 10th.

Read.

G. O., 10th July-1869, No. 2,243.

JULY.

Nos. 228-229

Dead houses.—Estimates, amounting to Rupees 3,040, for dead-houses to be attached to the Civil Dispensaries at Combaconum and Tranquebar, Tanjore District, approved with remarks.

Civil Building. New Work

Tanjore District

Estimate No 8 of 1869-70

Work Constructing a Dead House at Combaconum Standard Plan received with G. O. No. 905 dated 9 March 1869.—

No.	Particulars	Rate	Per	Amount	Rs.	Ans.	Pies.
533	Cft. of Brick in Chunam	2	Cft.	316	10		
37½	Sup. Cft. of lining floor with lead sheet 3lb. thick nailed with copper to the Teakwood Battens Embedded in the Grooves	1	Sft.	37	12		
725	Do of Roofing with flat & pan tiles & Chunam borders	98	Sq	68	14		
200	Do of Plastering with 1 Coat of Chunam	28		55			
1	Teakwood panelled door with framed Iron worker Complete 4½ × 8'	42	Each	42			
1	Do Glazed pan light over the above door panel 4½ × 1½	7		7			
3	Do glazed windows with panel Swinging Shutters Iron work & pulleys &c Complete 3' × 5'	15	Each	45			
3	Do Weather Boards, Bricks, Battens, Iron work &c Complete 3' × 7'	7		21			
18	Do Glazed Ventilators with framed Swinging Shutters Iron Tals pulleys &c Complete 2½ × 1½	9		72			
				Carried over	865	4	

Brought forward — 865 4 .

Teakwood Scantlings

107½ Cft. of Teakwood wrought & put up — @ 3 8 . Cft. 376 4 .

Teakwood Dissecting Table

3 17/32 Cft. Teakwood 6½ × 2½ × 2½ wrought & put up — 5 . . 17 10 10

16 7/8 Lbs. Lead sheet lining over Dissecting Table 3/16 inch thick with Copper nails — @ 1 . . Sqft. 16 4 .

2 Metallic Buckets — @ 7 . . Each 14 . .

1 Balance scale for Post mortem purposes — 15 . . Each 15 . .

1 Teakwood Spare dissecting table — 17 8 . . 17 8 . .

1 Teakwood Common table with drawers — 10 . . 10 . .

1 Arm chair — teakwood — 5 . . 5 . .

2 Teakwood Trestles for the support of Coffin — @ 2 8 . . 5 . .

12 — Do Blocks and Trudgers — @ . 4 . . 3 . .

6 Towel Pegs — . 3 . . 1 2 .

1 Teakwood Washing Stand (Camp Kitfood) with brass Basin — 10 . . 10 . .

Varnishing the doors, Windows & Ventilators with wood oil — 15 . . 15 . .

1 Lead Pipe with Cock 1½" in diameter 4' long to be fixed in the wall between Sink & outer Cistern — 10 . . 10 . .

Carried Down — 1381 10 10

Brought forward — 1381 10 10

1 Lead pipe 2½ long to be placed in one corner of the room as an out let in the floor 6" . . Each 6" — 1387 10 10

Excavation & filling — 10 . .

Scaffolding — 10 . .

Sundries & Contingencies — 72 5 2

Total Estimate Rupees — 1480 0 0

Engg Office 6th Dec
pre 17th June 1869.

Capt R.E.
Supt Engr 6th Div

Collector

Estimate for Building Quarters for Officers & Men at Fort Richardson 1880.

Carpenter Work.

Estimate of Lumber required for Building Officers Quarters at Fort Richardson as per Plan.—

Civil Building — 7D New York.

Fauquier District.

Estimate No 1869-70.

Work Constructing a Dead House at Fauquier on Standard Plan received with G.O. No 905, dated 19th March 1869.—

Quantity	Particulars	Rate Per	Amount	Amount of Each Part
3	Cft of Brick in Chunam	C. 26 Cft	395	12 6
3/4	Sup Ft of lining floor with lead Sheet 3/10 thick nailed with Copper to the Teakwood battens imbedded in the masonry	C 1	Sft 237	12
725	Do of Roofing with flat & pan tiles & Chunam bedding	9 8	"	68 14
2250	Do of Plastering with 1 Coat of Chunam	28	"	55 "
1	Teakwood Panelled door with frames Iron Hinges Complete 4½ × 8'	C 42	Each	42 "
1	Do Glazed fanlight over the above door frame 4½ × 1½	C 7	"	7 "
3	Teakwood Glazed windows with frames Swinging Shutters iron work & rope &c Complete 3' × 5'	C 15	"	45 "
3	Do Mattan Boarded Frames Battens, Iron Works &c Complete 3' × 7'	C 7	"	21 "
			Carried over	872 66

	Brought forward			872	66
8	Teakwood glazed Ventilators with punner swinging Shutters Cintels Rope &c Complete - $2\frac{1}{2}' \times 1\frac{1}{2}'$	9	Sft	72	
	Teakwood Seantling				
$107\frac{1}{2}$	Cft of Teakwood wrought & put up	38	Cft	3764	
	Teakwood dissecting Table $6\frac{1}{2}' \times 2\frac{1}{4}' \times 2\frac{1}{2}'$				
$3\frac{17}{32}$	Cft of Teakwood wrought & put up	5	Cft	17	1010
$16\frac{7}{8}$	Lead Sheet lining over dissecting table $\frac{8}{10}$ thick with copper nail	1	Sft	16	14
2	Metallic Buckets	7	Each	14	
1	Balance Scale for Postmortem purposes	15		15	
1	Teakwood Spare dissecting table $6\frac{1}{2} \times 2\frac{1}{4} \times 2\frac{1}{2}$	17	8	17	8
1	Teakwood Common table with drawer	10		10	
1	Arm-Chair Teakwood	5		5	
2	Teakwood trestles for the support of Coffin	2	8	5	
12	Do Blocks and Wedges	4		3	
6	Lowel Pegs	3		1	2
1	Teakwood washing Stand with trap basin Colmp Finish	10		10	
	Varnishing the Doors, Windows & Ventilators with wood oil	15		15	
	Carried Down			1450	134

	Brought forward			1450	134
1	Lead pipe with cock $1\frac{1}{2}$" in diameter. 4' long to be fixed in the wall between Sink and outer Cistern	10	Each	10	
1	do — do. $2\frac{1}{4}$' long to be placed in one corner of the Room as an outlet in the floor level	6		6	
				1466	134
	Excavation & filling			10	
	Scaffolding			10	
	Sundries & Contingencies			43	28
	Total Estimate Rupees			1560	

Engrs Office 6th
June 17th 1869

W. F. Oakes Capt. R.E.
Supdg Engr 6th Div.

John Morris
Collector

Supdg Engr Office 6 Div.
Tanjore 28th June 1869

№ 408

From Captain R. F. Oakes R.E.
Superintending Engineer
6th Division

To Colonel C. A. Orr R.E.
Secretary to Government
Public Works Depart.

Sir,

I have the honor to submit for sanction Estimates for two school houses prepared in accordance with the Standard Plan received with G.O. №905 of the 19th March 1869.

One of these Buildings is to be attached to the Civil Dispensary at Combaconum and the other to that at Pranquebar. Pradchatting has been provided for the floor, the walls considerably to the Estimate. Furniture has been provided for in the respective Estimates.

The sites selected being Government property no compensation for land is required.

I have the honor to be
Sir
Your most Obedt. Servt.

R. F. Oakes Captain R.E.
Supdg Engineer 6. Divn

Estimate Rs. 1356-
for Constructing Dr.
Lead House at
Pranguebar and
Tanjore Plans.

Public Works Department

No 2243

Proceedings of the Madras Government

Under date the 10th July 1869

Read the following

From The Supg Engr 6th Dn No 408 dated 28th June 1869

Recommending for sanction the estimates amounting to Rs 1480 and Rs 1560 for constructing Dead houses at the Civil Dispensaries at Cumbaconum and Tinnevelly

Submitted

WDM

Recd 12/7/69

Sent to Supg Engr 6th Dn
" Civil Surgeon, Cumbaconum
" Tinnevelly
" Architect
" Public Works Dept

3 5
5

P.C. 1869 Dept
Dated 10th July
from Govt P.W.D. 2406
The Supg Engineer
6th Dn
To
The Secy to Govt
P.W.D.

Dated 28th June 1869.
Recd 30th " "

No 408.

Dw 3

Forwarded for sanction two Estimates, Rs 1480 and Rs 1560 for constructing Dead Houses for the Civil Dispensaries at Cumbaconum and Tinnevelly.

No 2243: 10th July 1869.

No 228.
3rd July 1869 R.Gn

Rec 2700

Govt. of {1869} Madras.

PUBLIC WORKS.

To The Superintending Engr.
6th Division

Dated

Recd Encl. 3

G. O. 10th July 1869, No. 2243.

Nos. 228-229

Dead Stones Estimates amounting to Rs 3060 for dead stones the attached Civil Dispensaries at Combaconum and Tanjore &c, approved with remarks.

c 22 July 1869 R. Bn