

(1) Number of pages 10(2) Date of repair 19-12-1870

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Publicwork. DEPARTMENT.

G.O. No. 3087

Press
Mis.

410-11

Dated 19-12-

1870.

Not to be folded or roughly handled

1

*Proceedings of the Madras Government, Public Works Department,
19th December 1870.*

No. 410. Read the following letter from the Acting Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 29th November 1870, No. 187 :—

In reference to G. O., No. 3,820, of the 4th December 1869, I have the honour to forward, for the sanction of Government, from the Reserve under "Communications" of 1871-72 an estimate, amounting to Rs. 9,760 (accom-

panied by plan and specification), for re-constructing the four arches (lately fallen down) of the Shapakum bridge on Trunk Road No. VIII., on the road from Madras to Trichinopoly, in the South Arcot District.

2. The plan and estimate have been approved by the Collector of the District.

No. 411. ORDER THEREON, 19th December 1870, No. 3,087.

CIVIL WORKS, No. 31.

THE Government sanction the estimate of Rupees 9,760 for the re-construction of the fallen arches of the Shapakum bridge on the road from Madras to Trichinopoly in the South Arcot District.

2. The Superintending Engineer will apply for the necessary funds after the 1st April next when the question of providing them from the Reserve will be considered.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Acting Superintending Engineer, 5th Division, with Specification.
,, Controller of Public Works Accounts.

Erd. S. T. Augustin.

Communications.

South Arcot District.

N^o 4 Range.

Vidachellum Talook.

Abstract Estimate of 1870-71.

Work. — Reconstructing the 4 arches / lately fallen down / of the Sapankum Bridge in the 135th Mile of Imperial Road N^o II.

Quantity	Description of work	Rate	Per	Amount	Total
112	Wells 3 feet diameter and 5 deep	15	8	Each	1736
20876	Cubic feet of Brick in chunam work	2	6ft		2609 8
5660	Do. of Archwork	3	Do.		1061 4
218	Squares of Plastering two coats.	2	8	Sqrs	545
4	Centrings	248	8	Each	994
16588	Cubic feet of Removing old work	1	6ft		1036 12
12	Cubic yards of Rough stone in chunam	2	4	Cyd.	27
	Excavating foundation and temporary Dam				500
	Baling water				764 8
					9274
	Sundries and Superintendence at 5 per cent				486

Total Amount of Estimate Rupees. — 9760
Rupees Nine thousand seven hundred and sixty only.

N^o 4 Range Office S. Arcot.
Mainambady, 5th October 1870.

Chieuli Seal
Collector of South Arcot

/ Signed / P. C. Norfor
Executive Engineer
N^o 4 Range, S. Arcot.
P. C. Norfor
Executive Engineer
for
Actg. Superintending Engineer 5th Div.

No. 187.

Superint. Engin. Office, 5th Div.,
Cuddalore, 29th November 1870.

From,

The Asst. Superintending Engineer,
5th Division.

To,

The Secretary to Government,
Public Works Department.

Sir,

Enclosures 3.

Plan

Estimate

Specification.

In reference to G. O. No. 3820 of the
1st December 1869, I have the honor to forward,
for the sanction of Government, from the Reserve,
under "communications" of 1871-72, an estimate
amounting to Rs. 9,760 (accompanied
by plan and Specification) for Reconstructing
the 4 arches (lately fallen down) of the
Shapuram bridge on Trunk Road
No. VIII, on the road from Madras to
Trichinopoly, in the South Arcot District.

2.

The plan and estimate have been
approved by the collector of the District.

I have the honor to be

Sir,

Your most Obedient Servant.

W. M. J.

Executive Engineer,

and Superint. Engineer.

5 Divisional O. & S. M.

South Arcot District

N. L. Bangee.

Rs. 9,760

Reconstructing the 4 arches (lately

fallen down) of the Shapuram

bridge in the 135th mile of the

Imperial Road No. II.

Amount of Estimate Rs. 9,760.

Public Works Department

No 3087

Proceedings of the Madras Government

Under date the 19th Decr/70.

Read the following

From The Ag Supr Engineer } H.E. No 187 of 29th Novemr/70
5th Decr

The Government

sanction the estimate
of Rs 9,460 for the recon-
struction of the fallen
arches of the Shapaham
bridge on the road from
Madras to Trichinopoly
in the South Arcot District.

The Supr Engineer
will apply for the necessary
funds after the 1st April
next when the question
of providing them from
the Reserve will
be

Received
From the Ag Supr Engineer
H.E. No 187 of 29th Novemr/70
The Dy Superintd Engineer,
S. Arcot District.

Secy to Govt,
Madras.

Dated 29th
Decr 1870

18 Decr 1870

Enclosure 3.

Shapaham bridge.

Enclosure, see estimate
of Rs 9,460 for reconstruction
of the Shapaham bridge
on the road from Madras
to Trichinopoly.
No 3087-19 Decr 70

ADH

639 Decr 70

105 Dec 11/70

he considered.

W.B.

105 Dec 11/70

25-
Lo.

The Supr Cud 5" Du
5" Controller P. W. Acc 5"

63 Dec 170 B. 62

Dec 20/2/70

he considered.

(10) 12.1.82

Govt. of Madras.

PUBLIC WORKS.

To Secy. Engineering Engrs.
S. P. (Civil)

Dated

Recd.

Feb. 2

G. O. 17 Dec 1870, No. 3667

NOB. 111411

Shahar River Bridge - The est.

Male of King's for the reconstruction of the fallen arches of the Shahar River Bridge on the road from Madras to Krishnapur in the South Arcot District, situated in the river.