M.R.O. 1—77,006—8-6-37.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 456	Press / ~~Mis.~~
156-57	
Dated 9 2	1870.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
9th February 1870.

No. 156. Read the following letter from the Officer in charge of Public Works Operations in the Wynaad, to the Secretary to Government, Public Works Department, dated Vythery, 6th January 1870, No. 10:—

With reference to G. O., No. 2,704, dated 17th August last, I have the honour to forward an estimate, amounting to Rupees 1,610, countersigned by the Superintendent of Police, South Malabar, for constructing two Police huts at Nudghanny, for which a grant was given in the above G. O. pending submission of estimate.

2. The estimate has been drawn out from the standard plan, dated November 1867.

No. 157. Order thereon, 9th February 1870, No. 456.

CIVIL WORKS, No. 26.

Sanctioned, but the attention of the Inspector-General of Police and of Major Kennedy will be specially drawn to paragraph 2 of the orders in this Department, No. 3,994, dated 20th December 1869.

(True Extract.)

(Signed) CHARLES A. ORR, Colonel, R. E.,
Secretary to Government.

Wynaad Division
Malabar District

Estimate of probable cost of constructing 2. Police huts at Kadgunny.

Measurement. L.	B	D	Calculated contents	Superficial Contents.	Description of work	Rate	Amount of each Item	Total
					Foundation			
59	2¼	2½	331⅞		Principal Walls			
45⅓	1⅝	1½	110½		Cross walls of rooms			
15¼	1⅞	1½	38 11/24		Wall between passages			
35⅞	1⅜	1½	86 107/128		Back wall			
32⅛	1⅞	1½	81 207/256		Cross side walls of Courtyard			
¾	1⅞	1¼	1 57/128		yards 53			
85½	1¼	1½	66⅞		Verandah			
					Basement.			
68	2	½	68		Principal walls			
46	1¼	½	28 3/4		Cross & side walls of rooms			
15¼	1¼	½	9 17/32		Wall between Passages			
35¼	1¼	½	22 1/8		Back wall			
34⅞	1¼	½	21 22/44		Cross & side walls of Courtyard			
35¼	1	½	17 7/8		Verandah			
					Superstructure			
56	1½	8/8	686		Principal walls			
45	1	8/8	392		Cross side walls of rooms			
15	1	5	75		Wall between passages			
35	1	5	175		Back wall			
36	1	5	180		Cross side walls of Courtyard			
60	1	2	120		Gable Walls			
			2504					
			54		Deduction			
			2450		Total Brick in chunam Mortar 20/27 Cft.	9 " Cft.	816 10 8	
					Plastering			
				416	Principal Walls inside			
48	"	8⅔		432/3	do do out side			
56	"	7⅔					816 10 8	
				484⅔	Carried over			

Measurement. L	B	D	Cubical Contents	Superficial Contents	Description of work	Rate	Per	Amount of Each article	Work
				845½	Brought over				816 10 5
108	-	8/6		882	Cross side walls both sides				
30	-	5		150	Wall between passages				
20	1	-		20					
35	-	5		175	Back wall outside				
35	1	-		35	do do top				
32	-	5		160	do do inside				
72	-	5		360	Cross inside walls of court.				
72	-	1		72	do do over				
				60	yard Inside of door & windows				
120	-	2		240	Gable ends				
234/4	-	1/2		47 3/5	Basement				
				3117					
				96	deduction				
				3021	Total Plastering in 19/24	4	- -	1gross	120 13 5
					Flooring				
23	10¾			270¼	Rooms				
30	2¾			82½	Passages				
35½	2¾			97	Verandah				
				449¾	Total in Superficial ft	15	- -	do	67 7 5
89	25			975	Roofing over Rooms passages Verandah	40	- -	do	390 - -
					Wood work				
55	5/12	2/8	15 5/14		Bressummers				
58	1/2	1/4	7 1/4		Wall plates				
26¼	½	½	6 9/16		Pillars				
35	1	1/4	8 3/4		Foot board for Pillars				
			40 97/144		Total Cubic ft 1 12 - cft				70 - -
					carried over				1464 15 6

Measurement. L	B	D	Cubical Contents	Superficial Contents	Description of work	Rate	Per	Amount of each article	Work
					Brought over				1464 15 6
					Excavation				
60	2½	2½		375	Principal walls				
44	2	1½		132	Cross side walls of rooms				
16	2	1½		48	Wall between passages				
36	2	1½		108	Back wall				
33	2	1½		99	Cross side wall of Verandah				
36	1½	1½		81	Verandah Walls				
				843	Total Cubic ft or 31 2/3 Cyds	4	- - Cyd		7 12 8
					2 Batten doors	15	- - Each		30 - -
					2 Windows with wooden bars	10	- - do		20 - -
					2 large Padlocks to doors	3	8 - do		7 - -
									152 12 2
					Sundries @ 5%				80 3 10
									1610 - -

Total for one Block of 12 Rooms.

M.E. Ex: Engrs Office
Wynaad, Mysthery
25th December 1864

Robt. W. Kennedy. Major
Special Executive Engineer Wynaad.

Henry Cunningham Capt.
Supt. by Police
South Malabar.

Special Executive Engineer's Office
Wynaad, Puthery
the 6th January 1870.

No.

To,
The Special Executive Engineer
Wynaad

Sir,

I have the honor to forward herewith for your information and guidance a copy of a letter from the Secretary to Government in the Public Works Department, No. 2704 dated 21st December 1869, intimating the sanction of Government to the construction of two Police Huts at Nadgherry in the Wynaad Taluk.

2. The Estimate for the above mentioned huts is under preparation and will be submitted for sanction in due course.

I have the honor to be
Sir
Your most obedient servant
Robt. Wm. Kennedy Major
Special Executive Engineer
Wynaad.

Malabar District
Wynaad Division

Copy letter from Supt.
Executive Engineer, Wynaad
No 519. Dated 25 December
1869.

Dated 25 December 1869
Received

Estimate for Constructing
2 Police huts at Nadgherry

No. 1870 Despatch
from Gd Hope
The Special Executive
Engineer Wynaad
To
The Secretary to
Government
Department Pub. Works
Madras

Dated 6th
Rec'd 10th January 1870.

No 10.
Enclosures.
Forwards an
Estimate for constructing
Police Huts at Wynaad
Ghaut.

No 456 9th Feby 1870
Write an Order

Cancelled

No 456

Sanctioned, but the attention of the Inspector General of Police and of Major Kennedy will be specially drawn to para 2 of the order in this Department No 3994 of 20th Dec 1869.

W. N.

Fort St. George
9th Feby 1870

To
Major R. B. Kennedy
Controller of Police
Acc. Genl
Judl Dept
Inspector Genl of Police

Desp 9/2/70

Rec'd 15th January 1870 R. 3rd Feby

Dec 84

Govt. of Madras.

PUBLIC WORKS.

To Major R. B. Kennedy

Dated

Rec'd. 2nd.

G. O., 5 Feb 1870, No. 456

Nos. 156-157

Police Roads. Estimates for the Police Roads in the Agency tracts in the Nilgiris, Coimbatore Districts.