M.R.O. 1—77,006—8-6-37.

(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 627 Press -Mis.

487-88

Dated 24 . 2 1870 .

Not to be folded or roughly handled

No. 487. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated camp at Aulapaukam, 1st February 1870, No. 179:—

WITH reference to G. O. of the 21st April 1869, No. 1,318, I have the honour to forward, for the sanction of Government, a revised estimate of Rupees 3,360, accompanied by plans and specification, for improvements and additional wards to the Subsidiary Jail at Kullakurchi in South Arcot.

1 Plan:
1 Site-plan.
1 Estimate.
1 Specification.

2. When I passed through Kullakurchi last year I ascertained that the available space at the back of the Cutcherry was not sufficient for all the new buildings, as may be observed from the site-plan. A sum of Rupees 100 is therefore provided in this estimate for compensation for the additional ground required, and there will be now sufficient ground for all the wards, and the out-houses will not be too crowded.

3. An outlay of Rupees 686 was incurred in collecting materials for the work which is now at a stand-still, under the recent restrictive orders. I purpose to include this in my List of Incomplete Works due in April next, in case of the Government according sanction to the revised estimate.

No. 488. ORDER THEREON, 24th February 1870, No. 627.

CIVIL WORKS, No. 58.

THE Government sanction the revised estimate of Rupees 3,360 for additions and improvements to the Subsidiary Jail at Kullakurchi in the South Arcot District.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 5th Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Judicial Department.

Exd. F. R. Bantleman.

Govt. of {1870} Madras.

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER,

5TH DIVISION.

&c., &c., &c.

Dated February 24th.

Read. *Encl.*

G. O., 24th February 1870, *No* 627.

FEBRUARY.

Nos. 487-488

Subsidiary Jail at Kullakurchi.—Revised estimate of Rupees 3,360 for additions and improvements to the Subsidiary Jail at Kullakurchi in the South Arcot District, sanctioned.

Supg Engrs Office, 5th Div.

№ 179. Camp Ankalaparamma, 1st February 1870.

From

The Superintending Engineer

5th Division.

To

The Secretary to Government,

P.W.D.

Sir,

Enclosures 4.
1 Plan.
1 site plan.
1 Estimate.
1 Specification.

With reference to G.O. of the 21st April 1869, № 1318, I have the honor to forward for the sanction of Government a revised estimate of Rupees 3,360 accompanied by plans and specification for improvements and additional wards to the subsidiary Jail at Kullakurchi in South Arcot.

2. When I passed through Kullakurchi last year, I ascertained that the available space at the back of the Kachari was not sufficient for all the new buildings, as may be observed from the site plan. A sum of Rupees 100 is therefore provided in this estimate for Compensation

for the additional ground required, and there will be no sufficient ground for all the wards, and the out houses will not be too crowded.

3. An outlay of Rupees 686 was incurred in collecting materials for the work, which is now at a stand still, under the recent restrictive orders. I purpose to include this in my list of incomplete works due in April next, in case of the Government according sanction to the revised estimate.

I have the honble
Sir,
Your most obdt. servant

E A Ward Colonel, R.E.,
Superintg. Engineer.

C.P. 1870 Dept
From (5) No 4550
The Superintg. Engineer,
5th Division.

To The Secy to Government,
P.W.D.

Dated 1st February 1870.
Recd 3 " "
No 179.
Enclosures 4 #

Subsidiary Jail at
Kullakurichi.

Forwarding for
sanction a revised
estimate of Rs 3360 for
improvements and
additional wards to
the Subsidiary Jail
at Kullacurichi in
South Arcot
No 627 - M. Feby 1870

C. 9. July 1870 No. 18.

New Works.

Civil Buildings — 5th Division P.W. — No 3 Range — Kullacurichi Taluq
South Arcot District

Abstract Estimate of 1869-70

Work — Constructing a subsidiary jail with out houses at Kullacurichi.

Quantity	Description of Work	Rate	Per	Amount		
	Verandah & Jail Wards.					
31 2/3	Cubic yds. Concrete below foundations including excavation and filling in	1 14	Cft	56	9	
72	Cubic yds Rough stone in chunam in foundations & Basements	2 . .	"	144	.	
128	—do— Masonry in —do— in superstructure	3 . .	"	384	.	
197.08	Squares tiled roofing including ridges & chunam borders	13 8 .	dpc	257	9	3.
7.20	—do— laying with asphalte 3/4 thick	18 . .	do	129	9	
7.20	—do— Levelling course of bricks under do.	2 . .	do.	14	6	5.
4.29	—do— flooring with bricks 8" square in chunam	6 8 .	do.	27	4	2.
31.68	—do— Interior Plastering	2 8 .	do	79	3	2.
21.30	—do— Exterior Pointing	1 4 .	do	26	10	.
90.	Cubic feet Palmyrah wood	2 12	Cft.	247	8	.
55	—do— Teak wood	3 4 .	do.	178	12	.
4	Iron gratings with frames 7X3½	30 . .	do.	120	.	.
1	—do— —do— 7X4	31 . .	do	31	.	.
12.	Iron Ventilators without do. 5X2	9 . .	do.	108	.	.
	Superintendence			40	.	.
	Sundries			52	1	5
				1900	.	.
				1900	.	.

Carried over

Brought over — 1900.

Hospital Sheds.

13⅓	Cubic yds Concrete below foundations including excavating & filling in	1	14	Cyd. 25	
33.	—do— Rough stone in chunam in foundations and Basement	2		do 66	
41	—do— Masonry in —do— in Superstructure	3		do 123	
7.70	Squares Tiled (roofing) including peepers and Chunam borders	13	8	Sqre 103	15 2.
4.30.	—do— Saving with asphalte ¾ thick.	18		do 77	6 5
4.30	—do— levelling course of bricks under do	2		do 8	9 7
6.68	—do— Interior Plastering.	2	8	do 16	11 2.
6.89	—do— Exterior Pointing	1	4	do 8	9 9
29	Cft of Palmyrah wood	2	12	Cft. 79	12.
48½	Do. — Teakwood	3	4	do 157	10.
5	Cots 6x2.	10		Each 50	
	Superintendence				20
	Sundries.				23 5 11.

766.

Cook Room.

4½	Cubic yds Concrete	1	14	Cyd. 8	7.
2	Squares of Rough stone in chunam flooring 1½ feet thick	11		Sqre 22	
11	Cubic yds brick in mud	2	2	Cyd. 23	6.
2.52	Squares Tiled roofing including peepers & Chunam borders	13	8	Sqre 34	4
12⅓	Cubic feet Palmyrah wood	2	12	Cft. 33	14 8.
10 11/12	— do — Teakwood	3	4	do 35	7 8.
	Sundries				12 12 4

170.

Carried over — 2830.

Brought forward — 2,830

Latrine.

4	Cubic yards Concrete.	1	14	Cyd. 7	8.
34 9/4	—do— brick in mud	2	2	do 73	3 1.
14 2/9	—do— do in Chunam	3		do 42	10 8
5.25	Squares Tiled roof including peepers & Chunam borders	13	8	Sqre 70	4.
18⅓	Cubic feet Palmyrah wood	2	12	Cft. 51	5 4
22 7/8	—do— Teakwood	3	4	do 74	5 6
	Sundries.				10 1 5

330.

Deepening & repairing one well — 100.

Purchase money of ground required — for site &c — 100.

Total of Estimate Rupees. 3360.

No 3 Range Office South Arcot.
Kallacurichi
9th November
1869

[Sgd.] George C. J. Barnardo; B.A.
Assistant Engineer.

Edmd Beale R.E.
Superintg. Engineer.

Chas Beale
Collector of South Arcot.

P. W. Department.

No 627

Proceedings of the Madras Governm

Under date the 7th Feby 18

Read the follow

From The Superintending Engr 5th Division } H.E. No 179 of 1st Febuary 18

To the Secretary to Govt
P.W.D.

Fort St George

Abstract Estimate for Construction of Thatched Kitchen Shed & Privy at Kullacoorchy in the South Arcot District

Amount of Estimate Rs 3360

The Govern

sanction the perused e

:timate of Rs. 3360

for additions and im

:provements to the Sub.

:ordinate Jail at

Kullacoorchy in the

South Arcot District

5 Engr 5 Div. with Specifn

Accts

Engr

Cue 458

Govt. of 1870 Madras.

PUBLIC WORKS.

To

Dated 5

Rec'd. Encl.

G. O., 11th Feby 1870, No. 627

Nos. 487 & 488.

Subsidiary Jail at Kullacoorchy

Revised Estimate for Rs 3360 for additions and improvements to the Subsidiary Jail at Kullacoorchy in the S. Arcot Dt, Sanctioned

Cy. Feby 1870 N. 18