M.R.O. 1—17,6/2—9-50.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Reference_____

MADRAS RECORD OFFICE.

Government of Madras.

DEPARTMENT.

G.O. No. Press / Mis.

Dated 18 .

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 15th September 1870.

No. 249. Read the following letter from the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department, dated Bellary, 30th August 1870, No. 63 B. :—

I HAVE the honour to forward, for the sanction of Government, the accompanying plan, report, and estimate, amounting to Rupees 295, for constructing a corrugated iron verandah to the hospital at Ramandroog Depôt.

2. The necessity for this verandah is to replace a thatched one which was destroyed by storm on the 7th May last.

3. The estimate, etc., have been approved of by His Excellency the Commander-in-Chief, and as funds are available under the head "Minor New Works, Military," I request that the work may be sanctioned for execution from this source.

No. 250. ORDER THEREON, 15th September 1870, No. 2,216.

MILITARY WORKS, No. 15.

SANCTIONED, the charge being met from the source indicated by the Superintending Engineer.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division.
,, Controller of Public Works Accounts.
,, Military Department.

Exd. S. T. Augustin.

A.A.G.
Q.M.G.

Camp Nuspett 12th July 1870

Executive Engr

ABSTRACT ESTIMATE.

Bellary District.

Work Constructing a Corrugated Iron Verandah to the Hospital at Ramandrug. Vide Sup Engrs No 308 D/ 10th of May 1870. & Letter from the Offg Comg to the Engr D/ 9th Idem

Quantities.	Description of Work.	Rate.	Amount.	Amount of each part.
244½	Cft. Stone in Chunam.	a 2 6	38 3 3	
192	Sft. Plastering with 2 Coats of Chunam. & Sqrs	4 10 a	8 1/4 1	
85	Sqrs ft. Granite Slabs. Sqrft	a 2 8	14 2 8	
18	Cft. Teakwood wrought & put up.	5 a a	90 a a	
414	Sqrs ft. Corrugated Iron Roofing with Screws. Sqrs	30 a a	124 3 2	
57/9	Cycs Earth work.	a 4 a	1 4 5	
//	Rafter Nails 6" Each	a a 3	a 2 9	
	Black Smiths Iron Work for Securing	a a a	2 a a	
	Inserting Rafters in walls and Refilling.	a a a	1 6 a	
			280 4 4	
	Sundries & Superintendence 5 per Cent		14 11 8	
	Total Estimate Rupees		295 a a	

Passed for Rs 295 a a

Offg Dy Asst Genl Engr

Madras 17th August 1870

W. Mackenzie Lieut Col RE.
Supdg Engineer &c &c.

Hospett Ramapoorum
Camp Hospett
12th July 1870

Executive Engr

A.A.G.
Madras

No. 63/42. Superintending Engineer's Office.
3rd Division.
Bellary 30 August 1870.

From,
The Superintending Engineer
3rd Division.

To,
The Secretary to Government
Public Works Department
Fort Saint George

Sir,

I have the honor to forward for the sanction of Government the accompanying Plan Report and Estimate amounting to Rs 295-4- for constructing a verandah to the Hospital at Ramandroog Depôt.

2. The necessity for this Verandah is to replace a thatched one which was destroyed by storm on the 9th May last.

3. The Estimate &c have been approved by His Excellency the Commander-in-Chief and as funds are available under the head "Minor Works" I request that the "Works Military" may be sanctioned for execution from this source.

I have &c
(Signed) Lindsay Lt Colonel
Executive Engineer
for Superintg. Engineer 3 Divn

Enclosures.
1. Plan
1. Report
1. Estimate
3.

Received 3 Aug 1870.
Registered

Abstract Estimate
Amount 295-4-
for Constructing a Verandah from the Hospital at Ramandroog

R.F. 1870 - 7K. Dept.

From,

No 345

The Superintending Engineer

3rd Division.

To,

The Secretary to Government

Public Works Department.

Fort Saint George.

No. 63.

Dated 30 August

Received 2nd Sept. } 1870.

Enclosures 3.

No 2216 - 15 Sept 70

Forwarding ff 6s

Sanction Plan Report

& Estimate - Rs 295/-

for constructing a

Corrugated Iron

Verandah to the

Hospital at Poonan

- drog ff

With an Order.

No 2216 Received, the Plan Report & Estimate mentioned in the Margin, which are returned herewith.

Superintending Engineer.

3rd Division.

16/9/70

Recd 15 Sept 70 Rep 9

C/3451

Govt. of Ceylon Building

PUBLIC WORKS.

The Superintending Engr
3rd Circle

15 Sept 2216

969-257

Hospital at Ramanathan's

The estimate Rs. 295 for
constructing an Corrugated
Iron roofed Verandah to
the Hospital at Raman-
athan's sanctioned.