M.R.O. I—77,006—8-6-37.

(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

# MADRAS RECORD OFFICE.

## Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 62 Press —Mis.—

125-26

Dated 10 1 1871.

***Not to be folded or roughly handled***

*Proceedings of the Madras Government, Public Works Department, 10th January 1871.*

No. 125. Read the following letter from the Acting Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Dowlaishweram, 16th December 1870, No. 3,176:—

ADVERTING to G. O., No. 2,527, of 24th October 1870, I have the honour to forward herewith an estimate, accompanied by a plan, amounting to Rupees 3,000, for the additions and alterations to the building now occupied by the Superintending Engineer's Office, 1st Division, at Dowlaishweram, and to request that the necessary sanction of Government may be obtained for the same.

1 Plan.
1 Estimate.

2. In the event of the estimate being sanctioned by Government, I have to request that the necessary funds may be placed at my disposal from the Reserve of the following year.

---

No. 126. ORDER THEREON, 10th January 1871, No. 62.

CIVIL WORKS, No. 10.

G. O., No. 2,310, dated 23rd September 1870.
" " 2,527, " 24th October "

ADVERTING to the orders marginally noted the Acting Superintending Engineer of the 1st Division submits with this letter an estimate of Rupees 3,000 for alterations and additions to the building now occupied as his office.

2. His Excellency the Governor in Council sanctions the estimate and will take into consideration the practicability of providing funds on an application being made by Major Fischer after the 1st April next.

(True Extract.)

Colonel, R.E.,
*Secretary to Government.*

To the Acting Superintending Engineer, 1st Division.
" Controller of Public Works Accounts.

Exd. S. T. Augustin.

Supg: Engineers Office 1st Dn
Dowlaishweram 16th December 70

No. 3176

From

The Actg: Supg: Engineer
1st Division

To

The Secretary to
Government P.W.D.
Madras

Sir,

Adverting to G.O. No. 2537 of 24th October 1870, I have the honor to forward herewith an Estimate accompanied by a Plan amounting to Rs. 3,000 for the additions and alterations to the building now occupied by the Supg: Engineers Office 1st Division at Dowlaishweram, and to request that the necessary sanction of Government may be obtained for the same.

2 In the event of the Estimate being sanctioned by Government, I have to request that the necessary funds may be placed at

any

my disposal from the Reserve of the following year.

I have the honor to be
Sir
Your most obedient Servant
Wm. T. Sherman Maj. R.E.
Ag. Supg. Engineer 1st. Division

5

my disposal from the Revenue of the following year.

MENT

NEW-WORK.

ABSTRACT ESTIMATE No.

TALUQ Rajahmundry

DISTRICT Godavery

Additions and Alterations to the Late District Superintendent's now Occupied by the Superintg Engrs Office 1st Divn at Dowlai

| Description of Work. | Rate. | per Item. | Amount. | Total. |
|---|---|---|---|---|
| Squares of Underoofing | " 12 " | Sqr | 12 8 5 | |
| Cyds of Removing Walls | " 8 " | Cyds | 34 2 8 | |
| do of Opening 3 Windows into old walls in Cuskroom | 1 " " | do | 3 5 4 | |
| Removing the terraced ruined Buildings | | | 30 " " | |
| Cyds Roughstone work in Chunam | 5 " " | do | 377 | |
| do Brickwork in chunam plaistering | 4 3 6 | do | 45 " " | |
| do Brickwork in Chunam | 3 " " | do | 512 | |
| Squares flooring with brick on Edge in Chunam and plastering 2 Coats Chunam | 10 3 " | Sqr | 127 9 7 | |
| do plastering 2 Coats Chunam and White washing | 2 7 6 | do | 205 1 2 | |
| Cyds Cut Stone in Chunam to Steps | 10 " " | Cyds | 36 10 8 | |
| 6 ft Countrywood Wrought & and put up | 1 8 " | Cft | 477 12 | |
| Squares Roofing with flat & pantiles and Chunam borders | 7 4 " | Sqr | 226 8 5 | |
| do Retiling with ⅓ of flat & pantiles of Front Verandah Old roof | 2 12 " | do | 20 10 " | |
| Carried Over | | | 2108 4 3 | |

No 1870 Deputy
Dr No 3176 for Jany
Cr No 5231
From the Supg Engr
1st Divn
To
The Secretary to Govt
P.W.D. Madras
Dated 16th December 1870
Received 24 do 1870
Forwards for sanction
of Government Estimate amounting
to Rs 3000 for additions
and alterations to the
Building occupied
by Supg Engineers Office
with Conclusion

No 125
6 Civil/71 Dt 9-1-71

No 62 - 10 Jany 1871

| | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Brought forward | | | 2108 | 4 | 3 | | | | Brought Over | | | 2218 | 7 | 5 |
| 3.68/100 | | Iguares Ridge ventilators to the roof in the Country wood rafters, & rafters with uprights, flat and pan tiles and Chimanbo | | 15 | " " | Pcs | 55 | 3 | 2 | 2 | | New Teakwood battened windows (3×3.4) with frames and Iron fixtures & ea to Plans & Library room | 10 | | each | 20 | |
| 3 | | Old Battened doors, 2×4.8×7 and 1×3.6×7. of the ruined terraced building to be repaired and fitted to record and Stationary rooms | | 3 | " " | each | 9 | " | | 6 | | New teakwood Battened windows with wooden bars frames and Iron fixtures & ea Complete to Stationary and Record Room (4×5) | 12 | " " | do | 72 | |
| 1 | | Teakwood New panelled door (3½×7) with frames and Iron fixtures & ea to plans and Library room | | 20 | " " | do | 20 | | | 14 | | Old Teakwood panelled windows (4×5) to be filled with glass Shutters inside to the drawing room with 16 glassed Shutters, to be from Ends of drawing room and Clerks rooms | 3 | " " | do | 12 | |
| 1 | | Old battened door (3.4×6.3) of the present press room to be repaired and fitted to the proposed press room | | 3 | " " | do | 3 | | | 3 | | New Teakwood panelled windows (5×5) Shutters to one side and glassed Shutters to inside with frames and Iron fixtures to Clerks room newly opened | 24 | " " | do | 72 | |
| 1 | | Old Battened window (3×5) of the present press room to be repaired and fitted to the Mathematical Instruments Room | | 2 | " " | do | 2 | " | | | | Putting Bamboo battens with hooks round the building | | | | 80 | |
| 1 | | New Teakwood battened window (3×5) with frame and Iron fixtures & ea Complete to the Mathematical Instruments Room | | 12 | " " | do | 12 | " | | | | Excavating foundations & filling in basement &c | | | | 30 | |
| 6 | | Old battened windows (3×3.4) of the ruined terraced building to be repaired and fitted to the proposed press and Plan Room | | 18 | " " | do | 9 | " | | | | Carried Over | | | | 250 | 7 5 |
| | | | | | | | 2218 | 7 | 5 | | | | | | | | |

| | | | |
|---|---|---|---|
| Brought Over | 2504 | 7 | 5 |
| Contingencies | 255 | 8 | 7 |
| | | | 2760 |
| Add the Amount for Repairing the Existing building with Country wood Rafters Rafters Reepers Plah and Pantiles where required and Plastering and Whitewashing and Repairing Cracks &c &c | | | 240 |
| Total Estimate Rs. | | | 3000 |

Superintdg Engrs
Office 1st Division
Dowlaiswaram
14th December
1870

Lieut. Taubman Major R.E.
Acting Superintdg Engr 1st Div.

Ellis Captain Colonel &c &c &c
Sir
I have the honor to forward herewith for the orders of Government the accompanying Estimate for Rs. 3000 for alterations and additions to the building now occupied as the Office of the Superintending Engineer 1st Division Godavery
I have &c &c &c
(Signed) W. Taubman Lieut.
Acting Superintdg Engr 1st Div.

Dft. 5234/70

Dft. Dept

No. 6252

Proceedings of the Madras Government
Under date the 16 January 1871
Read the following


From the Actg Supdg Engr
1st Div
Dated 14 Dec
Received 16 Dec 1870

Y. O. No 2310 of 23 Sept/70.
" " 2527 " 24 Oct/70.

Adverting to the orders marginally noted the Actg Supdg Engineer of the 1st Division submits with this letter an Estimate of Rs. 3000 for alterations and additions to the building now occupied as his Office

His Excellency the Governor in Council sanctions the Estimate & will take into consideration the practicability of providing funds on an application

being made by Major Fischer
after the 1st April next.



To Lieut. Col. Dr.
Controller, R.W. Accts.

Dec'd 23/11/71

66 Long/71 Q 99

Lieut. Col. Dr.

No. 5234

Govt of {1871} Madras.

PUBLIC WORKS.

To The Actg Superintending Engr
1st Circle

Date 1

Recd. 2

G. O. 10 Jany 1871. No. 62

Nos. 1258 126

Build Mr. The estimate
P.Rs. 3000 for alterations
& additions to the Court House
occupied by the Office
of the Asst Collr & Sub
Collr sanctioned with
remarks.