M.R.O. I—77,064—8-9-38.

(1) Number of pages

(2) Date of repair

(3) Initials of the Reference

MADRAS RECORD OFFICE.

Government of Madras.

DEPARTMENT.

G.O. No. 723 Press Mis.

Dated 27 18

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
27th June 1871.

No. 480. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 17th June 1871, No. 69 .—

I HAVE the honour to submit, for the sanction of Government from the grant of Rupees 3,000 for Minor New Works under Military at Bangalore, the undermentioned estimate :—

1 Estimate
1 Specification.

Constructing V shaped drain in rear of cook room, in lieu of square drain at the hospital occupied by 21st Fusiliers, Rs. 120

2. The estimate has been approved of by His Excellency the Commander-in-Chief.

No. 481. ORDER THEREON, 27th June 1871, No. 1,723.

MILITARY WORKS, No. 15. SANCTIONED.

(True Extract.)

of any length not less than 2½ feet, with edges neatly dressed bedded in stiff clay, and the joints set in cement. The joints to be scraped to a depth of one inch, and pointed with lime putty.

Every thing necessary for the neat, and workmanlike completion of the work to be provided whether particularly mentioned in the estimate or not.

No

Specification to accompany Estimate for Constructing V shaped drain in front of Cook room in lieu of square drain at the hospital occupied by Lt. Lovelace.

Amount of Estimate Rs 120

The present square drain in front of the Cook room to be pipped up and V shaped drain to be built with stone slabs 3" inches thick and of any length not less than 2½ feet, with edges neatly dressed bedded in stiff Clay, and the joints set in Chunam. The joints to be scraped to a depth of one inch, and pointed with lime putty.

Every thing necessary for the neat and workmanlike Completion of the work to be provided whether particularly mentioned in the estimate or not.

All

... All materials and workmanship employed to be of the best description and subject to the approval of the Executive Engineer of Bangalore who shall have the entire power of ordering the removal of any work which he is dissatisfied.

Approved

Capt. Wood

Executive Engineer Bangalore

A Boileau Colonel R.E.
Superintending Engineer 5th Div.

Executive Engineer's Office
Bangalore 22nd May 1871

Military

Sixth Division P.W. Mysore

Bangalore

Abstract Estimate of 1871-72

Work Constructing V Shaped drain in rear of Cook room in lieu of Open drain at the Hospital occupied by 21st Fusiliers -

Quantities	Description of Work	Rate Per	Amount Estab
184	Running ft. of V Shaped drain	" 0 "	Rs. 115 " "
	Sundries		5 " "
			120 " "

Total Amount of Estimate Rs 120 " "

Executive Engineer's Office
Bangalore 22nd May 1871

(Signed) H. H. Wood Captain R.E.
Executive Engineer,
Bangalore.

Asstt. Sr. Insp. Gen'l Office
Bangalore 23rd May 1871

Approved by order
(Signed) W. Cobrow Major
Asstt. Inspector General
Mysore Division

A Boileau Colonel R.E.
Superintending Engineer 5th Div.

No. 69.

Superintg: Engrs Office, 5th Divn,
Cuddalore, 17th June 1871.

From,
The Superintending Engineer,
5th Division.

To,
The Secretary to Government,
P. W. Department,
Madras.

Sir,

…sures - 2
…nte
…fication

I have the honor to submit, for the sanction of Government, from the grant of Rupees 3,000 for Minor New Works under Military at Bangalore, the under mentioned estimate.

Constructing V shaped drain in rear of Cook Room, in lieu of Square drain at the Hospital occupied by 21st Fusiliers Rs 120

2. The estimate has been approved by His Excellency the Commander-in-Chief.

I have the honor to be
Sir,
Your most Obedient Servant,

[signature] Col. R.E.
Superintg: Engineer, 5th Divn.

Fitt Simon R.E.
Bangalore

P.W. 2816/71

Abstract Estimate for Constructing V shaped drain in rear of Cook room in lieu of Square drain in the Hospital occupied by 21st Fusiliers.

Amount of Estimate Rs 120

C/R & A 8/9

S. Nr. 1871 Dept.
From, (6) A: 2816.
The Supreme Govt:
Simla.

To
The Secretary Govt.
P. W. Department
Madras.

Dated 17th
Rec'd: 19. June 1871
No. 69.

Encl: 2.

Forwarding for sanction an estimate of Rs. 120. for a V shaped drain in rear of Cook-room of the Hospital of the 21st Fusiliers at Bangalore.

No. 1725. 27th June 1871.

Under Secretary.

Executive Engineer
Bangalore.

Dated 29th June 1871.

Rec'd 30th June 1871.

C. 21st June 1871 / R. 24th

Copy of 1871 Madras.

PUBLIC WORKS.

To The Superintending Engr.
5th Circle

Dated

Rd

Read

" 27th June 1871 No 1723.

Nos. 4804/481

Mr Knowles &
Bonsfalne
No 1723 of 27th June 1871
for info and