M.R.O. 1—77,006—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Reference_____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 1939 Press
392-93 —Mis.—

Dated 22-7- 18 91.

Not to be folded or roughly handled

No. 392. Read the following Endorsement of the Acting Chief Engineer for Irrigation, dated Madras, 8th July 1871, No. 41 :—

From the Agent and Manager of the Madras Irrigation and Canal Company, to the Acting Chief Engineer for Irrigation, dated Madras, 3rd June 1871, No. 245.

I HAVE the honour to forward an estimate for repairs to the Hindry Offices and store-rooms, amounting to Rupees 700, the same being charged to Revenue Account, together with the Chief Engineer's letter No. 704, of 29th ultimo, and Mr. Crawford's explanatory letter on the subject.

From the Chief Engineer, to the Agent and Manager of the Madras Irrigation and Canal Company, dated Kurnool, 29th May 1871, No. 704.

I HAVE the honour to forward an estimate for repairs to the Hindry Offices and store-rooms, amounting to Rupees 700.

2. The charge will be to Revenue Account, and Mr. Crawford's letter which accompanies fully explains the necessity for, and the character of, the proposed repairs.

From W. F. CRAWFORD, Esq., Conservancy Engineer, to the Chief Engineer for the Madras Irrigation and Canal Company, dated Kurnool, 9th May 1871, No. 263.

I HAVE the honour to forward the enclosed estimate for repairs to the Hindry Office buildings, and to request you will obtain sanction for the same as soon as possible.

2. The roof over the offices leaks excessively through cracks caused by settlement in the timbers, for which no* allowance was made by raising the centre part. The outer surface in consequence is in many places almost perfectly level, and in heavy rains the water cannot get away fast enough through the spouts. I propose therefore to take off the present roof and raise the rafters in the centre 6 inches, so as to give that amount of fall on either side of the centre line of roof (6 inches in 8½ feet).

* Insufficient.

3. The roof over the east and west store-rooms and the timber-shed also leaks very much from the same cause, but I propose merely to stop the cracks as much as possible with pitch and tar caulking.

4. The amount in contingencies will, I think, be sufficient to cover this.

5. The walls exposed to the north-west monsoons require a coat of rough plaster for which I have made allowance.

6. Also two buttresses are required to the western gables of store-rooms, as they are inclined outward from unequal settlement.

7. In the western store-room one archway needs building up, as the arch is badly cracked from settlement.

Proceedings of the Madras Government, Public Works Department, 24th July 1871.

HINDRY DIVISION, HINDRY BUILDINGS.

REVENUE ACCOUNT.

Estimate for repairing Hindry Office chargeable to Revenue Account.

Quantity.	Particulars.	Rate.	Per	Amount.	Total.
		RS. A. P.		RS. A. P.	RS. A. P.
14	Square. Plastering inside with two coats of chunam ...	2 8 0	Square ...	35 0 0	
17·34	Square. Removing and re-roofing the office with 2 inches flagging, 2 inches of mud, 3 layers (2½ inches) of flat tiles in chunam, with two layers of hemp yarn laid across ways, and over all 1 inch of good plaster laid on in three coats	15 0 0	Do. ...	260 1 7	
18	Cubic feet. Teak for raising centre of roof ¾ × ¼ × 16 × 6 = 18 cubic feet ...	4 0 0	Cubic feet	72 0 0	
22	Cubic yard. Rubble masonry in two buttresses to gable ends of store-room and building up archway in the west store-room	2 4 0	Cubic yard	49 8 0	
99	Square. Plaster to exposed wall of compound (outside) one coat	2 4 0	Square ...	222 12 0	
	Contingencies at about 10 per cent.	.....	.....	60 10 5	
					700 0 0

KURNOOL, 29*th May* 1871.

(Signed) F. H. HENSLOWE, *Agent and Manager.*

(Signed) J. H. LATHAM, *Chief Engineer.*

SUBMITTED to Government with a recommendation that the above estimate, amounting to Rupees 700, may be sanctioned to the debit of Revenue Account.

2. The last repairs to these buildings were sanctioned in G. Os., Nos. 3,579 and 3,967, of 8th November and 18th December 1869, respectively, and the total expenditure on the Hindry Office and store buildings up to 30th April 1871, including original construction, has been Rupees 15,452-8-1.

No. 393. ORDER THEREON, 24th July 1871, No. 1,939.

IRRIGATION, No. 21.

SANCTIONED, but the Government observe that this is another instance of increased expenditure being necessary for faulty construction in the first instance.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Acting Chief Engineer for Irrigation.
,, Agent and Manager for the Madras Irrigation and Canal Company.

1 xd. E C. Slunker.

(3)

Madras Irr: and C. C.
Madras 3d June 1871

No 245

From

The Agent and Manager

To

Major J. G. Ryves R.E.
Chief Engineer for Irrigation
and Joint Secy to Govert
Madras.

Sir

I have the honor to forward an
Estimate for Repairs to the Hindry
Office and Store Rooms amounting to
Rupees 700 — the same being charge-
to Revenue A/c together with the Chief
Engineers letter No 704 of 29 Ultimo and
Mr Crawford explanatory letter on
the Subjects.

I have the honor to be
Sir
Your most obed Servant

D. Sinclair Resr Core
Agent and Manager

No. dated Copy
Public Consultations Office
Received 24th June 1841

To
C. W. Hamilton Esqre
Secretary Government
Madras

Sir,

I have the honor to forward for the information & orders of Government the accompanying letter from the Hindoo Committee of Subscriptions to the Cuddapah Fund, soliciting the grant of Government aid to the charitable object contemplated by the Committee, viz. the erection of a Choultry for the accommodation of Travellers at the Mussulmans Tomb at Jonnavaram in the Talook of Cuddapah.

I have the honor to be
Sir
Your most obedient humble Servant
Harris
Secretary to Government

No. dated 24th June 1841

To
The Secretary to Government
Fort St. George

Sir,

I have the honor to acknowledge the receipt of your letter No. 2345 dated 3rd instant, forwarding for the information of the Hindoo Committee of Subscriptions for the Cuddapah Fund, a copy of a letter from the Collector of Cuddapah, soliciting the grant of Government aid to the charitable object contemplated by the Committee, viz. the erection of a Choultry for the accommodation of Travellers at the Mussulmans Tomb at Jonnavaram in the Talook of Cuddapah.

In reply I am directed to state that the Committee will be glad to receive from Government such aid as they may be pleased to afford for the same object.

I have &c.

To Agent 8 June 54

No. 2345
Dated
From
The Agent & Manager
S. I. C. Co
To
The Chief Engineer
in Irrigation
Fort St. George

Dated 3rd June 1841.

Received 6 June 54.

P. W. 3308/Encl 2

Forwards Estimate for Repairs to Anicut for Rs 900/- together with Copies of Messrs Latham & Crawford's letters.

The roof over the offices leak excessively through cracks caused by Settlement in the timbers for which no allowance was made by raising the centre part. The outer surface in consequence is in many places almost perfectly level and in heavy rains the water cannot get away fast enough through the spouts. I propose therefore to take off the present roof and raise the rafters in the centre 6" so as to give that amount of fall on either side of the centre line of roof (6" in 8½ feet)

The roof over the East and West store rooms and the Timber Shed also leak very much from the same cause, but I propose merely to stop the cracks as much as possible with pitch and tar caulking.

The amount in Contingencies will I think be sufficient to cover this.

The walls exposed to the N. W. monsoons require a coat of rough plaster for which I have made allowance.

Also 2 Butresses are required to the western gables of store rooms as they are inclined outwards from unequal Settlement.

In the western Store room one archway needs building up as the arch is badly cracked from Settlement.

I have &c

Sigd W. F. Crawford

Conservancy Engineer

(True copy)

Sigd R. D. Mathews

Asst to Chief Engineer

P.R. 3308/71

Madras Irrigation and Canal Company

Monthly Division Monthly Buildings

Revenue Account

Estimate for Repairing Monthly office

Chargeable to Revenue Account

Quantity	Particulars	Rate Rs	As	Ps	Amount Rs	As	Ps	Total Rs	As	Ps
114 Sqr	Plastering inside with 2 Coat Chunnam	2	8	- Sqr	35	-	-			
1731 "	Removing and Re-roofing the office with 2" flagging 2" of mud 3 layers (2½ inches) of flat Tiles in Chunnam and 2 layers of Gunny yarn laid Cross ways and over all 1 inch of good plaster laid on in 3 Coat	15	-	- Sqr	260	1	-			
18 Cft	Teak for raising Centre of roof ¾ x ¼ x 16 x 6 = 18 Cft	4	-	- Cft	72	-	-			
22 C.Ft	Rubble Masonry in 2 buttresses to gable ends of Store room and building up archway in the W. Store room	2	4	- C.Ft	49	8	-			
99 Sqr	Plaster to Exposed wall of Compound (outside) 1 Coat	2	4	- Sqr	222	12	-			
	Contingencies at about 10 Per Cent	-	-	-	60	10	5			
								Total Rupees	700	-

Kurnool

29th May 1871

John Wallace

Chief Engineer

For Madras Irrigation

Agent and Manager

No. 41.

Letter from the Agent and Manager Madras Irrigation and Canal Company to the Chief Secretary to Government No. 2215 dated 16th June 1871 submitting Estimate No. 704 of 29th May 1871 and Plan for Lampards establishment

Letter No. 268 of 9th Idem and enclosures

Estimate for Rs. 700 on the Nizams Choultry Bridge Pykar and Stone Parapets

Submitted to Government with the above Letter

Recommended in G.O. No. 3679 of 1871

Irene Sanctioned in G.O. No. 1646 Dated 15th September 1869.

Rupees 700

Sanctioned to the debit of Provincial Revenue

The Estimate is for Rupees 700

Original

No. I. and C. Co

Irrigation Division

Choultry Buildings

Revenue Account

Estimate for repairs to Choultry office chargeable to Revenue account.

May 1871

Amount Rupees 700

P.W. 3308/71.

Office of the Chief Engineer & Secretary to Government Madras. Dated 16th July 1871

To The Secretary to Government Public Works Department

Sir,

I have the honor to forward herewith the Estimate for Rupees 700 for repairs to the Choultry Office at the Nizams Choultry Bridge Pykar and Stone Parapets.

Sundry Serv. Estimates

Capt. R.E.

Executive Engineer

Forwarded.

Revd. Scott.

Agent & Manager

P. W. No. 1871 Dept
No. 4.
9 No. 3398.
From Under Secy. to Govt.
To The Secretary to Govt.
Dated 8th July 71.
Received 11th
Encl. 3
Submitted to Govt.
with a recommendation
for sanction an
Estimate for Rs 700
for the repairs of
the Stud[illegible] Office
and Store Yard.

Recd. 25/7/71

With our order
No. 1909-24 dated July 71

Rs 1939 Sanctioned, but the Government observe that this is another instance of misrepresentation of facts, the Officer having necessary for daily conveyance of files and utensils

Chief Engr. for Chief Engr. Genl. P. Works for U. C. P.

Rs 8 November 69 Rs 176-177
" 18 Dec " 341-342

613 July 71 Rs 15

Book 25/7/71

350

Estt. of 1871 Works.

PUBLIC WORKS.

To Northern Divn. for Irrigation

Dated.

Rcvd. Encl. 3

G. O. 24 July 1871. No. 1937.

Nos. 1921-1923.

Henry office & Store rooms.

The Estimate for the Repairs of the Henry office & Store rooms with Remarks.