M.R.O. 1—77,006—8-6-37.

(1) Number of pages 14

(2) Date of repair 7-6-46

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

DEPARTMENT.

G.O. No. 1957 Press / Mis.

Dated 26-7- 1937.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 26th July 1871.

No. 430. Read the following letter from the Acting Superintending Engineer, 8th Division, to the Secretary to Government, Public Works Department, dated Camp at Courtallum, 11th July 1871, No. 1,178:—

As the cost of the work herein proposed exceeds one-fourth of the valuation of the building, I have the honour to submit, for the sanction of Government, a plan, specification report, and estimate of Rupees 450, for improving and repairing the Moonsiff's Court-house at Mana-Madura, attached to Shevagunga, Madura District. The estimate has been prepared at the request of the Civil Judge, who has countersigned it in token of approval.

2. The building is in a very bad state of repair and urgently needs attention. The cost of the proposed work can be met from the sum of Rupees 3,030, allotted in Part III. of the current year's Budget under "Civil Buildings Minor Repairs" to Revenue, etc., buildings, Madura District.

No. 431. ORDER THEREON, 26th July 1871, No. 1,957.

CIVIL WORKS, No. 29. SANCTIONED.

(True Extract.)

Abstract Estimate No. 59 of 1870-71

District Madura

Work. Improving & Repairing Moonsiffs Court at Mana Madura attached to Shevagungah.

original Valuation Cost
Cost of last repair
year amount

970 -- 1861/62 135 --

Quantities	Description of work	Rate	Amount	Amount of each part
	Record Room			
1 3-15/27	Cubic yds of brick jilly in Chunam	1 --	1 9 4	
1 65/100	Space of 2 coats plastering in chunam	2 8	1 2	
1 115/160	Do of flooring with 8" Spo bricks in Chunam including covering	7 --	10 2 5	
2	Mon[illegible] with plastering & new roof 2½ X½	3 5	7 --	
½	Cuyd of brick in Chunam work for Do	1 --	2 --	37
3½	Coft of Vengay wood wrought & put up including lead flashing &c	3 --	10 8	
2	Stone Corbels for placing under Beam	1 --	2 --	40 59
	Moonsiffs Court-room			
2 2/27	Cuyds of brick in mud	2 8	5 2 11	
3 6/27	Do of brick in Chunam	1 --	12 4 3	
3 11/12	Spaces of plastering 2 coats in Chunam	2 8	7 12 5	
2	Do of re-roofing with couples, battens, nails, flat & pan tiles including Chunam borders &c complete.	10 --	20 --	
2 19/100	Do of eaves to be added to the present roof	17 8	38 5 2	
	Do of ridging tiles	1 --	5 12 --	
5 3/4	Windows with shutters, hinges &c	7 --	28 --	
1	complete 2½ x4			
1	Door with frames, hinges &c complete 3½ x6	15 --	15 --	

10	Stone slabs each 2'x4½x3"		6	3	12		
10	Verjay struts each 3'x4½"x3"		1	2	8		
27	Rft. of stone slabs for steps		4	6	12	145	14 9
	Gymnastaho room						
9/3	Cuyds of brick in mud		2	8	23	5	14
4 11/27	Do of brick in chunam		4		17	10	1
2 30/100	Sqrs of flooring with 8" sqrd bricks in chunam including chunam pointing		7		20	4	9
9 35/100	Sqrs of 2 coats of chunam plastering		2	8	23	6	
4½	Do of re-roofing with ½ portion of new materials		10		45		
1¼	Do of eaves to be added to the present roof		17	8	21	14	
6	Windows with wooden bars &c complete each 2½x4'		7		42		
1	Door with frames &c complete 3½x6		15		15		
8	Struts of Verjay 3'x1½"x3" each		4	2			
27	Rft of stone slabs for steps		4	6	12	220	42
23½	Sqrs of 2 coats yellow wash		4	5	14		
3½	Sqrs of 2 coats of Redwashing to basement		4		14		
6¼	Do of red painting to 12 windows 4 Doors, 2 Ventilators & all Struts		1	8	9	16	2
	Sundries including Scaffolding Dismantling &c					7	54
	Superintendence					430 20	
	Total Estimate Rupees					450	

Madura
29th June/71

Received
1 7 71
J.D.G.

Ric.d J. Roberts Lieut Col RE.
Acting Superintg. Engineer
S. Div.

I. D. Goldingham
Civil Judge

No 59 of 1871-72

Work - Improving & repairing
Kroonaiff & Court at Viana
Pradura attached to the
- vaguega - Madura District
Amount of Estimate Rs. 450-

2/

Enclosure No. 2 in a Letter from the Offg. Supg. Engineer 8th Dn. to the Secretary to Govt. N.W.P. No. 1178 dated 11th July 1871.

O.N. 3395/71.

Estimate.

No. 1178 Superintg. Engineer's Office 8th Dn.
Camp Courtallum 11th July 1871.

From

Lieut. Col. H.A. Roberts R.E.
Offg. Superintg. Engineer 8th Dn.

To

Colonel J. Burpendale R.E.
Secretary to Government N.W.P.

Sir,

As the cost of the works

Enclosures 3 herein proposed exceeds one fourth
1 Abstract Estimate of the valuation of the buildings
1 Plan repairs
system of Government, a Plan,
Specification Report, and Estimate
of Rupees 450. for improving and
repairing the Moonsiffs' Court House
at Mana Madura, attached to
Sheraguiga, Madura District—
the Estimate has been prepared
at the request of the Civil Judge
who has countersigned it in token
of approval.—

2/ The building is in a very
bad state of repair and urgently

needs attention. The cost of the proposed work can be met from the sum of Rupees 3,030 allotted in Part III of the current year's Budget, under "Civil Buildings" "Minor Repairs" to Revenue & Civil Buildings, Madura District.

I have the honor to be
Sir
Your Most Obedient Servant

Ric.d Roberts Lieut. R.E.

To The Secretary to
Govt. of Madras

Dated 11th July 1871
Received 17 " "
1-8-71

No. 1957 Enclosures.

Forwards for the sanction of Govt. Plans Specification and Estimate for repairing the Moonsiffs Court House at Manamadura at Shevagunga, Madura & as the cost exceeds one fourth the value of the buildings

No. 1957 of 26th July 1871

Public Works 1871 Department
From (1) Rs. 3395 11/8
The Ag. Sub Engr 8th Div.

No. 1957
Manamadura
Rd. 27/7/71

Rd. 27/7/71
Rd. S. Dt. Engr
26. July 71

Rd. 29. July 71 Dr. 22nd

J. O'Donnington
Civil Judge

C/o 3395

Govt. of 1871 Madras.

PUBLIC WORKS.

To The Executive Engr
& Ch. Division

Dated.

Rcd. Encl. 2

G. O. 26th July 1871, No. 1957.

Nos. 430 1431

Mandapam Court House at
Mana Madura. The Estimate of Rs 450 for repairing
the Mandapam Court House
at Mana Madura, Sanctioned