M.R.O. 1—77,606—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 1798 Press / Mis.

Dated 31 7 1871.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 31st July 1871.

No. 514. Read the following letter from the Superintending Engineer, 3rd Division, to the Secretary to Government, Public Works Department, dated Bellary, 18th July 1871, No. 731 :—

I HAVE the honour to forward, for the sanction of Government, the accompanying plan, report, and estimate amounting to Rupees 3,670, for constructing quarters for the Rest-house Serjeant at Ghooty.

2. The building of such quarters is considered to be absolutely necessary, and the plan, etc., now submitted have been approved of by His Excellency the Commander-in-Chief.

3. I propose, if sanctioned, to enter the work in my Budget Estimate for 1872-73, and trust Government may be able to provide the necessary funds, as the Serjeant is very much inconvenienced for the want of proper quarters, by having to live under canvas in all weathers for the past two years.

No. 515. ORDER THEREON, 31st July 1871, No. 1,998.

MILITARY WORKS, No. 10.

His Excellency the Governor in Council sanctions the plan with estimate, amounting to Rupees 3,670, for the construction of quarters for the Rest-house Serjeant at Ghooty, and approves of the entry of the work in the Superintending Engineer's Budget lists for 1872-73.

(True Extract.)

Captain, R.E.,
Under Secretary to Government.

To the Superintending Engineer, 3rd Division, with Specification.
" Controller of Public Works Accounts.
" Military Department.

Exd. S. T. Augustin.

3C

Civil Works — Revised — Military

ABSTRACT ESTIMATE.

Bellary DISTRICT

WORK *Constructing Quarters for Boathouse Serpeant at Ghooty as called for in Supdg: Engineers Docket No. 2474 of 3d March 71*

Quantities.	Description of Work.	Rate.	Per	Amount.	Amount of each part.
1229 1215p	Cft. Foundation Rubble stone in Chunam	" 3 "	Cft	230 7 " 227 14 6	
879	Cft. Basement ——do——	" 3 3	Cft.	116 9 "	
3076	Cft. Wall above ——do——	" 3 9	Cft.	720 15 "	
81	Cft. Flat arch ——do——	" 4 "	Cft	12 12 -	
16	Cft. Circular arch ——do——	" 4 "	Cft.	4 " -	
2436	Sqft. Plastering 2 Coat Chunam	2 8 "	Sqr.	85 14 6	
3436	Sqft. Whitewashing	" 4 "	Sqr.	8 9 5	
1238 1238	Sqft. Pointing with Chunam	1 8 "	Sqr.	17 1 1	
1586	Sqft. Roofing with flat tiles in Chunam, Pot-tiles of Chunam borders	17 " "	Sqr.	269 9 11	
1036	Sqft. Flooring with dressed Granite slabs in Chunam framed & imbedded in Marter, flag & long lengths above 1/2 ft Sqr	18 " "	Sqr	186 7 8	
32	Sqft. Granite slabs in front steps 1 1/4 ft breadth	" 3 9	Rft.	7 8 -	
7	Rft. —— do —— to rear steps 1 ft. breadth	" 3 "	Rft.	1 5 -	
1	Granite Slab above Window 3 1/2 x 1 1/2 x 1/4	1 5 "	each	1 5 "	
1	—— Do —— above Shelf 7 x 1 1/2 x 3/4	2 10 "	do	2 10 -	
229	Cft. Jarkwood wrought & put up	3 8 "	Cft	801 8 "	
225	Master Nails	3 " "	100	6 12 "	
	Carried over			2536 12 10 2470 13 "	

Quantities.	Description of Work.	Rate.	Per.	Amount.	Amount of each part.
	Brought over			2527 1 6 / 2761 4 8	
5	1/3 Pannelled 2/3 Venetian Doors with frame & the best hinges locks & bolts Complete 3/2x7	33 11 "	each	168 7 "	
3	Venetian Windows with frames hinges, Bolt & buttons Complete 3x5	20 10 "	do	61 14 "	
1	Venetian Window do do 2x4	11 " "	do	11 " "	
1	Batten Door with frame, hinges bolts &c Complete 3x6/2	19 8 "	do	14 8 "	
2	Wooden pregs to Bathroom 2' long	" 2 "	do	" 1 "	
550	Sqft. Woodening to Doors and Windows	2 8 "	Sqrt.	13 12 "	
64	Cyds Filling Basement & Tramping	" 2 6	Cyd.	10 " "	2527 1 6
45 3/4	Cyds Excavating foundations	" 2 "	Cyd.	5 " "	2761 4 8
	Coalroom, Latrine & Compound				
582 1/2	Sqft. Foundations Brant stone in Chunam	" 3 "	Sft.	103 1 6	
224	Sqft. Basement do do	" 3 3	Sft.	165 5 "	
1095/2	Sqft. Wall above do do	" 3 3	Sft.	322 8 4	
74	Sqft. Coping work do do	" 3 3	Sft.	13 " 6	
9	Sqft. Money Combwork Pot holes in	" 2 6	Sqft	1 6 6	
32 1/2	Sqft Covering Joint Woodwork	" " 4	Sft.	" 10 10	
2	Granite Slabs above Doors 4 1/2 x 1 1/2 x 1 1/2	1 11 "	each	3 6 "	
1	D abve Chimney Combs. work 6 x 1 1/2 x 1 1/2	2 4 "	do	2 4 "	
73	Sqft. Flooring with dressed Granite Slabs in Chunam foundation	18 " "	Sqft	13 2 3	
1725	Sqft: Pointing with Chunam	1 8 "	Sqft	23 14 "	
220	Sqft: Roofing with Pandrowood Battens & Chunam Centres	13 " "	Sqft	28 9 7	
	Carried over			461 15 6	2761 4 8

ities.	Description of Work.	Rate.	Per.	Amount.	Amount of each part.
	Brought over			461 15 6	2761 4 8
20	Cft. Teakwood wrought & put up	3 8 "	Cft.	70 " "	
20	Master Reels	3 " "	100	" 9 7	
18	Cyds: Gravelling watering and ramming to Yard	" 6 "	Cyd.	6 2 "	
2	Batten Doors with frames, hinges, locks bolts &c Complete	18 " "	each	36 " "	
3	Cyds Filling Basement, Tramping &c	" 2 6	Cyd	" 7 6	
21	Cyds: Excavating foundations	" 2 "	Cyd.	2 10 "	578 6 7
					3405 11 1
					3339 11 3
					165 2 5
					170 2 3
					100 2 6
	Sundries at 5 per Cent				
	Superintendence at 3 do				3670 " "
	Total Estimate Rupees				3670 " "

Bellary 30th June 1871

W. Tadd, Brigade Major
Commanding Bellary District

Approved
Bellary RANGE OFFICE
30th May 1871

Lieut
Asst Engineer in charge
Bellary Range.

Recd.
The Plan

W. Tadd Lieut. R.E.
Asst Engineer

Bellary Station
Engl. Cantonment
From
The Asst. Engineer
In charge Ghoody Range,

To

The Superintending Engineer
3rd Division,

Dated 30 May 1871.
Received 1st June 1871.

Abstract Estimate amounting to Rupees 3670 — "

for Constructing Quarters for Rest-house Serjeant at Ghoody

7c

No. 731. Superintending Engineer's Office.
3rd Division.
Bellary 18 July 1871.

From,
The Superintending Engineer
3rd Division.

To,
The Secretary to Government
Public Works Department
Fort Saint George

Sir,

I have the honor to forward for the sanction of Government the accompanying Plan, Report and Estimate amounting to Rs 3670/- for constructing Quarters for the Rest House Serjeant at Ghoody.

2. The building of such Quarters is considered to be absolutely necessary, and the plan &c. now submitted have been approved of by His Excellency the Commander-in-Chief.

nclosures.
3.

3. S.

3. I propose, if sanctioned, to enter the work in my Budget Estimate for 1872-73, and trust Government may be able to provide the necessary funds, as the Sergeant is very much inconvenienced for the want of proper quarters, by having to live under canvas in all weathers for the past two years.

I have the honor to be,

Sir,

Your most obt Servant

[illegible] Lieut

Superintending Engineer

3rd Dist

9c

P.W. 18/11-12 Dept.
Sr. Office for July No. 3463.

From,
The Superintending Engineer
3rd Division.

To,
The Secretary to Government.
Public Works Department.
Fort Saint George.

No. 131

Dated 15 July 1871.
Received 20

Forwarding for Sanction approved Estimate &c - Rs 3670/- for constructing Quarters for the Rest House Serjeant at Chooty, & requesting to provide the Sum do for the Object No. 1998 - 31 July 1871

No 514

No. 1998. P.W. Department

Proceedings of the Madras Government.

Under Date the 31st July 1871

Read the following:

From The Supt Engr 3rd Div. No. 131 dated 15th July 1871.

Forwarding for Sanction approved Estimate &c - Rs 3670/- for constructing Quarters for the Rest House Serjeant at Chooty, and requesting to provide the Sum do for the Object.

Read also the following:

From The Secretary to Government Public Works Department No. 1998 dated 31st July 1871.

Forwarding for Sanction approved Estimate &c - Rs 3670/- for constructing Quarters for the Rest House Serjeant at Chooty, and requesting to provide the Sum do for the Object.

His Excellency the Governor in Council sanctions the plan with estimate amounting to Rupees 3670 for the construction of Quarters for the Rest House Serjeant at Chooty, and approves of the entry of the work in the Supt Engineer's Budget lists for 1872/3.

46/4

To The Supt Engineer of the 3rd Division
The Controller
Military Deputy

Recd 1/8/71

C. No-3463.

Govt. of H.S.T.B Madras.

PUBLIC WORKS.

To The Superintending Engr
3rd Division

Dated

Rcvd. 2

G. O. 31st July 1871, No. 1998.

Nos. 514 & 515

Quarters for the Collector Sergeant-at-Arms

Estimate of Rs 3870
sanctioned for entry in
the Budget-lists for
1872-73.