M.R.O. 1—77,(66—3-6-37.

(1) Number of pages

(2) Date of repair

(3) Initials of the Reference

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2224	Press / Mis.
1-1-42	
Dated	19

Not to be folded or roughly handled

No. 421. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 1st August 1871, No. 92:—

WITH reference to paragraph 5 of G. O., No. 594, of the 1st March 1871, I have the honour to submit, for the sanction of Government, an estimate, amounting to Rupees 22,000, accompanied by a plan and specification, for constructing a school-room providing accommodation for 150 adults and 140 children, European Infantry, at Bangalore.

1 Estimate, Rupees 22,000.
1 Plan.
1 Specification.

2. A sum of Rupees 10,000 has been granted for this building in the Imperial Budget of 1871-72, Item No. 13.

No. 422. ORDER THEREON, 31st August 1871, No. 2,224.

MILITARY WORKS, No. 8.

Vide G. O., No. 58, dated 14th February 1871.

THE Government sanction the plan and estimate, amounting to Rupees 22,000, for constructing a school-room for the European Infantry at Bangalore.

2. It is observed that the building will accommodate 150 adults and 140 children, and that a sum of Rupees 10,000 has been provided for the work in the current year's Budget.

(True Extract.)

Captain, R.E.,
Under Secretary to Government.

To the Superintending Engineer, 5th Division, with Specification.
,, Controller of Public Works Accounts.
,, Military Department.

Exd. S. T. Augustin.

No 92. Surveyor Engineer's Office, 5th Division,
Cuddalore, 1st August 1871.

From, Colonel A. J. N. Boileau, R.E.,
Superintending Engineer, 5th Div.,

To, Colonel J. Carpendale, R.E.,
Secty. to Government, F.W.D.

Sir,

With reference to paragraph 5 of
G. O. No 594 of the 1st March 1871, I have
the honor to submit, for the sanction of
Government, an estimate amounting to
Rupees 22000., accompanied by a plan and
Specification, for constructing a School Room
providing accommodation for 150 adults
and 140 children, European Infantry at
Bangalore.

2. A sum of Rupees 10,000. has been
granted for this Building in the Imperial
Budget of 1871-72, Item No 13.—
I have the honor to be
Sir,
Your most obedient Servant.

Enclosures 3.
1 Estimate Rs. 22,000.
1 Plan
1 Specification

Boileau Colonel R.E.,
Superintending Engineer, 5th Divn.

Rec'd Franco 4/9/71-2.

Dy. 1871. Dec. 4.
From Secy. to Govt. for Orgent
No. 3705
The Supdg. Engineer,
5th Division
To, The Secy. to Government,
P.W. Departt.

Dated 1st Dec. 1871.
Rec'd 4th Dec. 1871.

No. 92.

Enclosures 3.
1-E. Rec'd 1 Plan

School room.

Submitting for sanction an estimate of Rs. 22000- for constructing a School room for Adults & Children European Infantry at Bangalore.

No. 2224-31 Aug. 71

No. 421

6 Offg. Asst. 17-Dec. 28.

	Brought over			15580	
748	Nos of Nails 3" long	7	Each	27	
294	Running feet of Wrought iron spouts 4" diameter	12	Rft	221	
115.40	Squares of Wood oiling two coats	Sqre		231	
24	Pair of 1½ inch ⅓ pannelled, ⅓ venetioned and ⅓ glazed door with 4½×3½ frams strong pivot hinges, bolts 9" brass locks with key plates &ca complete 4×8	38	12 Each	930	
20	do of 1½ venetion windows with glazed shutters, frames 4½×3½ with strong iron plate hinges 9" long hooks eyes buttons brackets and other fittings &ca complete 4×6	51	do	1020	
44	Swing windows with 1½ glazed shutters frames 4½×3½ with strong pivots cleats ropes and other fittings &ca complete 4×1½	10	do	440	
12	Pair of 1¼ pannelled shutters with 4"×3½ frames including locks hinges &ca complete 3×5	19	do	228	
43.35	Squares of Chocolate painting two coats	5	Sqre	27	
20	Sets of boards with 10 hat pegs in each including wood oiling and fixing complete	5	Each	100	
20	Nos of hooks for hanging lamps	4	do	5	
1140	Cubic feet of Earthwork for ramp around the building	2	Cft	12	
26.60	Squares of Gravelling 3" thick well watered and rammed	1	Sqre	27	
688	Running feet of V shaped drain	6	Rft	258	
1	Nos of Marking board	5	Each	5	
4	do of Inventory boards	12	do	3	
	Levelling the ground			40	
				19350	
	Sundries			960	
	Total Rupees			20310	
	Urinals and Colonades				
1363	Cubic feet of Excavation	1	Cft	7	
	Carried over			7	20310

	Brought forward			7	20310
1363	Cubic feet of Foundation stone in chunam	2 6	Cft	213	
215	do of Basement do	2 6	do	34	
1507	do of Superstructure brick in chunam	2 9	do	259	
117	do of Archwork	4	do	29	
10	Nos of Columns of 1½ diameter with brick in chunam	10 6	Each	105	
1.34	Squares of Honey comb tile work	8	Sqre	11	
100	Running feet of Cornice work	12	Rft	75	
28.61	Squares of Plastering with 2 coats	2 8	Sqre	71	
11.58	do of Whitewashing	3	do	2	
17.03	do of Bluewashing	4	do	4	
71⅔	Cubic feet of Teak wood wrought and put up	3 8	Cft	257	
60	Nos of Nails 9" long	1	Each	1	
7.41	Squares of Terracing	27 8	Sqre	204	
238	Cubic feet of Filling in basement	½	Cft	1	
4.53	Squares of Flooring with stone slabs &ca	15	Sqre	68	
1.73	do of Flooring with asphalte	22	do	38	
36	Running feet of Stone slabs treads for steps	4	Rft	9	
12	Nos of Stone slabs under breasummer 1½×1½×¼	3 6	Each	3	
64	Rft of Wrought iron spouts 4" diameter	12	Rft	48	
2	Pair of Pannelled doors 3½×7 with frames &ca complete	31	Each	62	
4	Glazed swing windows 3×1½ do do &ca complete	7	do	28	
5⅞	Squares of Wood oiling two coats	2	Sqre	11	
3	Nos of Urinal seats with tubs &ca	3	Each	9	
4	do Tubs do	1 8	do	6	
70	Square feet of Iron partition	9	Sqft	39	
1.71	Squares of Chocolate painting two coats	5	Sqre	9	
2	Marking boards	5	Each	10	
2	Inventory boards	12	do	2	
				1610	
				80	
	Sundries			1690	
	Total Rupees			22000	

A. Dr. M.E. General's Office in Mysore
Bangalore 2nd June 1871.

Approved
By Order
W. Osborn Major
Offg A. Dr. M.E. General & M. Dm
Executive Engineers Office
Bangalore, 31st May 1871.

Grand Total of Estimate Rupees 22000 - -

(Signed) H. W. Wood Captain, R.E.
Executive Engr Bangalore

Colonel, R.E.
Superintending Engineer 5th Dn

P.W. Dept

№ 2224

Proceedings of the Madras Government

Under date the 31st August 1871.

Read the following

From the Supt Engineer
of the 5th Dn

(Hereunto № 927 1st August 1871)

The Government sanction the plan and estimate amounting to Rs 22,000 for constructing a School Room for the European Infantry at Bangalore.

It is observed that the building will accommodate 150 adults and 140 children, and that a sum of Rs 10,000 has been provided for the work in the Current year's Budget.

Ord

vide G.O. dtd 58, dated
14th Feby: 1871.

№

Supt Engr 5th Dn with Spcn
Controller P.W. Accts
Military Departt

Dept 1/9/71

No. 3705

Govt of {1871} Madras.

PUBLIC WORKS.

To The Superintending Engineer
5th Division

Dated

Recd. 2

G. O. 31st Augt 71. No 2224.

Nos. 421 & 422

School room. The estimate amounting to Rs 22,000 for constructing a School room for the European Infantry at Bangalore, sanctioned with reservations.