M.R.O. 1—77,654—6-8-81.

(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2311 Press Mis.
173-74
Dated 11-9- 1874.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 11th September 1871.

No. 173. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 1st August 1871, No. 93:—

1 Plan
1 Estimate
1 Specification.

WITH reference to G. O., No. 1,642, dated 19th June 1871, I have the honour to submit, for the sanction of Government, a revised plan and an estimate of Rupees 7,540 for the construction of robing-rooms and waiting and watching sheds at the new Cemetery for all denominations of Christians at Bangalore.

2 As directed by Government, I furnished the Executive Engineer with a sketch reducing the area of the proposed buildings from 1,369 to 966 square-feet, by dispensing with one of the three entrance openings suggested by Lieutenant-Colonel Roberts, and the present design and estimate have been prepared in accordance therewith. This estimate still exceeds the first estimate* by Rupees 180, but it falls short of the second† by Rupees 3,120.

* Rupees 7,360
† ,, 10,660

3. I consider that the abridged space is quite sufficient to meet the requirements for funeral parties in all weathers As the general arrangement of the building proposed by Colonel Roberts appears to be good, and the style of the work is in conformity with that of the enclosure wall and entrance gates of the Cemeteries, I do not consider it advisable to further lower the estimate by disturbing the same.

4. The Government will not lose sight of the fact before reported, that the Mysore Government have agreed to bear the cost of half the amount, Rupees 7,540, of the proposed outlay.

No 174. ORDER THEREON, 11th September 1871, No 2,311.

CIVIL WORKS, No. 9.

IN the Order of the 19th June 1871, No 1,642, the Government returned for revision a revised plan and estimate of Rupees 10,660 for the construction of robing-rooms and waiting and watching sheds at the new general Cemetery at Bangalore on the ground that the proposed expenditure was quite disproportionate to the nature of the buildings required.

2. With the letter above recorded the Superintending Engineer of the 5th Division submits a plan and estimate, amounting to Rupees 7,540, which is Rupees 180 in excess of the original, and Rupees 3,120 below the second estimate for the work. The Superintending Engineer considers that it would be impracticable still further to reduce the estimate without destroying the architectural effect of the structures and abridging the accommodation within limits inadequate to the general requirements of the station, and His Excellency the Governor in Council accordingly sanctions the plan and estimate, a moiety of the cost of the work being borne by the Mysore Government.

3. As the available funds under Provincial at the disposal of Government in this Department will not admit of an allotment being made for this work during the

current official year, the question of the provision of the required amount, namely, Rupees 3,770, will be referred for consideration in the Financial Department.

(True Extract.)

Captain, R.E.,
Under Secretary to Government.

To the Superintending Engineer, 5th Division, with specification.
" Controller of Public Works Accounts.
" Ecclesiastical Department.
" Financial "

Exd. S. T. Augustin.

2/1

No 93 Superintg: Engineers office, 5th Divn,
Cuddalore, 1st August 1871.

From,
Colonel A. J. H. Boileau, R.E.,
Superintending Engineer, 5th Dn,
To,
Colonel J. Carpendale, R.E.,
Secretary to Government, P.W.D.

Sir,

Enclosures 3.
1 Plan
1 Estimate
1 Specification.

With reference to G.O. No 1692 dated 19th June 1871, I have the honor to submit, for the sanction of Government a revised Plan and an Estimate of Rs 7,510 for the construction of Robing rooms and Waiting and Watching sheds at the New Cemetery for all denominations of Christians at Bangalore.—

2. As directed by Government I furnished the Executive Engineer with a sketch reducing the area of the proposed buildings from 1,369 to 966 Square feet by dispensing with one of the three entrance openings suggested by Lieut.-Colonel Roberts, and the present design and estimate have been prepared in accordance

accordance therewith. This estimate still
exceeds the first Estimate* by Rs. 180, but
it falls short of the second* by Rs. 3120.. * Rs. 1360..
3. I consider that the abridged space * ---- 10,660.
is quite sufficient to meet the requirements
for funeral parties in all weathers. As the
general arrangement of the building proposed
by Colonel Roberts appears to be good,
and the style of the work is in conformity
with that of the enclosure walls & entrances
gates of the Cemeteries, I do not consider it
advisable to further lower the estimate
by disturbing the same.
4. The Government will not lose sight
of the fact before recorded that the
Mysore Government have agreed to bear
the cost of half the amount Rs. 7,540—
of the proposed outlay.—

I have the honor to be
Sir,
Your most obedient Servant
[signature]
Colonel R.E.,
Superintending Engineer, 5th Circle.

Encl

Rc 19 Lrs 1st Rc 312
313

Ps 1871 Rc 7

From Pro of Govt for abstr
Rs 3706
The Supg Engr 5th Divsn
To The Secy to Govt
P.W.D.

Dated 18th August 1871
Recd 24 August 1871

No 93.
Enclosures 3. Rs Cas-

Submitting for sanction revised Abstract Estimate of Rs 3540 for constructing Ko king rooms &c at the New Cemetery at Bangalore.

No 193
Copy & Abstr sent to Supt & Asst

5th Division, D. P. W.

Civil Buildings — Bangalore — New Works.

Revised Abstract Estimate of 1871-72.

Work.— Constructing additions to the Ossoor road Cemetry at Bangalore.

Quantity	Description of works.	Rate	Per	Amount	Total.
2,051	Cubic feet of Excavation	" . 1	Cft	11	..
2,051	Do of Foundation stone in chunam	" 2 6	do	320	..
3,132	Do of Superstructure do	" 3 .	do	587	..
62½	Do of Archwork do	" 8 .	do	31	..
150	Nos of Cuddapah stones for Arches, doors, and windows (1¾ x 1 x ¾)	1 . .	Each	150	..
160	do do do (1¾ x ¾ x ¾)	" 12 .	do	120	..
4	Nos of Stones for window sills 6 x 1¾ x ½	2 8 .	do	10	..
4	Running feet of Stone slabs over gable walls 1¾ x ¼	" 8 .	Rft	12	..
3018	Square feet of Dressing	" 4 .	Sft	755	..
43·42	Squares of Pointing with lime putty	2 . .	Sqre	87	..
11·17	do of Plastering with chunam	2 8 .	do	28	..
11·17	do for White washing two coats	" 3 .	do	2	..
106	Cubic feet of Teak wood wrought and put up	3 8 .	Cft	371	..
90	Nos of Nails 7" long	" . 7	Each	3	..
270	Running feet of Iron rod ¾ diameter	" 6 .	Rft	101	..
8	Nos of Stone slabs for steps	" 5 .	Each	3	..
56	" of String course of cut granite	" 10 .	do	35	..
7·04	Squares of Roofing with corrugated iron sheeting screwed with galvonized iron screws	50 . .	Sqre	352	..
5·52	do of Terracing	27 8 .	do	152	..
166	Cubic feet of Filling in basement with earth	. " ½	Cft	1	..
1·97	Squares of Paving	15 . .	Sqre	30	..
6·68	do of Gravelling	1 8 .	do	10	..
11·08	do of Wood oiling two coats	2 . .	do	22	..
	Carried over			3193	..

		Brought over				3193 ..
2	Nos of Wrought iron spouts 3" in diameter and 1/16 inch thick		3	8 .	Each	7 ..
2	Pairs of Pannelled doors 4'×10½ with glazed gothic top frames &ca		50	..	do	100 ..
4	—do— of Windows 4'×3' venetioned shutters outside and glazed shutters inside with frames &ca		60	..	do	240 ..
1	—do— of Pannelled shutters for almirah 3'×4 ft. with frames &ca		15	..	do	15 ..
4·86	Squares of chocolate painting two coats		5	..	d/yd	24 ..
1	Nos of cast iron cross		13	..	Each	13 ..
						3592 ..
		Sundries				178 ..
		Total Amount of Estimate Rupees for one				3770

Executive Engineer's Office
Bangalore, 15th July 1871

(Signed) H. W. Wood Captain, R.E.
Executive Engineer, Bangalore

Colonel, R.E.
Superintending Engineer, 5th Div

P.W. Dept.

No 2311.

Proceedings of the Madras Government

Under date the August 1871.

Read the following.

From the Supt Engineer
of the 5th Dn

(Store enter No 93 of 1st August 1871)

In the order of the
19th June 1871, No 1642, the
Govt returned for revision
a revised plan and
estimate of Rs 10,660 for
the construction of Policing
Rooms and Watching and
watching sheds at the new
General Cemetery at Banga-
lore, on the ground that
the proposed expenditure
was quite disproportionate
to the nature of the buildings
required.

With the letter above
recorded the Supt Engineer
of

5th Division, D. P. W.

Bangalore.

B.P. No 3706/71
11th Septr 71 Re 2311

Revised Abstract Estimate
for constructing additions to the
Ossoor road Cemetry at
Bangalore.

Amount of Estimate Rs 7540.

I see nothing in the plan
but gateways & two
Rest rooms. If there is
also a well 750 Rs. is
not Engineer. Before
sanctioning it should
be shewn for the
Carpenter — Mason &
Mallie accommodation
the nature of the
work really requires
[illegible]

of the 5th Division submits a plan and estimate amounting to Rs 7,540 which is Rs 180 in excess of the original and Rs 3,120 below the second estimate for the work.

2. The Supt. Engineer Col Boileau apparently considers that it would be impracticable still further to reduce the estimate without destroying the architectural effect of the structures and abridging the accommodation within limits inadequate to the general requirements of the station, and His Excellency the Governor in Council accordingly sanctions the plan and estimate, a moiety of the cost of the work being

being borne by the Mysore Government.

3. As the available funds under Provincial at the disposal of Govt. in this Department will not admit of an allotment being made for this work during the current official year the question of the provision of the required amount (viz:) Rs 3770 will be referred for consideration in the Financial Departt.

Cubbon

To
The Supt Engr 5th Div North Canara
" Controller P. W. Accts
" Ecclesiastical Departt
" Financial "

Dated 12/3/71

C. No-3706-

Govt. of Madras.

PUBLIC WORKS.

To The Secretary Govt.
of Fort St. George

Dated

Rec'd 2

G.O. 11 Sept. No. 2311.

Nos. 1703/174.

Calling reports &c. Retaining
of Nos 5720 from the collr
Coimbr &c all the Bangalore Executive
& the Superintg of Pmbdy
Funds & referred to the Financial
Depts.