M.R.O. 1—77,006—8-6-37.

(1) Number of pages 10

(2) Date of repair 17-6-24

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2403 Press / Mis.

541-362

Dated 21-9-1871.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
21*st September* 1871.

No. 341. Read the following letter from the Officiating Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 2nd September 1871, No. 123:—

1 Estimate, Rupees 1,860.
1 Specification.
1 Plan.

WITH reference to G. O., No. 225, of the 20th January 1870, I have the honour to submit, for the sanction of Government, an estimate amounting to Rupees 1,860, accompanied by plan and specification, for constructing a new hospital privy at Mercara.

2. The plan and estimate have been approved of by His Excellency the Commander-in-Chief.

No. 342. ORDER THEREON, 21st September 1871, No. 2,403.

MILITARY WORKS, No. 10.

SANCTIONED. No funds are at present available.

(True Extract.)

Captain, R.E.,

5th Division D. P. W.

Military. Bangalore New Works.

Abstract Estimate for 1871-72.

Work.—Constructing a Privy for Hospital at Mercara.

Quantity	Description of works.	Rate	Per	Amount	Total
750	Cubic feet of Excavation	1	Cft.	4 ..	
733	do of Foundation stone in chunam	3 6	do	160 ..	
406	do of Basement do	3 6	do	89 ..	
1399	do of Superstructure brick in chunam	6 .	do	525 ..	
104	do of Archwork	8 .	do	52 ..	
28	Running feet of Cornice work	4 .	do	7 ..	
98	Squares of Honey comb brick work	16 . .	Sqre.	16 ..	
24.77	do of Plastering with chunam	7 . .	do	173 ..	
1.65	do of do with cement	30 . .	do	20 ..	
11.37	do of Whitewashing two coats	9 .	do	6 ..	
13.40	do of Bluewashing do	11 .	do	9 ..	
6	Running feet of Stone slabs treads for steps	7 .	Rft.	3 ..	
220	Cubic feet of Filling in basement	½	Cft.	1 ..	
296	Squares of Flooring with stone slabs set in mortar and pointed with lime putty	20 . .	Sqre.	59 ..	
1.74	Squares of Asphalte flooring	50 . .	do	87 ..	
19⅓	Cubic feet of Granite cut stone for drain	1 4	Cft.	24 ..	
9...2½	do of Teakwood wrought and put up	4 . .	do	276 ..	
135	Nos. of Nails 7 inches long	1	Each	8 ..	
7.31	Squares of Roofing with double course of pot tiles @ ea.	27 8	Sqre.	201 ..	
	Carried over			1720 ..	

	Brought over		1720 ..
581	Squares of Wood Piling two coats	@ 3 & Sqr	20 ..
4	Nos of Urin tubs	6 Each	24 ..
			1764 ..
	Sundries		96 ..
	Total Amount of Estimate Rupees		1860 ..

Executive Engineer's Office
Bangalore, 30th June 1871.

(Signed) H. W. Wood Captain R.E.
Executive Engineer, Bangalore.

Asstt. Dr. Mr. General's Office M. Dy.
Bangalore, 4th July 1871.

Approved
By Order
(Signed) B. M. Deane Major
Asstt. Dr. Mr. General M. Dy.

Louis Pelly Lieutenant R.E.
Of the 5th Division

5th Division, D. P. W.

Bangalore.

P. W. 4165/71

Abstract Estimate
for Constructing a Privy
for Hospital at Mercara.

Amount of Estimate Rs. 1860.

B. D. Ly. Rs 1165

No. 123.

Superintg: Engineer's Office, 5th Division,
Cuddalore, 2nd September 1871.

From,
Captain James Verner R.E.,
Offg: Supg: Engineer, 5th Divn.

To,
Colonel J. Carpendale R.E.,
Secretary to Government, P.W.D.

Sir,

Enclosures 3.
1 Estimate Rs. 1860.
1 Specification.
1 Plan

With reference to G.O. No. 225 of the 20th January 1870, I have the honor to submit for the sanction of Government, an estimate amounting to Rupees 1,860, accompanied by plan and Specification, for constructing a New Hospital Privy at Mercara.—

2. The Plan & Estimate have been approved of by His Excellency the Commander-in-Chief.—

I have the honor to be
Sir,
Your most Obedient Servant.

James Verner Captain R.E.
Offg: Superintg: Engineer, 5th Divn.

Rec 20th January 1870 No 433 434

46

Transmitted. Works and Buildings Dept. Public Works Dept. 8th Jan 1870.

Copy of Letter No. 18

P. W. 1871 Dept

No. 4165

From,

The Offg: Supg: Engineer

5th Division

To

The Secty. to Government

of I. & B. Depart.

Dated 2nd

Recd 4th } September 1871

No. 123.

Enclosures 3.

Forwards for sanction

an estimate of Rs. 1,860

for Constructing a Veni

Hospital Privy at

Mercara.

No. 2403-21 Sept. 1871

Forth order

No 4165

Govt of Madras.

PUBLIC WORKS.

To The Superintending Engr
5th Division

Dated.

Rcvd. Encl. 2

G. O. 21 Septr, No. 2403.

Nos. 341 1342

New Hospital Privy - The Estimate of Rs 1860 for constructing a new Hospital Privy at Veram, sanctioned with remarks.