M.R.O. 1—77,006—8-6-37.

(1) Number of pages 1

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public (Misc.) DEPARTMENT.

G.O. No. 2438 Press ~~Mis.~~

407-08

Dated 23-9- 1871.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 23*rd September* 1871.

No. 407. Read the following Proceedings of the Madras Government in the Judicial Department :—

APPROVING of the plan and estimate of Rupees 6,000 for quarters for the Superintendent of the Rajahmundry Central Jail, and directing the amount to be provided in the Public Works Department for 1872-73.	(Here enter No. 1,263, 11th September 1871.)

No. 408. ORDER THEREON, 23rd September 1871, No. 2,438.

CIVIL WORKS, No. 24.

COMMUNICATED to the Superintending Engineer of the 1st Division who will include the building in his list of works for entry in the Provincial Budget for 1872-73.

(True Extract.)

Captain, R.E.,
Under-Secretary to Government.

To the Superintending Engineer, 1st Division.
„ Controller of Public Works Accounts.

Encl. E. C. Shunker

No. 43. Read the following letter from the Inspector-General of Jails, to the Chief Secretary to Government, Fort St. George, dated Ootacamund, 9th August 1871, No. 129:—

I have the honour to submit plans and estimates for quarters for the Superintendent of the Central Jail at Rajahmundry. The Superintending Engineer is of opinion that the outlay in money will not exceed Rupees 6,000.

From the Acting Superintendent of the Central Jail at Rajahmundry, to the Inspector-General of Jails, dated Rajahmundry, 3rd July 1871, No. 64.

I have the honour to forward, for your approval, plans and estimates for Superintendent's quarters at this jail as per margin; also a rough plan of proposed site and original letter from Collector, Godavery District, regarding the site.

One plan for the Superintendent's house.
,, plan for stables.
,, ,, ,, cook-house.
,, ,, ,, proposed site for Superintendent's quarters.
,, estimate.
,, statement of materials.
,, specification.

2. I would draw attention to the small quantity of land proposed to be handed over, *i. e.*, five acres; in other words, a square of 156 yards.

3. This would give 56½ yards clear of the house in its length and 66 yards clear in depth. In this space will have to be built stables, cook-rooms, and godowns, besides sinking a well.

4. I would, therefore, suggest the same quantity of land be granted as at other Central Jails. The road leading from Trunk Road to Warders' and Police Lines is a private one made by the jail.

6. The whole of the ground in plan of proposed site (marked in red-ink) is Government waste land and very poor soil.

From the Acting Superintendent of the Central Jail at Rajahmundry, to the Inspector-General of Jails, dated Rajahmundry, 3rd August 1871, No. 78.

In reply to your letter, No. 1371, dated 13th July 1871, I have the honour to inform you that I have seen Major Fischer, the Superintending Engineer of this Division, and learnt from him the following particulars regarding estimates for Superintendent's house at this jail.

ENCLOSURES.

One revised abstract estimate.
,, estimate of cost of materials.
,, plan of proposed site.
,, Collector's letter regarding site.
,, copy of letter sent to Collector regarding site.

2. In his opinion, "the contemplated outlay in money, that on out-houses included, will not exceed Rupees 6,000."

3. The items for entertainment of a free Carpenter Maistry and a free Bricklayer Maistry were included in estimate to meet any casualty that might occur to our Jail Carpenter and Bricklayer Maistry.

4. The dimensions of Salem house being out of proportion, they were altered by Superintending Engineer. I have not now got a plan of Salem house, but believe that one bed-room was 18 feet square, the other 22 × 18.

5. A free Carpenter Maistry and a free Bricklayer Maistry, jail servants, are available for work on house, but there are no convicts competent to work without a free Maistry to direct them.

6. I have requested the Collector to give me 100 yards on every side clear of basement of house, and received his reply yesterday, informing me that the piece of ground I require will be made over to me.

I would bring to your notice that a house for Superintendent is most urgently required, the only house available being the one I now occupy, and which is in a very dilapidated condition, the only other habitable house being at a distance of five miles from Central Jail.

The house lately occupied by Mr. Hallett is now in ruins.

Proceedings of the Madras Government, Judicial Department,
11th September 1871.

No. 44.

ORDER THEREON, 11th September 1871, No. 1283.

The Government approve of the plan and estimate of the proposed house for the Superintendent of the Jail at Rajahmundry. The Government direct that a provision of 6,000 Rupees on account of this building be made in the Public Works Budget of 1872-73, as it appears that no funds are available during the current year.

(True Extract.)

Captain, R. E.,
Under Secretary, P. W. D.,
for *Chief Secretary.*

To the Public Works Department, with ten enclosures.
,, Inspector-General of Jails.
,, Revenue Department.

RTMENT NEW WORK.

Revised ABSTRACT ESTIMATE No. 4

TALUQ Rajahmundry

DISTRICT Godavery

. Constructing quarters for the Superintendent of Central
ail at Rajahmundry as per Design

					Amount.			Total.
					78	9	5	
					7	2	8	
					8	"	"	
					3	4	9	
					9	5	4	
					9	9	7	
					4	1	"	
					2	4	"	
					0	"	"	
					18	4	"	
					7	12	"	
					7	3	2	
	Roof with 3 courses flat tiles and 3 Coats Chunam	16	"	do	798	3	10	
Square feet of	Teakwood panelled doors complete	1	8	do	535	8	"	
Do	of Teakwood Venetian doors and Windows Complete	1	12	do	624	12	"	
Do	of Glazed doors & Windows	1	8	do	420	"	"	
					11519	15	9	

Proceedings of the Madras Government, Judicial Department,
11th September 1871.

No. 44. ORDER THEREON, 11th September 1871, No. 1263.

The Government approve of the plan and estimate of [illegible] the Superintendent of [illegible] provision of [illegible] Budget of 1 year.

To the Public Wor
" Inspector-(
" Revenue D

Pub. Works 1871 Selected
Chief Engineer's Office

JUDICIAL 5th Oct 50

No: 2435. 23 Sept 1871.

DEPARTMENT NEW WORK.

Revised ABSTRACT ESTIMATE No. 4

TALUQ Rajahmundry

DISTRICT Godavery.

WORK. Constructing quarters for the Superintendent of Centra Jail at Rajahmundry as per revised Design

Quantity or Number.	Description of Work.	Rate.	per Item.	Amount.	Total.
832 4/27	Cyds Rough stone in Chunam	4 . .	Cyd	3328 9 5	
78. 2/27	do Brick work in Chunam	4 8 . .	do	351 2 8	
4. 2/27	do do Circular arches	6 . .	do	28 . .	
16. 3/27	do do Flat arches	5 8 . .	do	93 4 7	
19 1/9	do Cut stone work in Chunam	12 . .	do	229 5 4	
58 1/10	Squares Flooring with brick on Edge in Chunam and plastering 2 Coats Chunam	16 . .	Sqr	929 9 7	
187 3/10	do Plastering 2 Coats Chunam and Whitewashing	3 12 . .	do	704 1 .	
377	Running feet of Cornice work	. 4 . .	Rft	94 4 .	
30	No. Brick Columns or pillars	9 . . .	Each	270 . .	
889.5/12	Cft. of Teakwood wrought and put up	3 . .	Cft	2668 4 .	
7 5/8	Squares of Terrace Roofing with brick on Edge in Chunam 3" thick Jelly, 3 Courses flat tiles and 3 Coats Chunam in and out	22 . .	Sqr	167 12 .	
36 24/25	Squares of Roofing with flat and pan tiles and Chunam border	7 8 . .	do	277 3 2	
49.80/100	do of sloping Bengal Terrace roof with 3 Courses flat tiles and 3 Coats Chunam	16 . .	do	798 3 10	
357	Square feet of Teakwood panelled doors Complete	. 1 8 . .	Sq ft	535 8 .	
357	do of Teakwood Venetian doors and Windows Complete	1 12 . .	do	624 12 .	
280 1/2	do of Glazed doors Windows	1 8 . .	do	420 . .	
				11519 15 9	

	Brought over							11579 15 9
	Painting doors & windows							1140
	Painting woodwork R with wood oil							120
	Excavating foundations and filling in basements							200
	Contingencies							1200 " 3 "
	Cook Room and Stable as per Original Plan.							13180
	Stable							
27 16/27	Cyd. Rough Stone in Chunam	4	"	Cyd	110	5	11	
57 6/27	do Burnt Brick in Clay and painted with Chunam	3	"	do	171	10	8	
58 1/2	Cft Country wood	1	12	Cft	102	6	"	
15 8/100	Square Roofing with flat and pan tiles, Countrywood	25	"	Sqr	377	"	"	
	Rafters, Red Rafters							
	Excavating foundations &c				4	"	"	
	Contingencies				74	9	5	
								840
	Cook Room							
14	Cyds Rough Stone in Chunam	4	"	Cyd	56	"	"	
38 11/27	do Burnt brick in Clay and painted with Chunam	3	"	do	115	3	7	
7 46/100	Square Roofing with flat and pan tiles, Countrywood Rafters and Chunam border	25	"	Sqr	186	8	"	
					357	11	7	14020

	Brought over				357	11	7	14020
23 1/4	Cft Country wood	1	12	Cft	40	11	"	
36	Square ft Country wood door	"	6	"	Sq ft	13	8	"
6.72/100	Square feet Plastering with 2 Coats Chunam	3	12	"	Sq ft	25	3	2
	Excavating foundations					4	"	"
	Contingencies					38	11	3
								480
	Grand Total Rupees							14500

Superintending Engineer's Office 1st Dec
Accepted
27th June 1871

Constructing Major R.E.
Acting Superintending Engineer 2nd Div

Specification to accompany the estimate for Constructing Quarters for the Superintendant of Central Jail at Rajamundry.

Amount of Estimate ——— Rs (14,000) ———
Fourteen thousand Rs. Rs per Items be low mentioned
Quarters for the Superintendant Rs 13,180
Stables ——— 840
Cook room ——— 480

Total Rupees 14500

Main Building

Foundations

All walls and pillars to be built with rough stone in Chunam of 4 ft. deep with 2 offsets. The width at bottom 3 ft and at top 2½ ft. The Verandah walls foundations to be of the same materials of 2 ft deep with 2 offsets. The width at bottom 2½ and at top 2½ ft.

Basement of Walls and pillars.

To be three feet high above the ground level, the width 2 ft and to be built with the same materials as above. The bath rooms walls, basement to be 3 ft high above the ground 1½ ft width to be built with the same materials.

Walls above

To be built throughout with rough stone in Chunam of 1½ thick upto 15½ ft high, and the remainder ½ ft to be built with brick in Chunam under rafters. The circular and flat arches over the doors and windows are to be built with brick in chunam of 1½ ft thick.

A Stable and a Cook-room are also included in the Estimate As per Original Estimate and plan.

Lt. Nov 15th 1871

Lt. Nov 15th 1871

Lt. Nov 15th 1871

No, 216

Salem Central Jail Office.

The 31st August 1871

FROM,

THE SUPERINTENDENT OF THE CENTRAL JAIL,

SALEM.

TO,

The Under Secretary to Govt
P.W. Dept
Fort St. George

SIR,

With reference to your Memorandum No. 127 dated 24th August 1871 I have the honour to forward this day's berry by the plan required. As however the house underwent several alterations during its progress, I forward also the rough working plan. You will perceive that there are actually 4 large rooms, whereas only 3 were in the original plan

I have the honor to be
Sir,
Your Most Obedient Servant

A Statute and a Cook-room are also

No. 1116.

10

Memorandum

Mr. Undersigned has the honor to acknowledge the receipt of Memorandum No. 198 from the Under Secretary to Government dated 24th Instant and regrets he is unable to forward for reference the plan of the Superintendent's house at the Central Jail. Conductor Rowe at the Central Jail. Considering as it was only destroyed a short time ago and to its unfinished state. —

Mr. Undersigned has the honor to acknowledge the receipt of Memorandum No. 198 from the Under Secretary to Government dated 24th Instant and regrets he is unable to forward for reference the plan of the Superintendent's house at the Central Jail. Conductor Rowe at the Central Jail. Considering as it was only destroyed a short time ago and to its unfinished state. —

Lt. Colonel Superintendent
Central Jail

26th August 1871

To the Under Secretary
to Government N.W.P.
Fort Saint George

P. W. 1871 Despatches

18 DEPARTMENT

FROM, No. 4122.

THE SUPERINTENDENT

CENTRAL JAIL SAL

P. W. 4450/71.

To, The Undersecretary
to Govt. N.W.P.
Forwarded Govt.

Dated 31st August 18
Rcvd. 1st Sept. 71.

ENCLOSURES. 2.

No. 206

Subject.

Despatch
Plans No 127
Forward 2 Plans
Despatches Home.

No 223.

From Mercantile Assistt: Constantt Sault

To Registrar

The Collector, Godavery Dt.

Sir,

Coconada

With reference to my letter No.
125 of 19th April 1871, I have the honor to
request you will be pleased to direct me whether
there is any objection to my granting one Annadeol
a parwah release of the Godavery house robout &c &c
built for Superintendent: the site being the
same as the one mentioned in the above letter.

I would further state that this is entirely
waste land about 36 acres in extent.

I have the honor &c,

Registrar
21st Augt 1871

Signed/ H. C. McDermott
Asst Collt: Constantt Sault

True Copy

Signed/ H. C. McDermott
Asst Collt: Constantt Sault

Pro 24th August/71 No 128 Revs

P. W. 1871 Dept
From No 4028.
The Actg Inspector Genl;
of Jails
Ootacamund

To The Under Secretary
to Government P. W. Dept
Fort Saint George

P. W. 4450/71.

Dated 26th
Recd 28th August/71

No 1114.

Regrets he is unable
to supply the plan of
the Superintendents'
Quarter at the Central
Jail Coimbatore.

Statement of Materials required for the quarter of
Superintendent of Central Jail at Rajahmundry.

13

Qty	Particulars	Rate	Amount

Copy of Letter
Sent to Collector
Bauary 1873
for a further Quantity
of Oil

Rec'd 1873/71

Rec'd 1873/71

Copy of Letter
Sent to Collector
Bauary 1873
for a further Quantity
of Oil

Rec'd 1873/71

Rec'd 1873/71

Rec'd 1873/71

Statement of Materials required for the quarter of
Superintendent of Central Jail at Rajahmundry.

13

Quantity	Particulars	Rate	Amount
952.000 lbs	of Firewood for burning lime for Chunam bricks. terrace bricks. pillar bricks— flat tiles and pan tiles at 500 lbs—	1 ..	1704 ..
1450 Ft	Teakwood ~~———~~ I.T.	2 ..	3081 4 .
35 Do	— Country wood ———	1 ..	350 ..
1500	Brass small vernier hooks at 100	1 8 .	22 8 .
150	Clasp bars 12" by 10" ———	. 6 .	56 4 .
240	Do — 10"×9" ———	. 5 .	75 . .
160	Parras. Charcoal ———	. 4 .	37 8 .
30	measures of Cobalt varnish for painting boors and windows per diem	2 4 .	77 8 .
10	Hands Wood oil for painting wood work &c	5 ..	50 ..
120	Dozen of screw nails of sizes ———	. 3 .	22 8 .
1	Brick layer Hundry for 6 months —	25 ..	150 ..
1	Do — Carpenter Hundry Do —	25 ..	150 ..
1600 lbs	of Iron required for folding hinges bolts, rafter nails rafter nails and iron work to Lupees. 16 at lbs ~~16~~	. 1 6	150 ..
	Sundry Materials		75 8 .
			6000 ..

Wm. Strachan Major R.E.
Sy. Superintendent Engineer
16 Div

P.W. 4480/71

From The Collector of Godavery &c
To Captain Strachan R.E.
Rajahmundry
Dated 10th June 1871
Rec'd 23rd do
Knd. 26 do

Sir I have the honor to forward herewith Invoice of Stores for the month of May 1871 as per margin & to request you will be pleased to cause the Articles specified to be supplied from the Public Stores at Rajahmundry

I am Sir
Your most obedient Servant
Collector

Rajahmundry 10th June 1871

Rs. Invt. 1573/71

Rs. Invt. 1573/71

No 2438 P.W.D.

Pre-reading Office Boards Copy.

Read the following

Rec. Office Boards Copy. 1/3

Asst. Engineer 11/4 Circle (W. E. Dy 12638 11/4 Sept 71

Communicated

to the Superintending

Engineer of the 1st

Division with the

request that the building

of Quarters

may be taken for entry

in the Provincial

Budget for 1872/73.

Encl

Estimate of Cost of

materials required

for Office Quarters at

Agalawady Contt:

Encl.

Rs. 6000.

P.W. 4450/71

Dno 23d Sept 71 de L 407.—

L. prd. 1573/71

No 4650-

Sobt. of {1871} Madras.

PUBLIC WORKS.

Superintending Engr
1st Division

Encl. 12

G. O 23 Septr. No 2438.

Nos. 4074408

Quarters - the S. Septr 9th
1st to be separated to include
the quarters for the Septr 9th
Regiment at present in his list
of Roads for Lucky entitled
Division Budget for 1872/73.