M.R.O. 1—77,000—3-6-37.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works **DEPARTMENT.**

G.O. No. 2528 59-60	Press ~~Mis.~~
Dated 5-10-	18 71.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 5th October 1871.

No. 59. Read the following letter from the Officiating Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 16th September 1871, No. 134 :—

1 Estimate.
1 Specification.
1 Plan.

WITH reference to G. O., No. 110, of the 19th August 1871, I have the honour to state that the additions and alterations proposed to the Salem Talook Cutcherry are few, but indispensably necessary.

2. The cutcherry itself is a building of a very ancient date, though substantial enough, but the interior accommodation is most inconvenient, and the records, the Revenue Establishment, and the Police are crammed together. The proposed alterations will give a separate and spacious room for the records, an adequate room for the Police, and a properly arranged office room for the Tahsildar and Sub-Magistrate.

3. The estimate amounts to only Rupees 865, and I trust that, under the circumstances above stated, these urgently required alterations will be sanctioned.

No. 60. ORDER THEREON, 5th October 1871, No. 2,528.

CIVIL WORKS, No. 5.

THE plan and estimate which have been re-submitted with this letter are sanctioned, but the Government, in this Department, have no money at their disposal for appropriation to the work at the present time.

(True Extract.)

Captain, R.E.,
Offg. Joint Secretary to Government.

To the Superintending Engineer, 5th Division, with Specification.
„ Controller of Public Works Accounts.
„ Revenue Department.
„ Financial do.

Exd. S. T. Augustin.

No 134.

Superintg: Engr's Office, 5th Divn,
Cuddalore 10th September 1871.

From,

The Offg: Superintending Engineer,
5th Division.

To,

The Secretary to Government,
Public Works Department.

Sir,

Enclosures 3.
1 Estimate.
1 Specification.
1 Plan.

With reference to G. O. No 110 of the 19th August 1871, I have the honor to state that the additions and alterations proposed to the Salem Taluk Cutcherry are few, but indispensably necessary.

2. The Cutcherry itself is a building of a very ancient date, though substantial enough, but the interior accommodation is most inconvenient, and the records, the Revenue Establishment, and the Police, are crammed together. The proposed alterations will give a separate and spacious room for the Records, an adequate room for the Police, and a properly arranged Office room for the Tahsildar and Sub Magistrate.

3. The estimate amounts to only Rs 865

and

and I trust that, under the circumstances above stated, these urgently required alterations will be sanctioned.

I have the honor to be
Sir,
Your most obedient Servant

James Fortt Captain R.E.,
Offg: Superintg: Engineer, 5th Div.

5th Division, D. F. W.

New works.

Salem Taluk.

Buildings.

Salem District. — Salem Range. —

Abstract Estimate of 1871-72.

Rec'd 19th Aug 1871 No 110 Bis

No 1871 Dept
Roads & Buildings
The Offg: Supt: Engineer, 5th Division.
Amount Total

Rupees

From Fort No. D 422.

Salem Range at Salem.

To, The Secretary to Government, Madras. Dated 16th September 1871. Rec'd 18th } No 134.

Enclosures 3.

Taluk Kutcherry at Salem.

Resubmitting the plan & Estimate for the alterations proposed to the Taluk Kutcherry at Salem, with detailed explanations as to the nature and necessity of these alterations.

No 2528-5 dated 5th October 71

	2	54
	179	6
	19	11
	18	..
	61	4
	53	8
	187	8
	18	..
	116	..
	7	8
	100	..
	36	..
	10	..
	9	6
	5	..
	823	8 4

859

Coty 20 Sept 71

Sundries at 5 per Cent. — 41 7 8

Total Amount of Estimate Rupees — 865 ..

Salem Range Office
Dated, 8th July 1871.

C. J. Lawley
Collector of Salem.

Signed A. C. Lawford
Executive Engineer

A Fortt Colonel, R.E.
Superintending Engineer 5th Div.

and I trust that, under the circumstances above stated, these urgently required alterations will be sanctioned.

I have the honor to be

Sir

Your

5th Division, D. F. W.

New works.

Civil Buildings.

Salem Taluk.

Salem District. — Salem Range.

Abstract Estimate of 1871-72.

Work. Making certain alterations to the Taluk Cutcherry at Salem.

Quantity	Description of work.	Rate	Per	Amount	Total
28	Cubic yards of Earthwork	1 4	Cyd	2 5 4	
71 3/4	do of Brick in mud	2 8	do	179 6	
5 3/4	do of Brick in chunam	3 12	do	19 11	
4	do of Archwork	4 8	do	18 ..	
24 1/2	Squares of Plastering	2 8	Sqe	61 4	
26 3/4	Cubic feet of Jungle wood work	2 ..	Cft	53 8	
12 1/2	Squares of Roofing with palmirah rafters, bamboo reepers and pot tiles	15 ..	Sqe	187 8	
6	do of Flooring with concrete	3 ..	do	18 ..	
58	Running feet of Wooden railings common including wood oiling	2 ..	Rft	116 ..	
3 3/4	Squares of Shifting and relaying tiles in old roof	2 ..	Sqe	7 8	
4	Pannelled windows 3'x5' with frames, hinges iron bars complete including the cost of fixing	25 ..	Each	100 ..	
3	do do 2 1/2 x 3 do	12 ..	do	36 ..	
2	Removing and refixing doors in Tahsildar's Cutcherry and Police room	5 ..	do	10 ..	
12 1/2	Cubic feet of cut stones undressed	.. 12	Cft	9 6	
	Removing old walls and flooring of store room	.. ..	..	5 ..	
				823 8 4	
	Sundries at 5 per Cent			41 7 8	
	Total Amount of Estimate Rupees			865 ..	

(Signed) A. C. Lawford
Executive Engineer

Salem Range Office
Yercaud, 8th July 1871.

C. J. Lawley
Collector of Salem.

A Burleau
Colonel, R.E.
Superintending Engineer 5th Div.
7th 7/71

Public Works Department

No. 2528.

Proceedings of the Madras Government

Read the following

From

The Supt.g. Engineer of the 6th Division } (No. 6 No. 134 & 18 Sept. 71)

The plan and estimate which have been recommitted with this letter are sanctioned but the Government in this Department have no money at their disposal for appropriation to the work at the present time

23 Sept.

To

The Supt.g Engr. 6th Div. with Spcon.
" Controller P. W. Accts
" Rev: Departt.
" Finance
" Public Works Estimate for erecting certain additions to the Jail & Lock hospital at Salem.
" Amount of Estimate Rs 8805.

Depts 6/10/71

C. No. 4422.

Govt. of {1871} Madras.

PUBLIC WORKS.

To The Superintending Engr.
5th Division

Dated

Rec'd Encl. 2

G. O. 5th Oct 1871, No. 2528

Nos. 59 & 60

Labour Collectory at Salem

Estimate sanctioning
with the remarks
as noted
at the