M.R.O. 1—77,006—8-6-37.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

public works. DEPARTMENT.

G.O. No. 2647 Press Mis.
-89
Dated 15 (c - 18 1 .

Not to be folded or roughly handled

G1
1

Proceedings of the Madras Government. Public Works Department, 18th October 1871.

No. 288. Read the following letter from the Officiating Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 27th September 1871, No. 145 :—

WITH reference to G. O., No. 225, of the 20th January 1870, I have the honour to submit, for the sanction of Government for entry in the Budget of 1872-73, an estimate of Rupees 1,110, accompanied by plan and specification, for constructing solitary cells for Sappers and Miners at Bangalore.

1 Estimate, Rupees 1,110.
1 Specification.
1 Plan.
1 Site Plan.

2. The plan and estimate have been approved of by His Excellency the Commander-in-Chief.

No. 289. ORDER THEREON, 18th October 1871, No. 2,647.

MILITARY WORKS, No. 7.

THE estimate of Rupees 1,110 submitted with this letter for constructing solitary cells for Sappers and Miners at Bangalore is sanctioned.

2. An application for funds should be submitted after the 1st April next.

(True Extract.)

Captain, R.E.,
Offg. Joint Secretary to Government.

To the Superintending Engineer, 5th Division.
" Controller of Public Works Accounts.
" Military Department.

Exd. E. C. Shunker.

No 145

Superintg: Engrs Office, 5th Divn,
Cuddalore, 27th September 1871.

From,

The Offg: Superintending Engineer,
5th Division.

To,

The Secretary to Government,
Public Works Department.

Sir,

With reference to G. O. No 225 of the 20th January 1871, I have the honor to submit, for the sanction of Government, for entry in the Budget of 1872-73, an Estimate of Rupees 1110, accompanied by Plan and Specification, for Constructing Solitary Cells for Sappers and Miners at Bangalore.

2. The plan and estimate have been approved of by His Excellency the Commander-in-Chief.

I have the honor to be
Sir,
Your most Obedient Servant.

Encl 4 papers.
Estimate, Rs 1110
Specification
Plan
Title of Plan

Jacob Cortlandt Capt R. E.,
Offg: Superintg: Engineer, 5th Div.

5th Division S. C. P. Wks.

Military.

Bangalore.

New Works.

Abstract Estimate &c. for 1871-72.

For Constructing Solitary Cells for Sappers and Miners at Bangalore.

Quantity.	Description of Work.	Rate	Per	Amount	Total
742	Cubic feet of excavation		1	Cost	4
742	Do. Foundation, Stone in Chunam	2 6	Do.	116	
308	Do. Basement, Do.	2 6	Do.	48	
1,638	Do. Superstructure, Brick in Chunam	2 9	Do.	276	
81	Do. Arch work, Do.	4	Do.	20	
116	Running feet of Cornice work	4	Each	29	
27 1/10	Squares of Plastering with 2 Coats of Chunam	2 8	Sq.	69	
14-62	Do. Whitewashing, two coats	3	Do.	3	
13-23	Do. Bluewashing, two coats	4	Do.	3	
29 17/24	Cubic feet of Sea Coast wrought Teak	3 8	Cost	104	
20	Nos. of Nails, 6" long	6	Each	1	
3-25	Squares of Terracing with brick on edge, 3" Jelly, 3 Courses of flatties and 3 Coats of Chunam	27 8	Sq.	89	
1-78	Squares of Lime terracing with planed teak rafters 4 Courses of flatties and 3 Coats of Chunam	19	Do.	15	
2-56	Squares of Wood oiling, two coats	2	Do.	5	
295	Cubic feet of Filling in basement		1/4	Cost	1
2-47	Squares of Paving with Stone slabs set in mortar & pointed with lime putty	15	Sq.	37	
	Carried Over			820	

Rd 20th January 1872

From Lieut. Colonel [illegible]
Chief Engineer Southern Division
Bangalore

To
The Secretary to Government
P. W. Department.

No. 1871 Dated 27th December 1871.

Recd. 29th do.

No. 145 T.C.

Enclosures 4

Sir,

I have the honor to submit for sanction an estimate for Rs. 1110 for Constructing Solitary Cells for Sappers & Miners at Bangalore.

No. 2649 - 18" Oct. 71

Copy to Capt. Walker

No. 288

	Brought over			820	- -
16	Rft. of Stone Slabs tread for steps	-	3 - Rft.	3	- -
4	Nos. of Stone pillars 9'' × 1¼ × 2½	3	- - Each	12	- -
4	" of Stones 1½ long and 9" Square	-	8 - do.	2	- -
33	Rft. of Wrought iron Spouts 3" inner Diameter & 1/8 thick	-	12 - Rft.	25	- -
2	Pairs of Battoned doors 3 × 6 with frames and hinges, hooks, locks, &c. Complete	18	- - each	36	- -
2	" Battoned doors 2 × 5 with frames, hinges, hooks, locks, &c. Complete	10	- - do.	20	- -
6	Iron barred attic windows 3 × 1½ with frames &c. complete	6	- - do.	36	- -
6	Wooden sun Shades over attic Windows	9	- - do.	54	- -
3·11	Sq. of Corcous attic Carrosine paint-chocolate Color, two coats	5	- - Sq.	16	- -
1	No. of Marking board	5	- - each	5	- -
2	Sloping boarded Cots	12	- - do.	24	- -
				1,053	- -
	Sundries			57	- -
	Total Estimate Rupees			1,110	- -

Rupees One thousand, one hundred & ten only.

/Signed/ H. B. Wood Capt. R. E.,
Executive Engineer, Bangalore.

Exe: Engrs office,
Bangalore,
26th June 1871.

Actg. A.G. 2d Mr. General's Office Mr. 3d,
Bangalore, 30th June 1871.
"Approved"
By Order
/Signed/ B. Mr. Deane Major
Actg. A.G. 2d Mr. Genl. Br. 2d.

Lawrence Hyde Captain R.E.
Offg. Superintg. Engineer, 5th Div.

Pub Dept

No 2647

Proceedings of the Madras Government

Under date the 18th October 1871

Read the following

From the Offg Supt Engineer
5th Div (Executive No 1455/27 Sept 1871)

The estimate of
Rs 1110 submitted with
this letter for constructing
Solitary Cells for Sappers
and Miners at Banga-
-lore is sanctioned.

An application
for funds should be
submitted after the
1st April next.

Actl

Offg Sec

Supt Engr 5th Div Circle Speft
Controller P. W. Accts
Military Departt
Dated 19/10/71.

1/165/71

5th Division P. W.

Bangalore.

P. W. 4815/71

Abstract Estimate for
Constructing Solitary
Cells for Sappers and
Miners at Bangalore.

Amount of Estimate Rs 1110—

Dated 27 Sept 1871

C-20-4615-

Govt. of [1871] Madras.

PUBLIC WORKS.

To

The Superintending Engineer
5th Division

Dated

Rec'd. Encl. 3

G. O. 18th Octr. No. 2647.

Nos. 288-289

Sanitary Cells for Lepers
& Coolies Bangalore-

Estimate of Rs 1110
sanctioned & the P. Engr
instructed to apply for
funds after the 1st April
1872-