M.R.O. 1—77,000—8-6-37.

(1) Number of pages 12

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2765 Press / Mis.

13-14

Dated 1—11— 1871.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 1st November 1871.

No. 13. Read the following letter from the Officiating Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Camp at Ahtoor, 8th October 1871, No. 153:—

1 Estimate, Rupees 600.
1 Specification.
1 Plan.

With reference to G. O., No. 172, of the 20th September 1871, I have the honour to submit, for the sanction of Government, an estimate of Rupees 600, accompanied by plan and specification, for converting the old coffee room and oil godown at the east side of the General Parade, Bangalore, into a school of Army signalling.

2. The plan and estimate have been approved of by His Excellency the Commander-in-Chief.

No. 14. Order thereon, 1st November 1871, No. 2,765.

MILITARY WORKS, No. 1.

The estimate submitted with this letter is sanctioned, funds being provided as directed in the orders quoted by the Superintending Engineer.

(True Extract.)

Suptg. Engrs. Office, 5th Dn.,
Camp, Hebbal, 8th October 1841.

No. 153

From,

Captain James Vertue R. E.,
Officiating Suptg. Engr., 5th Dn.

To,

Colonel J. Carpendale R. E.,
Secretary to Government,
Pub: Works Depth.

Sir,

With reference to G. O. No. 192 of the 20th September 1841, I have the honor to submit, for the Sanction of Government, an Estimate of Rupees 600, accompanied by plan and specification, for converting the old Coffee room and Oil Godown at the East side of the General Parade, Bangalore, ~~ground~~ into a School of Army Signalling.

2. The plan and Estimate have been approved of by His Excellency the Commander-in-Chief. I have the honor to be

Sir,

Your most Obdt. Servant

James Vertue Capt. R. E.
officiating Suptg. Engr. 5th Division

Enclosures 3
1 Estimate Rs 600.
1 Specification
1 Plan.

No 13
Dated 16 Oct 1871

Dated 8th Oct 1871

From Lieut Colonel R. Pollock
Commanding 3rd Brigade Div. Sig. Corps
To Major Genl. Sir Arthur Cotton K.C.S.I.
Chief Engineer
&c. &c. &c.

Sir,

I have the honor to forward for the sanction of the Government of India the accompanying Estimate for converting the old Coffee room and Oil godown on the East side of General Hd. Qrs. ground into a School of Army Signalling at Bangalore.

2. The Estimate amounts to Rupees 1,000 and I request that the Sanction of the Government of India may be communicated to me by Telegraph.

I have &c.
(Signed) R. Pollock
Lieut Colonel
Commanding 3rd Brigade
Signalling Corps

No 1653

Enclosures 3.

Forwarding for sanction an Estimate of Rs. 1000 for converting the old Coffee room and Oil godown East of Hd. Qrs. ground into a School of Army Signalling.—

Dated 17 Oct 1871

Recd 17 Oct 1871

5th Division D. P. W.

Bangalore.

New Works.

Abstract Estimate of 1871-72.

Converting Old Coffee room and Oil godown on the East side of General ground into a School of Army Signalling at Bangalore.

Description of works	Rate	Per	Amount	Total
Squares of Dismantling the roof	8 .	Sqre	3 . .	
Cubic feet of Knocking down walls	. 3	Cft.	15 . .	
ditto of Excavation	. 1	do	1 . .	
ditto of Foundation stone in mud	1 9	do	21 . .	
ditto of Superstructure brick in mud	1 9	do	66 . .	
Running feet of Brick coping over rear walls of Store room.	5 .	Rft.	9 . .	
ditto of Almond Sticks treenail for 1 door	4 .	do	5 . .	
No. of Teakwood lintels for doors 4½ feet	4 . .	Each	4 . .	
do 3 feet	3 . .	do	21 . .	
Squares of Plastering with two coats of chunam	2 8	Sqre	27 . .	
ditto of Whitewashing two coats	. 3	do	19 . .	
ditto of Ceiling	. 4	do	12 . .	
ditto of Bluewashing do	. 4	do	8 . .	
Running feet of Ridge ventilators	3 14	Rft	54 . .	
No. of Finishing off pillars	3 . .	Each	36 . .	
pairs of Shutters with frames and fittings complete 3×6	18 . .	do	72 . .	
ditto of Glazed window shutters (without frames) and fittings complete 3×5	12 . .	do	48 . .	
ditto of Glazed window shutters (without frames) and fittings complete 3×4	10 . .	do	40 . .	
Squares of Chocolate painting two coats	5 . .	Sqre	79 . .	
Carried over			540 . .	

	Brought forward			540 . .
1	N° of Marking board	5 . .	Each	5 . .
13	— of Inventory do	. 12 .	do	10 . .
	Sundry repairs			15 . .
				570 . .
	Sundries.			30 . .

Total Amount of Estimate Rupees — 600 . .

Rupees Six hundred only.

Executive Engineer's Office
Bangalore, 31st July 1871.

[Signed] H. W. Wood Captain &c.
Executive Engineer, Bangalore.

I recommend

Captain, &c.E.
Offg. Superintending Engineer, 5th Dn.

Counts Abstract

No 65 dated 11th Oct. 1871 P.W.D.

Proceedings of Major Quarterly Court

Read the following

From

The Supdg Engr
5-Div.

(No. E. dated 15th Sept 1871)

The estimate sent
with this letter
is sanctioned, funds
being provided
in the manner
directed in the orders
quoted by the Superin-
tending Engineer.

By Order

H.A.

Supdg Engr 5th Div. with
Contractors
Early despatch

Dept 12/10/71

5th Division, D. P. W.

Bangalore.

P.W. 4878/71

Abstract Estimate for
Converting Old Coffee Room and
Oil Godown on the East side of
General Parade ground into a
School of Army Signalling at
Bangalore.

Amount of Estimate Rs. 600—

Contd 2nd Copy

Ch with 16 Oct/71

C-ho-4878

Govt. of (1871) Madras.

PUBLIC WORKS.

To The Superintending Engr
5th Division

Dated

Rcvd. — Encl. 2

G. O. 1st Nov. No. 2765.

Nos. 13914

School of Army Signalling at Bangalore. Estimate of Rs 600 sanctioned for connecting the old coffee room and Sd Jamun end of the general parade with a school of Army Signalling sanctioned —

C. Court 16 Oct 71