M.R.O. 1—77,006—8-6-37.

(1) Number of pages 14

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 2827. Press Mis.

135-36

Dated 8 11 , 1871.

Not to be folded or roughly handled

4

Proceedings of the Madras Government, Public Works Department, 8th November 1871.

No. 135. Read the following letter from the Special Executive Engineer, Wynaad, to the Secretary to Government, Public Works Department, dated Luckadie, 14th October 1871, No. 484:—

WITH reference to Proceedings of Government, No. 109, dated 15th January 1869, I have the honour, in connection with paragraph 3 of the Proceedings of the Board of Revenue, incorporated in above G. O., to forward a supplementary and revised estimate* for the Deputy Collector's Cutcherry at Manantoddy, substituting in obedience to G. O., No. 596, dated 24th February 1869, and G. O., No. 2,881, dated 9th September 1868, brick-in-chunam for those portions of the building previously estimated for as brick-in-mud, and asphalte flooring for the chunam floor of the original estimate; there is also an item for compensation for land taken up for site of the building which was not before included.

Public Works Department G. O., No. 267, dated 28th January 1869.

* Rupees 3,860.

2. The requirements for 1872-73 are made in anticipation of the revised estimate being sanctioned.

No. 136. ORDER THEREON, 8th November 1871, No. 2,827.

CIVIL WORKS, No. 6.

IN G. O., No. 267, of the 28th January 1869, an estimate of Rupees 13,580 was sanctioned for constructing an Office at Manantoddy for the Deputy Collector and Magistrate of Wynaad, the estimate provided for the greater portion of the walls being constructed of brick-in-clay.

2. With the letter recorded at the head of these Proceedings the Special Executive Engineer, Wynaad, in conformity with the instructions contained in a subsequent order submits a revised estimate of Rupees 17,440.

G. O., No. 596, 24th February 1869.

3. The excess is due to the substitution of brick-in-chunam for brick-in-clay in the walls, to the provision of asphalte for the floor, and to compensation for the site omitted in the original estimate.

4. Under the explanation afforded the Governor in Council sanctions the revised estimate of Rupees 17,440 for constructing the Deputy Collector's Cutcherry at Manantoddy.

5. The subject of paragraph 2 of Major Kennedy's letter will be considered when the Budget for 1872-73 comes under review.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Special Executive Engineer, Wynaad.
,, Controller of Public Works Accounts.

Exd. S. T. Augustin.

=nal Estimate; there is also an item for compensation for land taken.

Special Executive Engineer's
Office Wynaad Sub Division
14th October 1871.

No 1484.

From,

The Special Executive Engineer.
Wynaad.

To,

The Secretary to Government
Department Public Works.
Madras.

Sir,

With reference to Proceedings
P.W.D. G.O. No 267 dt/28th January 1869. of Government No 109 dated 15th January
1869 I have the honor in connection
with para: 3 of the Proceedings of
the Board of Revenue incorporated
in above G.O. to forward a supple-
+ Rs. 3860. .. .. =mentary and revised estimate
for the Deputy Collector's Cutcherry at
Manantody, substituting in ch.
=dience to G.O. No 596 dated 26th Febru-
=ary 1869 and G.O No 2881 dated 9th
September 1868 Brick in Chunam
for those portions of the Building
previously estimated for as Brick
in mind; and Asphalte flooring
for the Chunam floor of the origi-
=nal Estimate; there is also an
item for compensation for land
taken

taken up for site of the building which
was not before included.-

2. The requirements for 1872-73.
are made in anticipation of the re-
vised estimate being sanctioned.

I have the honor to be,
Sir,
your most obt Servant.

Bvt Lt. U. Kennedy Capt
Aph. U.S. Engineer Depot.-

Civil Buildings. 7

Malabar District
Wynaad Division

New Work.

Comparative Statement shewing the Excess of the Revised over the Original Estimate for Constructing a Public Court House at Manantoddy.

Description of Work	Original Estimate Quantity	Rate	Per Item	Amount	Revised Estimate Quantity	Rate	Per Item	Amount	Increase	Decrease
Brick in Clay ... Cft.	49601/2	23	C. ft. 100	3440 11 11	"	"	"	"		3440 11 11
Brick in Chunam. ... do	4446 16/21	40 8	do	18000 10 1	19407/8	40 8	C. ft. 100	7859 10 0	6059 " 7	" " "
Flooring ... Sqre.	314/5	6 8	Sqre.	2224 10	"	"	"	"	"	2224 10
Flooring with Asphatte ... do.	"	"	"	"	314/5	27 "	Sqre.	923 6 5	923 6 5	" " "
Wood Work. ... Cft.	3741 12/40	2 12	Cft.	864 3 11	314	2 12	Cft.	864 3 11	" " "	" " "
Plastering 3 Coats ... Sqre.	111 2/5	14 "	Sqre.	1559 9 7	111 2/5	14 "	Sqre.	1559 9 7	" " "	" " "
Roofing. ... do	49 1/2	23 "	do	1138 8 "	49 1/2	23 "	do	1138 8 "	" " "	" " "
Peepers ... Rft.	6006	25 "	Rft. 1000	150 2 5	6006	25 "	C. ft. 1000	150 2 5	" " "	" " "
Iron Work including Carriage ...	"	" "	"	1799 3	"	" "	"	1799 3	" " "	" " "
Panelled Screen ... Sft.	153	1 2	Sft.	172 2	153	1 2	Sft.	172 2	" " "	" " "
Doors Glazed 7 2/3 × 4 2/3 No.	10	51 12	each	517 8	10	51 12	ea	517 0	" " "	" " "
Do. Panelled 7 × 3 1/2 do.	5	38 "	ea	190 "	5	38 "	ea	190 "	" " "	" " "
Do. Do. 7 × 3 1/4 do.	2	35 14	ea	71 12	2	35 14	ea	71 12	" " "	" " "
Do. Do. 8 × 4 1/6 do.	1	43 10	ea	43 10	1	43 10	ea	43 10	" " "	" " "
Windows glazed 4 2/3 × 4 2/3 do.	7	37 "	ea	259 "	8	37 "	ea	296 "	37 " "	" " "
Do. Panelled 4 2/3 × 3 1/2 do.	2	25 9	ea	51 2	2	25 9	ea	51 2	" " "	" " "
Segmental Ventilators ... Sft.	56	1 2	Sft.	63 "	56	1 2	Sft.	63 "	" " "	" " "
Sundries ...	"	" "	"	1236 8	"	" "	"	1565 4 9	328 12 9	" " "
Compensation for Land ...	"	" "	"	" "	"	" "	"	175 "	175 " "	" " "
Total				13580 " "				17410 " "	7523 3 9	3693 3 9

Pro 9th Sept/68 Pl 584.
" 28 Jany/69 — 585 586
" 24 Feby — 599-600

Pro Dr. 1871 Dept. from Chief Engr. Nov. 4916.

The Spl. Sn. Engineer Wynaad

To,

The Secretary to Govt. P. W. Dept. Madras

Dated 14th October 1871
Received 17th

Encl: 1.-✓
No. 484.-

Submits a Revised Estimate for the Deputy Collector's Office at Manantoddy.-

No. 2827-8 Novr/71

No. 135

Copy 20 Oct/71 No. 365

Spl. Sn. Engineer's office
Vythery Wynaad
14 October 1871.-

W. Z. Kennedy. Capt.
Spl. Sn. Engineer Wynaad.

Civil Works No. 2827

Public Works Department

Proceedings of the Executive Engineer Wynaad

Read the following

From the Special Executive Engineer Wynaad (H.C. No. 4846/14 Octr 1870)

Ent. C. O. No. 267 of

the 28th January 1869.

Estimate of Rs. 13,680, was

Sanctioned for constructing an

Office at Manantody for

the D.C. Collector and Magistrate

of Wynaud, the Estimate

provided for the greater

portion of the walls being

constructed of Brick in

clay.

With the letter re-

corded at the head of

these Proceedings the

Special Executive Engineer

Wynaud

A/A.

P.R. 4916/71

Forwarded plan

and Estimate

for the proposed

Office of the Head

Assistant Collector

& Public Functionary

at Manantody

Wynaud in conformity with
the instructions contained
in a subsequent Order
submits a revised Estimate
of Rs. 17,440.

G. O. No. 596
24th February 1869.

The excess is due
to the substitution of
Brick-in chunam for
brick in clay in the wall,
to the provision of asphalte
for the floor, and to omi-
ssion for the Site omitted
in the original Estimate.

Under the explana-
nation afforded ~~His~~
~~Excellency~~ the Governor in
Council sanctions the
revised Estimate of
Rs. 17,440 for constructing
the Deputy Collector's Cutcherry
at Manantody.

The subject of
para 2 of Major Kennedy's
letter will be considered
when the Budget for
1872/3, comes under
review.

H.E.G.

24 Oct.

22
3

To The Special Ex: Engr.
Wynaud
" - Controller of P.W. Accounts.

Dept. 9/11/71.

No. 4916

Govt. of {1871} Madras.

PUBLIC WORKS.

To

The Special Executive Engr.
Nyanad

Dated

Recd. Encl. 1

G. O., 8th Novr 1871, No. 2827.

Nos. 135 & 136

Dy. Collectors Cutcherry at Ramanatdy. The revised estimate of Rs. 17,440 for constructing the Dy Collectors Cutcherry at Ramanatdy, sanctioned with remarks.

6 Octy 20 Octr/71