M.R.O. 1—77,006—8-6-37.

(1) Number of pages 7

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works. **DEPARTMENT.**

G.O. No. 3037 Press / Mis.

13-14-

Dated 1 - 12 — 1871.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 1st December 1871.

No. 13. Read the following letter from the Officiating Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 15th November 1871 No. 180:—

I HAVE the honour to submit, for the sanction of Government, from the grant of Rupees 3,000 "Minor New Works," Military, at Bangalore, an estimate of Rupees 140 for providing trap doors to upper stories of two male Hospitals of Cavalry and Artillery, one female Hospital, and two Recreation and Orderly Rooms for Cavalry on the Race Course, Bangalore.

1 Plan.
1 Estimate.
1 Specification.

2. The plan and estimate have been approved of by His Excellency the Commander-in-Chief.

No. 14. ORDER THEREON, 1st December 1871, No. 3,037.

MILITARY WORKS, No. 1. SANCTIONED.

(True Extract.)

5th Division, D. F. W.

Military. — Bangalore. — New Works.

Abstract Estimate of 1871-72.

Work.—Providing trap doors to upper stories of Two Male Hospitals of Cavalry and Artillery, one Female Hospital and two Recreation and Orderly rooms for Cavalry on the Race Course, Bangalore.

Quantity.	Description of work.	Rate	Per	Amount	Total
3-3--	Cubic feet of Teak wood wrought and put up	4 . .	Cft.	13 . .	
1	1 No. of Sheet iron (4×3×1/16)	3 6	Each	3 6	
2	Pairs of Hinges with Screws	4 8	do pair	1 . .	
2	No. of Iron hooks (18" long and 3/4 thick)	2 . .	do	4 . .	
9 27/32	Cubic feet of Dismantling terrace	. . 6	Cft.	4 11	
2	No. of Bolts including screws	1 . .	Each	2 . .	
	Painting chocolate color			5 . .	
	Fixing the frame & Co. in cement			2 11 .	
				26 15 11	
	Sundries			1 . 1	
	Total Rupees for One			28 . .	
	Total Amount of Estimate Rupees for Five			140 . .	

Rupees One hundred and forty only.

Executive Engineer's Office
Bangalore, 19th September 1871.

(Signed) H. W. Wood Captain, R.E.
Executive Engineer, Bangalore.

Approved
By Order
(Signed) B. M. Deane Major
Asst. Qr. Mr. General
Mysore Divn.

Asst. Qr. Mr. General's Office, Mysore Dn.
Bangalore, 23d September 1871.

Lancelot Wardell Captain, R.E.
Officiating Superintending Engineer, 5th Dn.

59.

1880.

Superintg: Engineer's Office, 5th Division,
Cuddalore, 15th November 1880.

From,
Captain James Vertue R.E.,
Offg: Supg: Engineer, 5th Division.

To,
Colonel J. Carpendale R.E.,
Secretary to Government, S.W.D.

Sir,

I have the honor to submit, for the sanction of Government from the grant of Rs. 3000.. Minor New Works," Military, at Bangalore, an estimate of Rupees 140.. for Dividing trap doors to Upper Stories of two Male Hospitals of Cavalry & Artillery, one Female Hospital, & two Recreation & Orderly rooms for Cavalry on the Race Course, Bangalore.

Courier 3.

n/ imate

cification

2. The plan and estimate have been approved of by His Excellency the Commander-in-Chief.

I have the honor to be
Sir,
Your most Obedient Servant.

James Vertue Captain R.E.,
Offg: Supg: Engineer, 5th Division.

Public Works 1871 Department

From Lt. Col. Supt. Engineer
5th Division

To The Secty. to Government,
P.W. Department

Dated 15th November 1871.
Rec'd 20th

No. 180.

Enclosures 3.

Trap doors. — 1 & Rd in

Submits for the sanction of Government an estimate of Rs. 1140 for providing Trap doors to upper Stories of 2 male Hospitals of Cavalry and Artillery Dets. Bangalore.

No. 3037 1st Dec. 71

With an order

No. 3037

Executive Engineer
Cantonment
Military Dept.

625 Sheets @ Rs. 28.

Copied 4/12/71.

No. 5514

Govt of India Works

PUBLIC WORKS.

To The Superintending Engr.
5th Circle

Dated. 1-8-1887

Rcd. 2

Ans. 1st Dec 1887.

Nos. 13414

Military Railways. Estimate of Rs: 140 for providing traps doors to certain Rly: Bridges on the Line Course at Bangalore, Sanctioned