

(1) Number of pages 9
(2) Date of receipt 12.28.1911
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No.	764	Press
359-360		Mis.
Dated	14-3	1871

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
14th March 1871.*

No. 359. Read the following letter from the Superintending Engineer, 6th Division, to the Secretary to Government, Public Works Department, dated Camp at Velangunny, 4th March 1871, No. 1,034 :—

1 Estimate, Rupees 194, for constructing screen walls to privies of family quarters of the Royal Artillery at Trichinopoly. .
1 Plan,

I HAVE the honour to forward, for the sanction of Government, the estimate noted in the margin. It has received the approval of His Excellency the Commander-in-Chief.

No. 360. ORDER THEREON, 14th March 1871, No. 764.

MILITARY WORKS, No. 14.

SANCTIONED.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

Military Army
Accommodation
for Troops.

Trichinopoly District - Minor New Work
Abstract Estimate No. 70-71.

Works - Constructing Screen Walls to Drivies of
Family Quarters Artillery at Trichinopoly -

Contents	Description of Charges -	Rate	Amount	Total
22 $\frac{3}{4}$	Cyds. of Secumation	@ " 1 .. C ^{rs}	1 66	
991 $\frac{7}{16}$	Cyds. of Brick in chumam	@ " 2 .. C ^{rs}	123 14 10	
1781 $\frac{1}{2}$	Sq ^{ts} of Plastering one Coat	@ 18 .. S ^q ^{ts}	26 11 7	
196	Do of Honey Comb tiling	@ 5 .. "	9 12 10	
52	Openings, demolishing & plastering	6 .. " each	19 8 "	
1999	Sq ^{ts} of Yellow washing	@ " 2 .. S ^q ^{ts}	2 8 "	
316	Do of white washing	@ " 19 .. "	5 6	
			184 3 3	
	Sundries & Contingencies		9 12 9	194 ..

Total Estimate Rupees 194 ..

(Signed) J. Virtue. Captain R.E.
Sec Engineer Trichinopoly

Superior Officer
Camp Chappaputro
30th January 1871

H. F. Dates Capt. R.E.
Super Engineer 6th Division.
Order Office Lucknow S^{rs}.
Trichinopoly 13th Feb^y 1871.
H. Hume Captain
Off. assigned Major S^{rs}.

No 1034

Sup Engineer's Office
Camp Velangunny 4 March 1871.
55

From, Captain R. F. Baker R.E.
Superintending Engineer - B. Div.

To, Colonel C. A. Orr R.E.
Secretary to Government. P.M.D.

Sir, I have the honor to forward for the sanction of Government the Estimate noted in the margin. It has received the approval of His Excellency the Commander-in-Chief. I have the honor to be

Yours most obedt. servt.

R. F. Baker R.E.
Sup Engineer B. Div.

Billingsbury
Accountant General
Superintendent
Colonel C. A. Orr R.E.
Secretary to Government
P.M.D.
4 March 1871

Enclosed in letter
from the Sup Engineer
B. Div. to the Secy.
to Govt. P.M.D.
No 1034 dated
4 March 1871.

10/10/71

10/10/71

11/7/42
Govt. of 1871 Madras.

PUBLIC WORKS.

To The Superintending Engrs
Public Division

Dated.

Recd.

Encl. 2

G. O. 14th March 1874

Nos. 359-360

Privies. The estimate of
Rs. 144 for screen walls
& Privies of 4 family
quarters of the Royal
Artillery at Trichinopoly,
Sanctioned.