

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 1487	Press
254-255	Mis.
Dated 15-7	182

Not to be folded or roughly handled

17

*Proceedings of the Madras Government, Public Works Department,
15th June 1872.*

No. 254. Read the following letter from the Superintending Engineer, 8th Division, to the Secretary to Government, Public Works Department, dated Madura, 29th May 1872, No. 902:—

In compliance with the instructions contained in G. O., 18th March 1872, No. 769, and its accompanying Budget, I have the honour to submit herewith, for the sanction of Government, an estimate of Rupees 7,250 for the restoration

- 1 Plan.
- 1 Estimate of Rupees 7,250.
- 1 Specification Report.

of a portion of Tiroomala Naick's Palace at Madura.

2. This service is entered in the Provincial and Local Budget of 1872-73 as No. 50, under the heading of "Civil Buildings, Original Works," with an allotment of Rupees 10,000.

3. An estimate of Rupees 10,000 was prepared by the Palace Overseer and was submitted to me through the Range Officer. On referring the matter, however, to the Government Architect, that gentleman informed me that he wished to visit Madura before the estimate was sent in. Mr. Chisholm arrived here yesterday, and he has requested me to submit at once for sanction a portion of the said estimate, namely, that contained in the accompanying estimate, and to state that he will prepare a supplemental estimate for such further work as he proposes to get carried out this year.

4. In order to prevent further delay, I have now authorized the Range Officer to proceed with the work in anticipation of the sanction of Government, and I trust that, under the circumstances, this course will be approved.

No. 255. ORDER THEREON, 15th June 1872, No. 1,487.

CIVIL WORKS, No. 21.

THE Government sanction the estimate of Rupees 7,250 submitted with this letter, and await the further estimate proposed to be furnished for the balance of the grant of Rupees 10,000 included in the current year's Provincial Budget for the restoration of Teroomala Naick's Palace.

(True Extract.)

Captain, R.E.,

Acting Joint Secretary to Government.

To the Superintending Engineer, 8th Division, with Specification.
" Controller of Public Works Accounts.
" Consulting Architect.
" Financial Department.

Exd. S. T. Augustin.

No 71 of 1872-73

Abstract Estimate for the portion to be
Restored in Siroomal Naick's Palace at
Madura

Quantity

Particulars of Works Rates Amount Total

Wagon Vault

6406 3/4	Sqre feet of Plaster in Chumam 3 Coats 3-8	224 3 9		
1042 1/2	do Cornice work in Chumam 3-8	162 14 3		
356 1/4	do Plaster Mouldings do 3-8	133 9 6		
132	bft granite ashlar moulded 3-8	396 "		
1010	Dragoons in Chumam each 1-8	15 "		
" 35	Ornamental flowers " 2-	70 "		
" 2	Volutes in Chumam " 1-8	3 "		
" 4	Birds " 1-8	6 "		
" 1	Griffin head and central Archedes 5-	3 "		
" 5	Larger Griffin in Chumam Couple 25-	125 "		
" 4	do do do 25-	100 "		
" 5	Pillasters in Chumam for Griffin 5-	25 "	12 65 11 6	

Octagon Dome

20256	Sqre feet of plaster in Chumam 3 Coats 3-8	708 15 4		
11/9	Cub yds of brick in do (above 30ft) 5-8	61 1 9		
2038 1/2	Sqre ft of Cornice Work in Chumam 4-2-6	318 8 3		
1813 1/2	do Pavement concrete & terr. 8-	145 1 3		
25 5/7	Cub yd of brick in Chumam on top 4-	100 11 10		
80-9	Cub feet of teak wrought frames 3-12	302 13 "		
848	Sqre feet of Doors & Windows 3-8	1272 "		
44 3/4	Cyds dismantling old wall " 8-	22 6 "		
5	Pinacles over Dome 4-	20 "		
6	Iron Lies 1 1/2" Diameter " "	100 "		
18 1/2	Sqre feet of oil paint 2 Coats for doors 2-	37 "		
600	do of plaster mouldings in Ch: " 6-	225 "	33 13 9 5	
			4579 4 "	

The Provincial and Local Budget of 1872-73
as No 50 under the heading of Civil Buildings
Original Works, with an allotment of
Rupees 10,000. —

3 The Estimate of Rs 10,000.
was prepared by the Palace Overseer
and was submitted to me through the
Range Officer. On referring the matter ^{however}
to the Government Architect, that
Gentleman informed me that he wished
to visit Madras before the Estimate
was sent in. Mr Chisholm arrived
here yesterday and he has requested
me to submit at once for sanction
a portion of the said Estimate viz
that contained in the accompanying
Estimate, and to state that he will
prepare a Supplemental Estimate for
Such

such further work as he proposes to get
carried out this year —

4 In order to prevent further
delay I have now authorized the
Range Officer to proceed with the
work in anticipation of the sanction
of Government and I trust that
under the circumstances this course
will be approved. —

I have the honor to be

Sir
Your Most Obedient Servant
Richard Roberts Lieut Col R.E.
Superintending Engineer S.D.

Compd
S.D.

Cp 2738

Govt. of 1872 Madras.

PUBLIC WORKS.

To The Superintending Engineer
8th Division

Dated

Recd.

Encl. 2

G. O. 15 June 1872. 1487.

Nos. 254 & 255

Tirumala Naick's Palace

at Madura Estn

Rs. 7250 for the resto-
ration of a portion of
Tirumala Naick's
palace at Madura,
Sanctioned with remarks.