(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 1962-63 Press Mis.
294-96
Dated 17th August-1872

Not to be folded or roughly handled

No. 294. Read the following letter from the Consulting Engineer for Railways, to the Secretary to Government, Public Works Department, dated Madras, 1st August 1872, No. 404 :—

With reference to G. O. No. 1,365, dated the 31st May 1872, I have the honour to submit a list of half-yearly maintenance sanctions for the Great Southern of India Railway for the half-year ending 31st December 1872.

GREAT SOUTHERN OF INDIA RAILWAY.

Engineering Department.

Estimate for Maintenance of Way and Works, half-year ending 31st December 1872—*Negapatam to Erode.*

Miles maintained.		Departmentally.	By Contract.	Total.
Main Line.	Double...	.....	.... .	.....
	Single	168	.....	168
Sidings		13¼	.....	13¼
		...	.....	181¼

Estimate for Maintenance of Way and Works, half-year ending 31st December 1872, etc—(Continued)

Head.	Description of Work	Ordinary.	Chargeable to Public Works Renewals Fund.	—	
		Rs. A. P.	Rs. A. P.		
	Salaries, Office Expenses, and General Superintendence ... Rs. 2,036 8 4 × 6	12,219 2 0			
	Total Head I. ...	12,219 2 0			
I.	MAINTENANCE, PERMANENT WAY.				
	I.—Wages.				
	1 Gang at Rs 115 0 0 × 6	690 0 0	.....	1 Ganger at .. Rs A. P. 10 0 0. 15 Platelayers at Rupees 7 105 0 0	Rs A. P. 115 0 0
	1 Do. at ,, 76 0 0 × 6	456 0 0	.....	1 Ganger at .. .. 12 0 0 1 Do at . 10 0 0 9 Platelayers at Rupees 6 54 0 0	76 0 0
	1 Do at ,, 44 8 0 × 6	267 0 0	.....	1 Ganger at .. .. 9 0 0 1 Do at .. ... 8 0 0 5 Platelayers at Rupees 5½ ... 27 8 0	44 8 0
	1 Do at ,, 29 8 0 × 6	177 0 0	.....	1 Ganger at . .. ... 8 0 0 3 Platelayers at Rupees 5½ ... 16 8 0 1 Platelayer at 5 0 0	29 8 0
	1 Do at ,, 41 0 0 × 6	246 0 0	.....	1 Ganger at ... . 8 0 0 6 Platelayers at Rupees 5½ ... 33 0 0	41 0 0
	27 Gangs at ,, 24 8 0 × 6	3,969 0 0	.....	1 Ganger at ... ... 8 0 0 3 Platelayers at Rupees 5½ ... 16 8 0	24 8 0
	2 Do. at ,, 35 8 0 × 6	426 0 0	.....	1 Ganger at ... ... 8 0 0 5 Platelayers at Rupees 5½ ... 27 8 0	35 8 0
	10 Do. at ,, 30 0 0 × 6	1,800 0 0	....	1 Ganger at ... ... 8 0 0 4 Platelayers at Rupees 5½ ... 22 0 0	30 0 0
II.	1 Gang at ,, 42 0 0 × 6	252 0 0	.....	1 Ganger at ... . 8 0 0 1 Do. at ... ... 6 8 0 5 Platelayers at Rupees 5½ ... 27 8 0	42 0 0
	2 Gangs at ,, 41 8 0 × 6	498 0 0	.....	1 Ganger at ... ... 8 0 0 1 Platelayer at .. ... 6 0 0 5 Platelayers at Rupees 5½ ... 27 8 0	41 8 0
	1 Gang at ,, 27 8 0 × 6	165 0 0	....	1 Ganger at ... ... 7 0 0 1 Platelayer at .. .. 5 8 0 3 Platelayers at Rupees 5 ... 15 0 0	27 8 0
	1 Do. at ,, 40 8 0 × 6	243 0 0	.....	1 Ganger at .. . ... 7 0 0 1 Platelayer at ... ... 6 0 0 5 Platelayers at Rupees 5½ .. 27 8 0	40 8 0
	2 Gangs at ,, 29 0 0 × 6	348 0 0	.....	1 Ganger at . ... 7 0 0 4 Platelayers at Rupees 5½ ... 22 0 0	29 0 0
	27 Do. at ,, 23 8 0 × 6	3,807 0 0	....	1 Ganger at ... ... 7 0 0 3 Platelayers at Rupees 5½ ... 16 8 0	23 8 0
	10 Do at ,, 23 0 0 × 6	1,380 0 0	....	1 Ganger at ... . 8 0 0 3 Platelayers at Rupees 5½ ... 16 8 0	24 8 0
	4 Do. at ,, 22 8 0 × 6	540 0 0	.....	1 Ganger at ... ... 6 0 0 3 Platelayers at Rupees 5½ ... 16 8 0	22 8 0
	38 Line watchmen at Rs. 5 × 6	2,640 0 0	.....		
	4 Do at ,, 5½ × 6	132 0 0	.....		
	1 Gateman at Rs. 4 8 0 × 6	27 0 0	....		
	20 Gatemen at ,, 3 0 0 × 6	360 0 0	.. ..		
	5 Do. at ,, 5 0 0 × 6	150 0 0	.....		
	35 Do at ,, 4 0 0 × 6	840 0 0	.....		
	Establishment at ,, 280 0 0 × 6	1,680 0 0	....	4 Carpenters at Rupees 15 ... 60 0 0 4 Smiths at Rupees 15 ... ... 60 0 0 4 Boys at Rupees 5 ... ... 20 0 0 4 Sub-Inspectors at Rs. 35 ... 140 0 0 Total . 280 0 0	

Proceedings of the Madras Government, Public Works Department, 17th August 1872.

Estimate for Maintenance of Way and Works, half-year ending 31st December 1872, etc.—(Concluded.)

Head.	Description of Work.	Ordinary.	Chargeable to Public Works Renewals Fund.	
	II.—Materials.	Rs. A. P.	Rs. A. P.	
II.	Ballast, 10,000 yards, at 8 Annas	5,000 0 0	.....	
	Earthwork in repairing banks and side walks, 30,000 yards at Annas 1-6	2,812 8 0 350 0 0	....	Oil, waste, etc, etc.
	Stores	.....	750 0 0	
	Rails	.....	8,100 0 0	
	Sleepers	.. ..	500 0 0	
	Chairs	....	300 0 0	
	Spikes	...	70 0 0	
	Bolts and Nuts	... .	20 0 0	
	Fish-plates	.....	1,000 0 0	
	Keys	.. .. ..	75 0 0	
	Cushions	....	50 0 0	
	Gibbs and Cotters	. .....	70 0 0	
	Tie-bars	. .... .	500 0 0	
	Labour for renewing			
	Total Head II...	29,255 8 0	11,435 0 0	
	Repairs, Wages and Materials.			
III. (1)	Bridges	750 0 0	.....	
	Tunnels	.. ..	..... .	
III. (2)	Earthwork	500 0 0	... . ..	
	Fences	300 0 0	... .	
	Culverts	400 0 0	.....	
	Miscellaneous	800 0 0	.....	
	Total Head III...	2,750 0 0	... .	
	Repairs, Wages and Materials.			
IV. (1)	Stations, buildings and yards Signals, Gate lodges, etc.	*5,000 0 0	. ...	
IV. (2)	Staff Quarters	† 750 0 0	.... . .	
	Total Head IV	5,750 0 0	.... .	
V.	Maintenance by Contract	...	. ...	
	Total Head V	... .	...	
	Unclassified Expenditure			
VI. (1)	Plantations	‡ 750 0 0	.....	
VI. (2)	Tools and Plant	§ 1,000 0 0	...	
VI. (3)	Loss on Stores	.....	...	
	Total Head VI...	1,750 0 0	..... .	
	Grand Total	51,724 10 0	11,435 0 0	

* Whitewashing and repairing Platelayers' huts and Gatekeepers' lodges

	Rs	A.	P.
Whitewashing and repairing Platelayers' huts and Gatekeepers' lodges	1,380	0	0
Turn-table	100	0	0
Roofs	1,000	0	0
General repairs	2,520	0	0
Total	5,000	0	0

† General repairs and Whitewashing

	Rs	A.	P.
General repairs	500	0	0
Whitewashing	250	0	0
Total...	750	0	0

‡ Cutting trees for fuel for locomotive purposes and watering plants.

§ Platelayers' tools

Teichinopoly,
26th July 1872.

(Signed) W. S BETTS,
Agent.

(Signed) B C St. JOHN.

Proceedings of the Madras Government, Public Works Department, 17th August 1872.

Proceedings of the Madras Government, Public Works Department,
17th *August* 1872.

No. 295. ORDER THEREON, 17th August 1872, No. 1,962.

RAILWAY, No. 45.

ORDERED that the statement submitted with this letter be forwarded to the Government of India with reference to their Proceedings No. 656-A. R., dated 10th May 1872.

(True Extract.)

(Signed) G. W. WALKER, Colonel, R.E,
Secretary to Government.

No. 296. (DOCKET No 1,963, dated 17th August 1872.)

COPY of the above forwarded to the Government of India.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

Exd. E. C. Shunker.

RAILWAY DEPARTMENT. CONSULTING ENGINEER'S OFFICE.

No. 404.

From Lieut Colonel J. A. M. Stewart R.E.
Consulting Engineer for Railways,

To Colonel G. W. Walker R.E.
Secretary to Government,
Public Works Department,
Fort Saint George.

SIR,

With reference to G.O. No. 1365, dated the 31st May 1872, I have the honour to submit a list of half-yearly maintenance sanctions for the Great Southern of India Railway for the half-year ending 31st December 1872.

Madras
1st August
1872

I have the honour to be
Sir
Your most obedient Servt
Arthur Stewart Lt R.E
for Colonel Lt R.E

P. W. 1872 Depart.

No 3744.

No 1962.

Ordered that the Statement submitted with this letter be forwarded to the Govt of India with reference to their Pro: 656 A.R. dated 10th May 1872.

C.E. for Rep: ✓ A.C. No 1962 ✓.

Desp: 23/8/72 Copy of the above forwarded to the Govt of India.

Encd

Desp: 23/8/72 with 35 Enclosures

RAILWAY DEPARTMENT.

1872

From

The Consulting Engineer for Railways,

To

The Secretary to Government,
P. W. Department,
Fort Saint George.

Dated 1st August 1872.
Recd 2

Encl: 1 ✓

No. 406.

I have the honor to submit herewith a bill of half-yearly maintenance charges for the G. S. of I. Ry for the half year ending 31st Dec. 1871.

No 1962 Ordered to Govt of India

Clo 3766

Govt. of 1872. Madras.

PUBLIC WORKS.

To The Consulting Engr for Railways
& The Secretary to the Govt of India

Dated
Recd Encl. 1/

6 Oct Augt 1872 962.
963.

Nos 2944 2957 2961

Maintenance Sanctions

Forwarding Copy of letter from the C. Engr for Rys submitting list of maintenance sanctions of the G.S.I. Rys for the half year ending 31st Decr 72.

Passing orders on letter from the C. Engr for Rys Submitting list of maintenance sanctions of the G-S of I. Rys for the half Year Ending 31st Decr 72.