M.R.O. 1—77,606—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 2223 Press ~~Mis.~~
265-266

Dated 19-9- 1872.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 19th September 1872.

No. 265. Read the following letter from the Officiating Quarter Master General, to the Secretary to Government, Public Works Department, dated Fort St. George, 7th September 1872, No. 402-6,794:—

I HAVE the honour to forward report and estimate for Rupees 1,103 for making and putting up punkahs and other trifling work required for the European Female Hospital at Bellary.

2. The estimate is approved by His Excellency the Commander-in-Chief. The Superintending Engineer of the 3rd Division reports that there are no funds under "Minor New Works Military" to carry out the work; but as the punkahs are emergently required, I am directed by Sir F. P. Haines to request that funds may be allotted from some other source for so much of the work as refers to punkahs, for which a sum of Rupees 750 will be required.

No. 266. ORDER THEREON, 19th September 1872, No. 2,223.

MILITARY WORKS, No. 10.

THE estimate of Rupees 1,103 is sanctioned.

2. The Superintending Engineer will arrange for putting up the punkahs at a cost of Rupees 750 in anticipation of an allotment of funds hereafter. The remainder of the work provided for in the estimate should be carried out from the grant for Minor New Works.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 3rd Division.
" Controller of Public Works Accounts.
" Military Department.

Exd. E. C. Shunker.

Quarter Master General's Office
Fort St. George 7th September 1872

(3)

No. 402
6794

From

Colonel H. H. O'Connell
Offg Quarter Master General.

To

Colonel G. W. Walker.
Secretary to Government
Public Works Department

Sir,

I have the honor to forward Report and Estimate for Rs. 1103 for making and putting up Punkahs and other trifling work required for the European Female Hospital at Bellary

2. The Estimate is approved by His Excellency the Commander in Chief. The Superintending Engineer 3d Division reports that there are no funds under Minor New Works Military to carry out the work, but as the Punkahs are emergently required, I am directed by Sir F. P. Haines to request that Funds may be allotted from some other source for so much of the work as refers to Punkahs, for which a sum of Rs. 750 will be required.—

S

Please the Commander

Sir

Your Obedient Servant

N. T. Tonnell Colonel

Asst Qr Mr General

Rec'd March 18/72 Regd
Secy's Office Calcutta
Nº 4403.

The Quarter Master General
&c &c &c Bengal

Sir,

I have the honor to forward
herewith Estimate No 1103 for making
and putting up Punkahs and
other trifling work required
for the Kuddeah Female
Hospital at Bellary —
No 22 dated 13th March 72.

I am Sir
Your most obedient
Servant
R. M. Dipnall
Surgeon
Secretary to Govt
Mil Dept

Dated 7th April 1872
Rec'd 9th do
Entd 21st do
No 4102
1794

Forwarded herewith
Estimate No 1103 for making
and putting up Punkahs and
other trifling work required
for the Kuddeah Female
Hospital at Bellary —
No 22 dated 13th March 72.

I am Sir
Your most obedient
Servant
R. M. Dipnall
Surgeon
Secretary to Govt
Mil Dept

No 265

Dated Calcutta 11th April 1872

"Minor new Work"

Military

Abstract Estimate

Bellary District

(7)

Work. Making and fitting Punkahs and painting the glazed Windows and Fanlights &c in the Female Hospital vide Deputy Asstt Qr Mr Gl's No 186 of 29th February /72 and docket No 1104 of 27th June 1872.

Quantities.	Description of Work	Rate	Per	Amount	Amount of each part.
	Punkah				
	Timber				
0. 983	6ft of Teak wood wrought & put up	4	6ft	3 14 11	
	Fringe				
9½	L. Yds Canvas for inside, one foot broad and two breadths	3	L. Yd	1 12 11	
7.	Brown Holland glazed 3 feet broad	7	"	3 1 5	
14.	Red Tape for borders 2" broad two rows	2	"	1 12 5	
				10 8 5	
	carried over				

Compd MM

		Brought over			1085
		Canvas Leather			
2.		Slings for Punkahs	1 8	Each	3 -
		Copper			
½	lbs	Rivets for leather Slings	- ½ -	lbs	- 7 -
		Iron			
15.917	lbs	of Iron	- ½ -	lbs	3 15 8
14.	Sft	Wood piling to Punkah boards	1 8 -	Sft	- 3 4
		Tailors hire	1 8.		1 8 -
		Total Cost of one Punkah			19 10 5.
	D:	D: 28	D:		550 8
		Supporting Rods &c.			
23.499	lbs	of Supporting Rods &c	- 4 -	lbs	5 14 -
		Total for one			5 14 -
	D:	for 11			82 4 -
		Miscellaneous			
10.	lbs	Copper wire for fastening rod together	- ½ -	lbs	3 8 -
		carried over			38 - 6327 8

		Brought over			38 - 6327 8
31.160	lbs	Iron rod whole length of building to be fastened to Supporting rods at their Centre	- ½ -	lbs	7 12 8
40.		Yards of Punkah rope	- -	6 Yds	1 4 -
6.		Punkah wheels complete 18 diameter (wooden wheel)	- 8 -	Each	3 - -
		Bamboos Ropes &c for scaffolding &c			20 - -
216	Cft	Removing and rebuilding part of Stone in Chunam walls to allow Punkah rods to pass through	- 36	Cft	4 7 4 -
		Total for Miscellaneous			82 12 8
		Building a partition wall with door in large ward.			
6.15	Cyds	of Excavating foundation &c	- 2 -	Cyd	- 12 3.
		Stone in Chunam			
469.12	Cft	of Stone in Chunam foundation, basement and superstructure &c	- 26	Cft	73 4 9.
		Carried over			741 - 7154 4

	Brought over		74 1 -		715 4 4
	Plastering				
477.25	Sft Plastering with 3 Coats	5 8 -	Sqrs	26 4 -	
1.	Pannel and venetian door Complete 4×7	42 -	each	42 -	
6.	Rft of Slab over door 1½ × 4½	5 -	Rft	1 14 -	
56.	Sft wood, oiling	2 -	Sqrs	1 1 11	
	Total Plastering &c &c				145 4 11
	Bath Rooms				
41½	Lft of Slabs &c for bath room	7 -	Lft	18 26	
200.	Sft Asphalting floors ¾ thick	16 8 -	Sqrs	33 -	
	Total for bath Rooms				51 26
	Painting glazed parts of doors and windows &c.				
498.24	Sft of Painting &c &c &c &c		Sqrs	19 14 10	19 14 10
	Work not included in the first Estimate Sub Div.				
	Fitting Ventilators in the Latrines and providing rods for Lamps.				
240.	Lft of Removing Stones in chunam Pacca walls to make place for the Ventilator	1 -	Lft	15 -	
	Carried over			15 -	931 10 7

	Brought over		15 - -		931 10 7
114.	Lft of rebuilding with Stone in chunam and pointing	26 -	Lft	22 8 -	
126.	Sft Plastering with 3 Coats	5 8 -	Sqrs	6 4 10	
48	Lft of Slabs over the ventilators (2×6)	7 -	Lft	21 - -	
12	Iron barred Ventilators each (2×6)	3 12 -	each	45 - -	
18	Iron rods for Globes each 15 ft long and ¼ diameter	7 6 -		8 7 -	
	Total fitting ventilators &c				118 13 10
	Total				1050 8 5
	Sundries at 5 per Cent				52 7 7
	Total Estimate Rupees				1103 - -

No 10 Bellary Range
Bellary
20 July 1872.

William Lindesay C. E.
Executive Engineer 1st Class

Estimate prepared by Overseer.
Copied by S. Krishnaswamy
3rd Accountant.
Head Quarters Sub Division
Bellary 29th August 1872

Examined

Brigadier General
Commanding Sub Division

No 2223.

Rev. Mad Sept. 13.

Read the following

from the D.W. Genl (H.R. No 402/794) dt 7 Sept 72

The estimate of Rs 1103

is sanctioned -

The Supg Engineer will

arrange for putting up the

Punkahs at a cost of

Rs 750 in anticipation

of an allotment of funds

hereafter. The remainder

of the work provided for in

the Estimate should be

carried out from the grant

for Minor New works.

Genl

To

S. Engr 3d Dn with Memorl

Controller

Military Audtr

Recd 25/9/72

From

The Officer in Ch.

Bellary Dago

No. 4403/52.

The Supdg Engineer

3d Division

Dated 20th July 1872.

Sir,

I have the honor to forward herewith a Memorial from the Inhabitants of Bellary praying that a Punkah may be erected in the Female Hospital Wards at a cost of Rs 750 and to state that I have no objection to the work being carried out.

I have &c

Sd/ [illegible]

Lt Col

Offg Executive Engr

Bellary

Encl 1 Memorial

Recd 20/9/72

No. 2265.

Che 4403.

Govt. of {1872} Madras.

PUBLIC WORKS.

To

The Superintending Engineer

2nd Division

Dated

Recd. Encl. 2

G. O. 19 Septr 72, No. 2223.

Nos. 265-266

Cumbahs - Tree Estimate for making & putting up punkahs &c required for the European Female Hospital at Bellary, sanctioned with remarks -

Cir 18 Oct 72