M.R.O. 1—77,006—8-6-37.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

# MADRAS RECORD OFFICE.

---

## Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2481 Press / ~~Mis.~~
377-378

Dated 22-10- 1878.

***Not to be folded or roughly handled***

*Proceedings of the Madras Government, Public Works Department, 22nd October 1872.*

No. 377. Read the following letter from the Officiating Superintending Engineer, 6th Division, to the Secretary to Government, Public Works Department, dated Tanjore, 4th October 1872, No. 526:—

With reference to your memorandum No. 66, dated 9th September, I have the honour to submit a revised plan and estimate* for additions and alterations to the Guard-room of the Grand Magazine at Trichinopoly, the sentries' walk having been altered as you suggested.

2 Plans.
1 Sketch.
1 Estimate.
1 Specification.
* Rupees 1,180.

2. The previous arrangement was made with the approval of the Military Authorities, but they have no objections to offer to a lean-to walk, and I think the lean-to preferable to the detached walk, as it will be better sheltered and will cost rather less to construct.

---

No. 378. Order thereon, 22nd October 1872, No. 2,481.

MILITARY WORKS, No. 12.

His Excellency the Governor in Council sanctions the revised plan with estimate, amounting to Rupees 1,180, for alterations proposed to the Native Guard-room attached to the Grand Magazine at Trichinopoly in order to provide accommodation for a European Guard. The execution of the work must be deferred until funds are forthcoming.

(True Extract.)

Colonel, R.E.,
*Secretary to Government.*

To the Officiating Superintending Engineer, 6th Division, with Specification.
" Controller of Public Works Accounts.
" Military Department.

Extd. S. T. Austin.

Fuchinopoly District

Fuchinopoly or No. I Range.

Abstract Estimate No. of 1872-73

139 V

Work. Additions and alterations to the Guard Room of the Grand Magazine at Fuchinopoly for the accommodation of a Guard of British Troops. Vide G. O. No. 1900 dated 10th June/72 Military Depart.

| Quantity | Description of Charges | Rate | Amount | Amount of each part |
|---|---|---|---|---|
| | Additions to Guard Room | | | |
| 2133¾ | Cft. Brick in Chunam at | " 2 " | 266 11 6 | |
| 24¾ | " Flat Arch work in do. at | " 2 6 | 3 13 10 | |
| 157 6/12 | Sqr. ft. Plastering at | 1 8 " | 23 10 4 | |
| 496¾ | Do. of flooring with brick on edge in Chunam | 5 " " | 24 13 5 | |
| 288 7/12 | Do. ¾" Asphalte over brick on edge in Chunam at | 13 8 " | 38 15 2 | |
| 1080 7/8 | Do. of Roofing with flat and pan tiles, palmyrah couples and purlins &c. at | 20 " " | 216 2 10 | |
| 33 23/24 | Cft. Teak wood wrought and put up at | 3 8 " | 118 13 8 | |
| 1 | Teak wood door 7'×3½' with Iron work &c. Complete at | 27 " " | 27 " " | |
| 3 | Do. Windows batten 5'×3' with iron work &c. Complete | 17 " " | 51 " " | |
| | Excavating foundation and Filling in | | 7 " " | |
| | Carried over | | 777 13 2 | |

| | | | | | |
|---|---|---|---|---|---|
| | Brought forward | | | 777 | 13 2 |
| | Sundries | | | 42 | 2 10 |
| | Total | | | 820 | " " |

## Sentry's Walk Shed.

| | | | | | |
|---|---|---|---|---|---|
| 373/12 | Cft. Brick in chunam | at | " 2 " | 46 | 11 " |
| 504 | Sqrft. Plastering | at | 1 8 " | 7 | 8 11 |
| 12 | Stone Brackets including fixing | | 1 " " | 12 | " " |
| 37 25/36 | Cft. Country wood | at | 2 8 " | 94 | 3 9 |
| 9.50 | Sqrft. of Roofing with Palmyrah rafters, purpins, with pan tiles and plastered over, in 1" inch of chunam | at | 18 " " | 171 | " " |
| | Excavation and filling in | | | 5 | 8 " |
| | Scaffolding | | | 4 | 8 " |
| | Sundries | | | 18 | 8 4 |
| | Total | | | 360 | " " |

Total Estimate Rupees 1180 " "

Signed P R C Brockman Lieut R E
Executive Engineer Trincomalee

Supg Engrs Office 6th Divn
Jaffna 4th October 1872

Submitted
Major R.E.
Offg Supg Engineer 6 Divn

Supg Engrs Office 6th Division
Jaffna 4th October 72.

No 526.

From

Major J. C. Hasted R.E.
Offg Supg Engineer 6th Divn

...an R.E.
...P. W. D.

...your Memo
...I have the
...Com and
...terations
...and Magazine
...Walk
...suggested.
...has been made
...Military Au...
...no objections
...and I
...re to the
...be better
...altered & will cost Rupees less to
construct.—

I have the honor to be
Sir
Your most obdt Servt
Submitted Major R.E.
Offg Supg Engineer 6th Divn

| | | | |
|---|---|---|---|
| Brought forward | 777 | 13 | 2 |
| Sundries | 42 | 2 | 10 |
| Total | 820 | | |

| | | |
|---|---|---|
| 373/2 | Cft | |
| 504 | Sqrs | |
| 12. | Stone | |
| 37 25/36 | Cft | |
| 950 | Sqrs | |
| | rials | |
| | titles | |
| | 1"in | |
| | Estd | |

Enclosure in a.
№ 526, dated 4th
ber 1872 — from t
Offg Supg Engineer
to the Secretary to
P. W. D.

Q 622 Oct/72
42487
P. W. 4864/7
From 2nd October/72 Lt Bissy
Estimate R/L 1.
for additions & a
ations to the gu
Room of the gro
Magazine at J
nopoly for the ac
modation of a f
of British troops.

Offg Supg Engineer's Off
Sanjore 4th

Offg Supg Engineer's Office
Sanjore 4th October 72.

№ 526.

From,
Major J. O. Hasted R.E.
Offg Supg Engineer b.d.

To,
Colonel G. W. Walker R.E.
Secretary to Govt P. W. D.

Sir,

With reference to your Memo
№ 66, dated 9th September, I have the
honor to submit a revised Plan and
Estimate for additions & alterations
to the Guard Room of the Grand Magazine
at Trichinopoly, the Sentries walk
having been altered as you suggested.

The previous arrangement was made
with the approval of the Military Au-
thorities, but they have no objections
to affix a lean-to walk and I
think the lean-to preferable to the
detached walk, as it will be better
sheltered & will cost rather less to
construct. — I have the honor to be
Sir
Your most obdt Servt
John Hasted Major R.E.
Offg Supg Engineer b.d.

P.W. 1872 Repair
Nos. 4864.
The Offg. Supg. Engr.
Sixth Divn.

To,
The Secretary to
Govt. D. P. W.

No. 526

Dated 4th Oct. 72.
Recd. 7th Oct 72.
3 Plans 1/2 Est.

Forwards Revised Estt. made & plans for alterations to the Guard Room of the Grand Magazine at Trichinopoly and for providing a line to Sentry walk.

G.O. 2481. 22 Octr. 72.
With an Order

1Dl.

No. 2481

His Excellency the Governor in Council sanctions the revised plan with estimate amounting to Rs. 1180 for alterations proposed to the Native Guard room attached to the Grand Magazine at Trichinopoly in order to provide accommodation for a European Guard. The execution of the work must be deferred until funds are forthcoming.

I thought it had been determined years ago to move the Arsenal.?

Desp. 28/10/72
S. Engr. 6th Dn.
Contr. Mr.
Mily. Dept.

[illegible]

Gillw.

A. Watts

Oct 4864

Govt. of [1872] Madras.

PUBLIC WORKS.

To the Officer superintending the Engr & Surveyor Division

Dated

Rcvd. Encl 4

3 Plans

22 Oct 2487.

Nos. 3774378

Sand Magazine at Trichinopoly. Estimate Rs 1180 for alterations to the native guard room attached to the Sand Magazine at Trichinopoly in order to provide accommodation for a European guard, sanction to which to be deferred till funds are available