M.R.O. 1—77,006—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 504-508	2543	Press / ~~Mis.~~
Dated	29- 10-	1892.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 29th October 1872.

No. 507. Read the following letter from the Superintending Engineer, 5th Division, to the Chief Engineer, Department Public Works, dated Camp at Mamathoor, 10th October 1872, No. 144 :—

WITH reference to your memorandum No. 59 of the 28th August 1872, I have the honour to submit a revised estimate of Rupees 624 for making the verandah of the upper storey of the Female European Hospital at Bangalore secure against accidents of children falling out.

1 Revised Estimate.
1 Specification.
1 Plan.

No. 508. ORDER THEREON, 29th October 1872, No. 2,543.

MILITARY WORKS, No. 23.

HIS Excellency the Governor in Council sanctions the estimate of Rupees 624 for certain improvements to the upper storey of the Female Hospital at Bangalore.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with Specification.
" Controller of Public Works Accounts.
" Military Department.

Exd. E. C. Shunker.

5th Division D. P. W.

Military. — Bangalore. — New Work

Revised Abstract Estimate of 1872-73.

Work — Rendering the verandah of the upper Story of the Female European Hospital at Bangalore against accidents of Children falling out.

Quantity	Description of work.	Rate	Per	Amount	Total
1218	Running feet of Iron bars one inch diameter	6 .	Rft	456 12 .	
11-11-3	Cubic feet of Teakwood wrought and put up	38 .	Cft	41 12 6	
6-20¾	Squares of Green painting	5 .	Sqre	31 . 7	
348	Nos of Putting in bars coated with black varnish	3 .	Each	65 4 .	
				594 13 1	
	Sundries			29 2 11	
	Total Amount of Estimate Rupees.			624 . .	

Rupees Six hundred and twenty four only

Executive Engineer's Office
Bangalore, 24th September 1872.

[Signed] Henry M. Vibart Captain, R.E.
Executive Engineer, Bangalore.

Ed Md Colonel, R. E.
Superintending Engineer, 5th Dn

Supp. Engrs. Office 5th Div.
Camp Channathoor 10th October 1872.

No. 1464.

From
The Supg. Engineer
5th Division,
To The Chief Engineer
D.P. Works.

Sir,

With reference to your Memorandum
No. 59 of the 28th August 1872, I have
the honor to submit a revised Estimate
of Rs. 624 for enclosing the Verandah
of the Upper Story of the Female
European Hospital at Bangalore,
Screen against accidents of Children
falling out.

Enclosures 3.
1 Revised Estimate.
1 Specification.
1 Plan.

I have the honor to be,
Sir,
Your most obdt. Servt.

E A Ward Col. RE
Supg Engineer 5th Div.

5th Division D.P. Works
Bangalore.

P.W. 5005/72.

Abstract Estimate for
Enclosing the verandah of the
upper story of the Female Euro-
pean Hospital at Bangalore
against accidents of children
falling out.

Amount of Estimate Rs 624.

P. W. 1872 Department
No. 1005
From The Supg. Engineer
5th Division
To The Chief Engineer
P. W.
Dated 10th October 1872
Recd. 15th October 1872
No. 1111. 1-8 Rds.
Enclosures 3.

Submitting a revised estimate of Rs. 624 for making the Verandah of the upper story of the Female E. Hospital at Bangalore, secure against accidents of Children falling out.

No. 2543- 29th October 72

From

The Superintending Engineer
Cantonment Circle
Bangalore

To

The Chief Engineer
P. W. Department
Madras

Dated 4th November 1872

Sir,

I have the honor to solicit the favorable consideration of the estimate of Rs 624 for certain improvements to the Upper story of the Female Hospital at Bangalore.

Enclosures

1 Estimate
2 Plans
3 Letter from Civil Surgeon

Copy 18 Oct 72

No 5005

Govt. of 1872 Madras.

PUBLIC WORKS.

To The Superintending Engineer
5th Division

Dated

Recd. Encl. 2

G. O. 24th Oct. 1872 No. 2343.

Nos. 5078 & 5078

Female Hospital at Bangalore - Rct. of Rs: 624 for certain improvements to the Upper Story of the Female Hospital at Bangalore, sanctioned.