M.R.O. 1—77,006—8-6-37.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No.		Press / Mis.
3,4	2565	
Dated	1·11	1872.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
1st November 1872.

No. 3. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Camp at Virdachellum, 11th October 1872, No. 147:—

I HAVE the honour to submit, for the sanction of Government, an estimate of Rupees 690 for dismantling and re-building portion of the compound wall to old European Infantry Barracks, lower square, at Bangalore.

1 Estimate
1 Specification.
1 Plan.

2. The estimate and plan have been approved of by His Excellency the Commander-in-Chief.

3. Funds for the work will be applied for early in April next.

No. 4. ORDER THEREON, 1st November 1872, No. 2,565.

MILITARY WORKS, No. 2. SANCTIONED.

(True Extract.)

Major, R.E.,
Acting Joint Secretary to Government.

To the Superintending Engineer, 5th Division, with Specification.
„ Military Department.
„ Controller of Public Works Accounts.

Exd. S. T. Austin.

5th Division, D. P. W.

Bangalore.

Military. — New Works.

Abstract Estimate of 1872-73.

2 K 30

Work.— Dismantling and rebuilding portion of the compound wall to Old European Infantry Barracks, Lower Square at Bangalore.

Quantity	Description of work.	Rate	Per	Amount	Total.
4,777½	Cubic feet of Dismantling walls.	. . 1	Cft	24 14 1	
1,413¾	—ditto— of Brick in mud.	. 1 9	do	154 10 1	
1,334	—ditto— of —do— in chunam for coping.	. 2 9	do	229 4 6	
93·38	Squares of Plastering with one coat of chunam both sides to compound wall.	1 8 .	Sqe	140 1 1	
93·38	—ditto— of Bluewashing with two coats as above.	" 4 "	do	23 5 6	
66½	Running feet of Fixing glass on top of coping.	" 2 "	Rft	83 6 "	
				655 9 3	
	Sundries			34 6 9	
	Total Amount of Estimate Rupees.			690 " "	

Rupees Six hundred and ninety only.

Executive Engineer's Office
Bangalore, 14th August 1872.

(Signed) Henry M. Tibart Captain, R.E.
Executive Engineer, Bangalore.

By order
(Signed) W. R. Mesham Major
Asst. Dr. Mr. General Mysore Dn.

E A Ardagh Captain, R.E.
Superintending Engineer, 5th Dn.

No. 1147.

Supg. Engr. Office 5th Dn.
Camp Vidachallum 11th October 1872.

From
The Superintg. Engineer
5th Division,
To The Secretary to Government
P. W. D.

Sir,

Enclosures 3
1 Estimate
1 Specification
1 Plan.

I have the honor to submit for the sanction of Government, an Estimate of Rupees 624 for dismantling and rebuilding portion of the Compound Wall to old European Infantry Barracks, Lower Square at Bangalore.

2. The Estimate and plan have been approved of by His Excellency the Commander-in-Chief.

3. Funds for the work will be applied for early in April next.

I have the honor to be
Sir
Your most obt. Servt.

Edward Col. R.E.
Superintg. Engineer
5th Dn.

P. W. D. No. 8 of 2.

Abstract Estimate for dismantling and rebuilding portion of the compound wall to old European Infantry Barracks, Lower Square at Bangalore.

5th Division P. W. D.
Bangalore.

Amount of Estimate Rs 690.

Public Works 1872 Department.

From

No. 5008

The Supg. Engineer
5th Division,

To The Secretary to Govt.
of P.W.

Dated 11th October 1872.
Recd 15th October 1872.

No. 147.
Enclosures 3,

Submitting for the sanction of Government an Estimate of Rs. 624 for dismantling and rebuilding portions of the Compound Wall to old European Infantry Barrack at Bangalore.—

No. 2565 - 1st Nov. 1872.
Write Cen. Bdg.

No. 2565.
Sanctioned.
Encl.
Rs.

57
4

Dy. Cr. 5 "Secl. with Plan."
15 Supg. Engr.
5 Cantonment

Rec'd 25/11/72

Cir. 18 Oct 72

No 5008

Govt. of 1872. Madras.

PUBLIC WORKS.

To The Superintending Engr
& Mr Executive

Letd

Recd. —

Encl. 2

G. O. 1st Nov. 1872 No 2565.

Nos. 3 & 4

European Infantry Bar.
racks at Bangalore.

Estimate Rs: 690 for dismantling & rebuilding portion of the Compound wall to old European Infantry Barracks, Bangalore, sanctioned.