M.R.O. 1—77,006—8-6-37.

(1) Number of pages._____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2666 Press Mis.

194-95

Dated 12. 11. 1872

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 12th November 1872.

No. 194. Read the following letter from the Superintending Engineer, 5th Division, to the Secretary to Government, Public Works Department, dated Cuddalore, 2nd November 1872, No. 175:—

I HAVE the honour to submit, for the sanction of Government, an estimate of Rupees 205 for removing the old and building a new latrine for the hospital servants on the Race-course, Bangalore.

1 Estimate.
1 Specification.
1 Plan.

2. The plan and estimate have been approved of by His Excellency the Commander-in-Chief. The old latrine consists merely of a mud wall without a roof.

3. As soon as the additional grant under "Minor New Works" Military applied for is sanctioned, the work will be carried out.

No. 195. ORDER THEREON, 12th November 1872, No. 2,666.

MILITARY WORKS, No. 6. SANCTIONED.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, 5th Division, with Specification.
" Controller of Public Works Accounts.
" Military Department.

Exd. E. C. Shunker.

5th Division, D. F. W.

Military. — Bangalore. — New Works.

Abstract Estimate of 1872-73.

Work:— Removing old and building a new Latrine for the Hospital Servants on the Race Course, Bangalore.

Quantity	Description of work.	Rate			Per	Amount			Total		
352	Cubic feet of Removing old walls.			2	6ft	3	10	8			
256	do of Excavation for foundation.			½	do		10	8			
256	do of Foundation stone in chunam		2	9	do	44					
594¾	do of Superstructure stone in do		3		do	111	8	3			
61	Running feet of Flat stones 4" thick 2'-1'-0" broad		3		Rft	11	7				
4·55	Squares of Pointing		2		Sqre	9	1	7			
30	Running feet of Seats with stone Slabs (3½×1½×2')			2	6	Rft	4	11			
21	do of Uprights do (3½×6×1½)			2	6	do	3	4	6		
36	Cubic feet of Concrete work.			3	3	6ft	7	5			
							195	10	8		
	Sundries						9	5	4		
	Total Amount of Estimate Rupees.									205	

Rupees Two hundred and five only.

Executive Engineer's Office
Bangalore, 14th September /72.

/Signed/ Henry M. Vibart Captain, R.E.
Executive Engineer, Bangalore.

By order
/Signed/ W. R. Mesham Major
Asstt Dr Mr General M. Dte

Edward Colpitts, R. E.
Superintending Engineer, 5th Dn

No 175

Supg. Engineer's Office, 5th Divn.
Cuddalore, 2nd November 1872.

From

The Superintending Engineer,
5th Division

To

The Secretary to Government,
Public Works Department.

Sir,

Enclosures 3
Estimate.
Specification.
Plan.

I have the honor to submit, for the sanction of Government, an estimate of Rupees 205 for removing the old and building a New Latrine for the Hospital Servants on the Race Course, Bangalore.

2. The Plan and Estimate have been approved of by His Excellency the Commander-in-Chief. The old Latrine consists merely of a mud wall without a roof.

3. As soon as the additional grant under "Minor New Works" Military, applied for, is sanctioned, the work will be carried out.

I have the honor to be
Sir,
Your most Obedt Servant.

Edward Cole R.E.
Supg. Engineer 5th Divn.

5th Division
Bangalore.

P.W. 538 1/1/72.

Abstract Estimate
for Removing old mud building
& erecting a new Latrine for the
Hospital Servants on the
Race Course, Bangalore.

Amount of Estimate Rs 205.

P. W. 1872 Depart.

From A. 5387.

The Supg: Engineer
5th " Divn

To The Secy: to Govt:
D. P. W.

Dated 2nd } Novr: 1872
Recd: 5th }

No. 175

Encls: 3.

Submitting for the sanction of Govern= =ment an Estimate of Rs: 205 for removing old and building a new Latrine for the Hospital Servants on the Race Course Bun= =galow.

Lieut

Sanctioned

Engrs

2616

Executive Engineer's Signature

Dated 13-11-72

Received Coimbatore 6th Nov 72 - R III

Cho 5287.

Govt. of 1872. Madras.

PUBLIC WORKS.

To The Superintending Engr 5th Division

Dated

Recd. Encl. 2

G. O 12 Nov 1872. No 2666

I-En. No 1

Nos. 194 & 195

Race Course at Bangalore

The Estimate of Rs 205 for removing the old & erecting a new latrine for the Hospital Servants on the Race Course at Bangalore, Sanctioned—