(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 223-224.	2926	Press / Mis.
Dated	11-12-	1872.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
11th December 1872.

No. 223. Read the following letter from the Consulting Architect to Government, to the Secretary to Government, Public Works Department, dated Madras, 21st November 1872, No. 191 :—

I HAVE the honour to forward you the following documents :—

1. Elevation, Bellary Cutcherry.
2. Plan of lower floor.
3. Plan of upper floor.
4. Sections.
5. Detailed quantities and estimate.

2. This estimate is framed in accordance with the instructions conveyed in your memorandum No. 99, dated 8th August 1872. It provides for building a Cutcherry with the following accommodation on the upper floor :—

	FT.	IN.		FT.	IN.	
Magistrate's Court	39	10	×	30	0	1,195
Collector's room	23	10	×	20	0	477
Head Assistant's room	23	10	×	20	0	477
Second Assistant's room	24	4	×	20	0	487
Deputy Collector's room	20	0	×	17	0	340
Sheristadar	20	0	×	12	4	247
Treasury	20	0	×	20	0	400
Do. Office	20	0	×	14	6	290
Head Clerk	20	0	×	16	4	327
General Clerks	64	4	×	30	6	1,962
Sheristadars' Clerks	20	0	×	14	10	287
					Total...	6,489

3. The lower floor, which is only 12 feet high, will be devoted to the following establishments and to records, tiffin-rooms, and store-rooms, the superficial area being apportioned as follows :—

	FT.	IN.		FT.	IN.	
Printing Establishment	64	2	×	29	6	1,892
Head Printer	16	0	×	19	6	312
Records	99	6	×	21	6	2,139
Do.	81	6	×	20	0	1,630
Record keeper	23	6	×	19	6	458
Store rooms	39	6	×	30	0	1,185
Tiffin rooms	53	0	×	19	6	1,033
The upper part of the turrets above the level of the floor contain two rooms for stationery, each ...	15 × 15 × 2 =					900
					Total area...	9,549
					Add area of lower floor...	6,489
					Total area of superficial feet...	16,038

4. The building will be constructed of ordinary materials ; brickwork throughout with plain and solid stone dressings on the exterior. The roof will be of terrace, supported by teakwood trusses, beams, and joists. The doors, venetian throughout, with the addition of glass on the exterior faces.

Proceedings of the Madras Government, Public Works Department, 11th December 1872.

5. The total cost of the whole building, at the rates at present obtaining in Bellary, will be—

	Rs.
Including the stone dressings	97,982
Excluding the stone dressings	89,782

No. 224. ORDER THEREON, 11th December 1872, No. 2,926.

CIVIL WORKS, No. 10.

THE accompanying revised plan of a Collector's Cutcherry to be built at Bellary, submitted by the Consulting Architect in conformity with G. O. No. 899 of 22nd May 1871, will be forwarded for report by the District Engineer of Bellary as to the adequacy of the rates allowed, and for preparation of survey of the site, and of plans and estimates for whatever subsidiary buildings the Collector may consider necessary.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the District Engineer, Bellary.
,, Revenue Department.

No. 191 Consulting Architects Office
Madras 21st November /72

3B

From R. F. Chisholm Esqr. F.R.I.B.A.
Consulting Architect to Govt.

To Colonel G. W. Walker R. E.
Secretary to Government P.W.D.

Sir

I have the honor to forward you the following documents.

1 Elevation Bellary Cutcherry
2 Plan of Lower floor
3 Plan of Upper floor
4 Sections
5 Detailed quantities and Estimate.

This Estimate is framed in accordance with the instructions conveyed in your Mems No. 99 dated 8th august 1872
It providies for building a Cutcherry with the following accommodation on the Upper floor

Magistrates Court	39·10 X 30	1195
Collectors Room	23·10 X 20	477
Head Assistants room	23·10 X 20	477
2d Assistants room	24·4 X 20	487
Deputy Collectors Room	20·0 X 17	340
Sheristadas	20·0 X 12·4	247

	Brought over	3223
Treasury	20 . 0 X 20 . 0	400
" Office	20 . 0 X 14 . 6	290
Head Clerk	20 . 0 X 16 . 4	327
General Clerks	64 . 4 X 30 . 6	1962
Shorthand Writers	20 . 0 X 14 . 10	287
	Total.	6489

The lower floor which is only 12 ft high will be devoted to the following Establishmts and to Records, Tiffin rooms, and Store rooms, the superficial Area being apportioned as follows;

Printing Establishment	64 . 2 X 29 . 6	1892
Head Printer	16 . 0 X 19 . 6	312
Records	99 . 6 X 21 . 6	2139
	81 . 6 X 20 . 0	1630
Record Keeper	23 . 6 X 19 . 6	458
Store Rooms	39 . 6 X 30 . 0	1185
Tiffin Rooms	53 . 0 X 19 . 6	1033

The upper part of the Turrets above the level of the floor contain two Rooms for Stationary racks 15 X 15 X 2 = 900

Total Area	9549
Add Area of lower floor	6489
Total Area of Sup. ft.	16.038

The building will be constructed of ordinary materials. Brickwork throughout with plain and solid stone dressings on the exterior. The Roof will be of Terrace supported by teakwood trusses beams and joists. The doors, Venetian throughout, with the addition of Glass on the exterior faces.

The total cost of the whole building at the rates at present obtaining in Bellary will be including the stone dressings Rs. 97. 982. 0. 0
Excluding the stone dressings Rs. 89. 782. 0. 0

I have the honor to be
Sir
Your most Obedt. servt.

Chisholm -
Consulting Architect
Madras

Public Works Department.

No 2926

Proceedings of the Madras Government.

Read the following.

To

From The Consg Architect to Govt } No. 1918/21 Nov 1872

The accompanying Revised Plan of a Collector's Cutcherry to be built at Bellary, submitted by the Consulting Architect in conformity with G.O. No 899 of 22nd May 1871 will be forwarded for record by the District Engineer

Rd 8th August 1873

P. Dr. 1873 Nov 21st

Bellary Collectorate

Cost Rs 23,782.

P.W. Circular No

Dated 31st October 1872

Estimate for Collectorate Cutcherry

Bellary

Copy

Col. C. H. Walker Rc

Secretary to Govt P.W.D.

Dated 31st November 1872

Received 22 —"—

Bundle: Five.

Forwards plans and Estimate for Bellary Cutcherry.

No 2926. 11 Nov 1873

No 223.

Cir: 80 Despr lith 1/2 sheets

Engineer of Bellary as to the adequacy of the rates allowed; and for preparation of survey of the site, and of plans and estimates for which-ever Subsidiary buildings the Collector may consider necessary.-

Submission to Collectory at Bellary.

Qmd

22
22

To
The District Engr
Bellary
Rev Dept
Four plans & estimates

Desp 13/12/72

of Bellary &c.

Ch. 5/12

Govt. of {1872} Madras.

PUBLIC WORKS.

To The District Engineer
Bellary

WP

Dated

Rec'd. Encl.

G. O. 11th Dec. 72, No 2926.

Nos. 223 & 224

Collectors Jahiberry at Bellary.

Revised Plan of Collectors Jahiberry forwarded with instructions to the District Engineer.

Passed