

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public works.

DEPARTMENT

G.O. No.	1626	Press
B.P. No.		Mis.
315316		
Dated	21-6	1843

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
21st June 1873.*

No. 315. Read the following Proceedings of the Madras Government in the Judicial Department, dated 16th April 1873, No. 583 :—

Read the following letter from the Inspector General of Jails, to the Chief Secretary to Government, Fort St. George, dated Madras, 27th March 1873, No. 50.

I HAVE the honour, at the request of the Acting Superintendent of the Central Jail at Salem, to forward for sanction a plan and estimate for improving the office and store-room accommodation, at a probable cost of Rupees 1,223, in lieu of that sanctioned in the order quoted in the margin, at a probable cost of Rupees 2,940.

2. The present proposal is to convert the tower into an office for the Superintendent, Jailer, and Clerks, by removing the staircase in the centre, by building up two of the four large apertures and furnishing the other two with doors, and by turning the four smaller apertures into windows. The present debtors' ward and the room at the inner gate, formerly used as an office, both of which will be available when the new buildings are completed, will suffice for store-rooms if fitted with racks or shelves, the cost of which has been included in the estimate.

THE proposed arrangements are approved in lieu of those formerly sanctioned.

(True Extract.)

(Signed) W. HUDLESTON,
Chief Secretary.

No. 316. ORDER THEREON, 21st June 1873, No. 1,626.

CIVIL WORKS, No. 21.

COMMUNICATED to the District Engineer of Salem.

2. It is noted that the total of sanctions for the Salem Jail, including those of G. O., No. 1,233, of 14th May 1872, and G. O., No. 974, of 19th July 1872, is reduced by this change of plan to Rupees 25,713, of which sum Rupees 20,940 were provided in the Budget of 1872-73, and Rupees 4,100 additional by the last mentioned Government Order. His Excellency the Governor in Council regrets that such ample provision of funds was only availed of in the past year to the extent of about Rupees 6,517, leaving an inconveniently large sum to be provided from the Reserve for incomplete works of the current year.

3. His Excellency the Governor in Council must utterly repudiate the sufficiency of the excuses for slow progress made in the District Engineer's Administration Report, viz., the very unfavourable nature of the season, the scarcity of both labour and materials, and the competition of the Municipality. If work at the head-quarters of the range and district is thus complacently allowed to languish in future, the District Engineer and Range Officer concerned will have to account more satisfactorily for the same than has been done for the past year.

(True Extract.)

(Signed) G. W. WALKER, Colonel, R.E.,
Secretary to Government.

To the District Engineer, Salem.

„ Officiating Controller of Public Works Accounts.

„ Financial Department.

„ Accountant General.

Exd. S. T. Austin.

Share Copies.

Proceedings of the Madras Government, Judicial Department,
16th April 1873.

No. 59. Read the following letter from the Inspector-General of Jails, to the Chief Secretary to Government, Fort St. George, dated Madras, 27th March 1873, No. 50:—

I have the honour, at the request of the Acting Superintendent of the Central Jail at Salem, to forward, for sanction, a plan and estimate for improving the office and store-room accommodation, at a probable cost of Rupees 1,223, in lieu of that sanctioned in the Order quoted in the margin, at a probable cost of Rupees 2,940.

2. The present proposal is to convert the tower into an office for the Superintendent, Jailer, and Clerks, by removing the staircase in the centre, by building up two of the four large apertures and furnishing the other two with doors, and by turning the four smaller apertures into windows. The present debtors' ward and the room at the inner gate, formerly used as an office, both of which will be available when the new buildings are completed, will suffice for store-rooms if fitted with racks or shelves, the cost of which has been included in the estimate.

No. 60. ORDER THEREON, 16th April 1873, No. 583.
The proposed arrangements are approved in lieu of those formerly sanctioned.
(True Extract.)


Chief Secretary.

To the Public Works Department, with plans and estimates.
.. Inspector-General of Jails.
.. Accountant-General.

2015

2016 Oct 21

2015

2015

NO. 100

JUDICIAL

Civil Building
Salem District Salem Range Salem Taluk

Abstract Estimate of 1873

Work - Estimate for improving the central Tower of the Salem Jail.

Amount of Estimate Rupees 740 -

Quantity	Description of Work	Per Rate	Amount	Total
8 2/3	Sq. of Brick work in chunam - bft	3 12 "	30 13 4	
11/12	" of Arch work in chunam - do	4 " "	3 10 8	
4	Sq. of Plastering with 2 coats of chunam - bft	2 8 "	10 "	
1/5	" of Removing terrace roof over stair case in Verandah - do	" 8 "	1 7	
22 1/2	bft of Teak wood - bft	3 12 "	84 6 "	
20	Running feet of Stair case with new side & tread planks and top frames utilizing the present rails and rise planks - bft	5 8 "	110 "	
6	Iron brackets to support side planks of the stair case near wall including cost of fixing -	2 " "	12 "	
144	Sq. fut of framed screen in Teak wood with door ways - bft	1 4 "	180 "	
2	1/3 Framed & 2/3 Venetian door 4x8 with painting complete - bft	50 " "	100 "	
	barrier forward		530 15 7	

Brought forward 530 15 7

4 Glazed windows with circular tops
3 1/2 x 7 including the cost of fixing and
painting 30 . . . 120 . . .

1 Removing the stair case from the
main Building do 5 . . . 5 . . .

1 Removing the wooden top and re-
fixing the same into the verandah
including the cost of covering the
openings in the roof with terrace
bricks do 20 . . . 20 . . .

9 Running feet of wooden steps
common Teak wood Rft 3 8 . . 31 8 . .
Total 707 7 7

Sundries & Superintendence 32 8 5

Total Estimate Rupees 740 . . .

Salem Range Office
22nd January 1873

Signed / G. J. Turner
Assistant Engineer
Salem Range

Received Per [Signature] Major R. C.
District Engineer
Salem

No 1626 Public Works Department

Proceedings of the Madras Government

Read the following

Pro. of the Madras Govt. } H.E. No 683 of 16th April 1873
Judicial Department

Communicated to
the District Engineer
of Salem.

It is noted that
the total of sanctions
for the Salem Jail, in-
cluding those of G.O.
No 1233 of 14th May 1872
and G.O. No 974 of 19th
July 1872 is reduced
by this change of Plan
to Rs 25,713, of which
sum Rs 20,940 were

Salem District

Salem Charge

Salem Jail

Abstract Estimate

21-6-73

48000 1626 44

1872/73

Estimate for improving
the Central Prison of the

Salem Jail

Rs 20,940/50

Amount of Estimate Rs 20,940

provided in the Budget
of 1870-71 and Rs 4,100
additional by the last
mentioned S. O.

His Excellency the Governor
in Council regrets
that such ample pro-
-vision of funds was
only availed of in the
past year to the extent
of about Rs 6517, -
leading an interveni-
-ently large sum to be
provided from the Re-
-serve for incomplete
works of the current year.

His Excellency the
Governor in Council
must utterly repudi-
-ate the sufficiency of the

excuses for slow progress
made in the District
Engineers Administration
Report, viz the very
unfavorable nature
of the season, the scar-
-city of both labour
and materials, and the
competition of the mu-
-nicipality. If work
at the Head Quarters
of the Range and Dis-
-trict is thus compla-
-cently allowed to
linguish in future
the District Engineer
and Range Officer
concerned will have
to account more satis-
-factorily for the same

there has been done for
the first year.

Q. M. W.

. 38

Ms. dated to all
Sp. Comm. 9/7/73
N: 215.16.
Cir 11th June

To
" Mr. Eng. Salem ✓
" Controller ✓
" Financial Dept ✓
" Account General ✓

112747³

Code of 1873 Madras.

PUBLIC WORKS.

to the District Collector
Salem

Date

Page

Encl. 4

21st June 1876.

No. 31573/6

Salem District Collector.

Respectfully ordered in No. 112747³
to the District Collector.
to plan and
execute the improvement
to the K. K. Canal
in the District.