

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

Public works DEPARTMENT

G.O. No.	2539	Press
B.P. No.		Mis.
269-270		
Dated	14-10-	1951873

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
17th October 1873.*

No. 269. Read the following letter from Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Chepauk, 20th September 1873, No. 1,154:—

I HAVE the honour to forward, for the sanction of Government, the under-mentioned estimates, accompanied by plans and specifications, for completing the Cutcheries and Sub-Jails in the Nellore District.

7 Abstract Estimates.
7 Block Plans.
1 Plan of Taluq Cutcherry at Gudur.
6 Specifications.

2. Improving Taluq Cutcherry and constructing Subsidiary Jail at Gudur, estimate Rupees 6,500 (Budget No. 30). The estimate is for converting a part of the present Taluq Cutcherry into a Sub-Jail, and constructing Tahsildar's Court-room and record-room with out-buildings. The loss from the sudden stoppage of the work is stated to be Rupees 121. No iron cage or treasure-chest is provided, as there is already a treasury-room. The amount required for expenditure this year is Rupees 3,000, which is the allotment in the Budget.

First-class Taluq Cutcherry at Kanigherry,	estimate Rupees	20,900, (No. 29.)
Do. do. at Atmakur,	do. „	23,340, („ 33.)
Do. do. at Rapur,	do. „	21,050, („ 34.)
Do. do. at Udiagiri,	do. „	20,620, („ 35.)

3. These are proposed to be built in accordance with the standard plan circulated with G. O., No. 232, of the 23rd April 1872. The out-offices in each case consist of cook-room, hospital-shed, ryots' shed, public and jail latrines with compound wall and well. The estimates provide for treasure vaults. The amounts that can be spent on these buildings in the current year are as follow:—

Kanigherry		Rupees 4,764
Atmakur		„ 3,962
Rapur		„ 3,000
Udiagiri		„ 3,000
Second-class Taluq Cutcherry at Vencatagberry,	estimate Rupees	10,100, (No. 31.)
Do. do. at Sulturpett	do. „	10,190, („ 32.)

4. These are to be built in accordance with the standard plan circulated with G. O., No. 779A, of the 15th March 1871.

There are to be the same out-offices as in the case of the first-class Cutcheries, with well and compound wall and strong iron cage for the treasure. The proposed expenditure this year on the Cutcheries is—

Vencatagberry		Rupees 3,500
Sulturpett		„ 3,000

5. The balances of the grants for Budget Items 31, 32, 34, and 35 are available for transfer to other districts, also Rupees 2,500 from the amount surrendered from Item 29 and 1,500 from Item 33. The District Engineer has recommended that Rupees 2,736 from Item 29 and Rupees 3,538 from Item 33 should be reserved for other works in the district, viz:—

For constructing a Corpse Gate for the Nellore Cemetery		Rs. 956
Do. a Sea Custom-house at Itmakala		„ 650
Do. a Dead-house at Nellore		„ 1,130
Do. a Sub-Collector's Cutcherry at Ongole		„ 3,538
		6,274

Proceedings of the Madras Government, Public Works Department,
17th October 1873.

6. In anticipation of the sanction of estimates, I have authorized the District Engineer to collect the necessary materials for the above named Taluq Cutcheries.

No. 270. ORDER THEREON, 17th October 1873, No. 2,539.

CIVIL WORKS, No. 17.

WITH this letter the Inspecting Engineer for Buildings submits estimates for the following works in the Nellore

District, the amounts of which, the reductions necessary on account of hospital sheds which are dispensed with under recent orders, and the balances required to complete are given in the following statement:—

Work.	Amount of Estimate.	Deduct for Hospital Sheds.	Balance of Estimate.	Expenditure up to 31st March 1873.	Difference to be provided.	Amount of grant for current year.	Amount proposed to be spent in 1873-74 in round numbers.	Excess of grant.
Improving Taluq Cutcherry and constructing Sub-Jail at Gudur	Rs. 6,500	Rs. 650	Rs. 5,850	Rs. 3,788	Rs. 2,062	Rs. 3,000	Rs. 2,062	Rs. 938
First-class Taluq Cutcherry at Kanigherry	20,900	640	20,260	8,680	11,580	10,000	4,800	5,200
Do. do. at Atmakur	23,340	640	22,700	10,108	12,592	9,000	4,000	5,000
Do. do. at Rapur	21,050	650	20,400	12,588	7,812	5,000	3,000	2,000
Do. do. at Udiagherry	20,620	650	19,970	10,627	9,343	9,000	3,000	6,000
Second-class do. at Venkatagherry Cotta	10,100	640	9,460	2,248	7,212	7,500	3,500	4,000
Do. do. at Sairupett	10,190	660	9,530	4,867	4,663	5,000	3,000	2,000
Total...	1,12,700	4,530	1,08,170	52,906	55,264	48,500	23,362	25,138

2. His Excellency the Governor in Council sanctions these estimates, and observes that of the total of the grants provided in excess of the amounts proposed to be spent in this year, viz., Rupees 25,138, Rupees 5,590 have, in G. O. of the 27th August 1873, No. 2,140, been diverted to other works, leaving Rupees 19,548 which will be held at the disposal of Government.* It is hoped however that the District Engineer will be able to make arrangements for the utilization of larger sums than he expects to spend on these buildings this year, and he may rely on the necessary funds being available later in the year.

* To the credit of the Reserve.

(True Extract.)

Colonel, R.E.,

Secretary to Government.

To the District Engineer, Nellore.

.. Inspecting Engineer for Buildings.
.. Officiating Controller of Public Works Accounts.
.. Accountant General.
.. Judicial Department.
Exd. S. T. Austin.
Spare Copies.

Specification to accompany the Plans and Estimates for the construction of Lathies in connection with the Taluq Cutcheries &c. in the Nellore District.

The buildings to be in accordance with the plan adopted by the Joint Municipal Commission and to consist of the number of seats marginally noted.

The foundations of the pillars in front and rear to be 2'-6" square and to be 2 feet in depth with basements one foot in height over them.

The foundations of the walls between the pillars to be 1'-3" broad and 9 inches deep, The basement over them to be 1 foot in breadth and one foot in height.

The foundations will, where specially mentioned, rest on beds of concrete 6 inches in thickness.

The rear pillars to be 8'-9" in height and 1½ feet square.

The front pillars to be 5 feet in height and 1½ feet square.

The walls between the pillars in rear to be 2'-6" in height, with a breadth of one foot

For the establishment of 1st Class Cutcheries 12 seats.
Do. do. do. 2nd Class and do. 8 seats.
Magistrate's Cutcheries & for jails attached to 1st Class Cutcheries
For jails of 2nd Class Cutcheries & for jails attached to 1st Class Cutcheries 6 seats.
Magistrate's Cutcheries

11
Specification to accompany the
Estimate for the Construction of 1st
class Salug Outchurns in the
Nellor District.

The buildings to be in accordance
with the Standard design approved
of by Government in their order No
252 of 23rd April 1872.

The foundations of the main
and partition walls to be 3' 6" in
depth and to be built according to the
sections and with the footings
shown in the drawing.

The foundations of these walls
will, where specially
mentioned rest on beds of Concrete
one foot in thickness. The Concrete
to project 6 inches all sides beyond
the first Course of Masonry.

Nellor District.

Construction of Outchurns

1154 of 20th Sept 1873

To the Secy

P. N. 579573.

Specification for

accompanying the Estimate

for Construction of Salug

and Connections with the

Salug Outchurns in the

Nellor District.

The basement of main walls to be $1\frac{1}{2}$ feet in height and $1\frac{1}{2}$ feet in thickness. The basement of the partition walls to be $1\frac{1}{2}$ feet in height and $1\frac{1}{2}$ feet in thickness.

The foundation of the ~~basement~~ to be $4-1\frac{1}{2}$ in depth and where specially mentioned it will rest on a bed of concrete 2 feet in thickness. The ~~basement~~ to be $1\frac{1}{2}$ feet in height and $1-10\frac{1}{2}$ in thickness.

The walls above of the rooms for the Sahasildar and his establishment and for the Post Office to be $1-6$ in breadth and $11-6$ in height.

The walls above of the rooms for the Shiraastadar and for the Cashier to be $1-9$ in thickness and 12 feet in height.

The walls above of the rooms for the Police to be $1-6$ in breadth and $11-6$ in height.

The main walls above of the wards for prisoners to be $1-6$ in breadth and $14-6$ in height. The partition walls of these wards to be $1-3$ in breadth and $14-6$ in height.

The walls of the second story to be $1-6$ in breadth and $11-6$ in height.

There will be 24 ~~each~~ wood doors $4-4 \times 8-3$ as shown on the Standard plan.

There will be eleven windows of the dimensions given in the Plan in the record room. They will be furnished with iron bars and with venetian shutters.

The record room will also have a Circular Ventilator 2-3 in diameter.

The Prison wards will have six doors and six iron grated ventilators.

The doors will be iron banded inside and battened outside according to the Standard design.

Flat arches, of the dimensions given in the Estimate, to be built over all doors and windows not surmounted by semicircular arches.

15
Cut stone to be used for the steps leading to the Sahaidar's room, to the prison wards and to the Porch.

The flooring to be of 8" square bricks in mortar with a levelling course of 3 inches of brick jelly.

The floors of the Prison wards to consist of broken bricks 3" in thickness, of 4 inches of Concrete, and of a coat of Asphalt $\frac{3}{4}$ " of an inch in thickness.

The roofing to consist of teak tie beams, teak struts, teak rafters, teak purlins, and teak rippers, with iron work according to the standard design. The framework of the roof to be covered with the best flat tiles and a course of best pantiles and to be

finished off with Chumam boards.

The scantlings of the timber to be of the dimensions given on the Standard design for 1st Class Cutcheries.

The flooring of the record room to consist of 1 inch teak planks, of 3 inches of concrete, and of 3 coats of plaster.

The interior of the building to be plastered with one coat of Chumam. The exterior to be painted.

All exposed portions of wood work to be painted with 3 coats of Carron's oak color.

17
The masonry with the exceptions noted to be of brick in Chumam.

The materials and workmanship to be of the best description procurable.

The undermentioned Cutcheries will have concrete in the foundations.

First Class Salug Cutchery at Rapur
— do — do — at Amakur.
— do — do — at Kanigir.

D. Engr's Office
Mellor
31st July 1873.

Smith
District Engineer
Mellor

Edmond Colonel R.E.
Insp^g Engineers for
Civil & Mil^y Buildings.

19
Specification to a company the
Estimate for construction of a shed for Pylots
in connection with the Salug Cutcheries &c
in the Kallore District

This building will consist of one
room 40'-0" x 20'-0".

The roof will be supported by 12
country wood posts as shown in the stand-
-ard design.

The floor will be enclosed by a re-
-taining wall 2½ feet in depth inclusive of
foundation. It will be 1'-7" in breadth, for
a height of 1½ feet, and 1'-2" in breadth for
a height of 1 foot.

The flooring to be of 8" square bricks
in mortar, with a levelling course of
broken bricks, 3 inches in thickness.

The roofing to be of palmirah couple
and rapers and to be covered with best fl
tiles and a course of best pan tiles. It will
be finished off with chunam borders. The
wood work of the roof to be tarred.

The brusses to be of teak wood
of the annexed scantling - 5" x 7"

The masonry to be of brick in
chunam

Kallora District

Encl: in a letter No 1154
dated 20 Sept 1933

P.M. 5795/73.

Specification to
accompany Estimate
for construction of
1st class Salug
Cutcheries in the
Kallora District

Chumam.

The materials, ^{workmanship} to be of the best description procurable.

The undermentioned sheds for Ryoto will have concrete in the foundations.

Ryoto shed at Angole

— D^o — at Podela

— D^o — at Alluv.

— D^o — at Addasky.

— D^o — at Handakum.

— D^o — at Soolorpet.

District Engineer

Mellore

Signed R. Smith

31st July 1873

District Engineer

Mellore.

"True Copy"

Attd. Colonel R. E.

Inspecting Engineer for
Civil & Military Buildings

23
Specification to accompany the
Estimates for the Construction of 2nd
Class Salug. Butcherries in the
Mellore District.

The buildings to be in
accordance with the Standard design.

The foundations of the main and
partition walls to be 3'-1½' in depth
and to be built according to the
sections and with the footing
shown in the drawing.

The foundations of these will,
where specially mentioned, be
rest on beds of concrete one foot
in thickness. The concrete to project
6 inches on all sides beyond the first
course of masonry.

Mellore District

Enclosure in a letter
of 11/5/89 of 20/5/89

To the Secretary

P. M. 57957/3.

Specification for

accompanying the Estimates

for construction of sheds

for Salug. in connection

with the Salug. Butcherries
in the Mellore District.

The basement of main walls to be
1½ feet in height and 1½ feet in thickness.

The basement of the partition walls
to be 1½ feet in height and 1½ feet in thickness.

The main walls above of the rooms for
the Deputy Sahasildar and his establishment
to be 1½ feet in breadth and 12 feet
in height.

The partition walls of these rooms
to be 1-3" in breadth and 13-11"
in height.

The walls above of the room
for the Police to be 1½ feet in breadth
and 12 feet in height.

The main walls above of the
Wards for Prisoners to be 1-6"
in thickness and 13-9" in height.

The partition walls of these wards²⁵
to be 1-3" in breadth and 14-3" in
height.

There will be 11 teak wood doors
4-4" x 8-3" as shown on the Standard
Plan.

The prison wards will have 6
doors and 6 iron grated Ventilators.

The doors will be iron barred inside
and battens outside according to the
Standard design.

Flat arches of the dimensions given
in the Estimate to be built over all
doors and windows.

Set Stone to be used for the steps
leading to the Deputy Sahasildar's
room and to the Prison Wards.

The flooring to be of 8" square bricks
in mortar with a levelling Course of
3 inches of brick jelly.

The floors of the Prison wards to consist of broken bricks 3 inches in thickness, of 4 inches of Concrete, and of a coat of asphalt $\frac{3}{4}$ inch in thickness.

The roof to consist of teak tie beams, teak struts, teak rafters and teak purlins with iron work according to the standard design.

The framework of the roof to be covered with the best flat tiles and a course of best pan tiles and to be finished off with Chumam boards.

The scantlings of the timber to be of the dimensions given on the Standard Design.

The interior of the building to be plastered with one coat of Chumam. The exterior to be pointed.

27
All exposed portions of woodwork to be painted with 3 coats of Carrow Oat Color.

The masonry with the exception noted to be of brick in Chumam.

The materials and workmanship to be of the best description procurable.

The undermentioned Catchery will have Concrete in the foundations.

Second class Salug Catchery at
Loo-loo-pett.

St. Eng's Office
Kellow
31st July 1873

Smith
District Engineer
Kellow.

Edmd Colonel R.C.
Inspecting Engineer for
Civil & Mil^y Buildings.

William Dietrich

Enclosed you will find a letter from
dated 17th Sept 1893

P.M. 18/9/93

Appreciation to

Accountants the

Commissioners for Construction

of the New State of

Washington in the

Western District

To Mr. W.

Mr. W. Dietrich

Mr. W. Dietrich

Wm. Dietrich

Specification to accompany the estimates for the construction of book rooms in connection with the Taluk Butecherries ~~Rs~~ in the Nellore District.

The building to consist of one room with walls on three sides.

The foundation is to be 2 feet broad and 1-6 in depth. The retaining wall to be 1-7 broad and 1-6 high.

A basement of 1 ft to be raised with breadth of 1-7 and 1-2 respectively over foundations of main and retaining walls.

The foundations will, where specially mentioned, rest on beds of concrete 6 inches in thickness.

The rear wall above to be 6-9 in height.

The end walls including gables to be 11-6 in height to apex. They will be 1-2 in breadth.

The roof to consist of teak ridge pieces, palmirak rafters, reapers ~~Rs~~ and to be covered with best flat tiles and a course of best pan tiles and to be finished off with

Chunam

Nellore District

Envelope in a letter

15th of 20 Sept 18,

7668491

P.M. 579573.

Specification to
accompany the Estimate
for construction of
book rooms in connection
with the Taluk Butecherries
in the Nellore District

Chunam borders. The wood work of the roof to be tarred.

The flooring to be of 8" square bricks in mortar with a levelling course of 3 inches of brick.

The whole of the walls to be plastered with one coat of Chunam and whitewashed.

The masonry to be of brick in mortar.

The materials and workmanship to be of the best description procurable.

The undermentioned cookrooms will have concrete in the foundations.

Cook room at Ongole

Do at Podilac

Do at Allur

Do at Addanky

Do at Kandukur

Do at Sooloorpet

Distt Engrs Office
Nellore, 31st July 1873

Signed J.R. Smith
District Engineer, Nellore.

"True Copy"

EA and Colonel R.E.
Inspecting Eng^r for
Civil & Mil^y Buildings

Contd Paul

N^o 1154

Office of the Inspecting Eng^r
for Civil & Military Buildings
Chepauk 20 September 1873.

From,

Colonel E.A. Ford R.E.

Inspecting Engineer for Civil &
Military Buildings

To,

Colonel G.W. Walker R.E.

Secretary to Government, P.M.D.

Sir,

Enclosures 21.

1 Abstract
estimates

2 Block Plans

3 Plan of Talag

Cutcherry at

Godur

4 Specifications

5 Plans and specifications for completing

the Cutcheries and sub fails in the

Nellore District.

2. Improving Talag Cutcherry and

constructing subsidiary fail at Godur

Estimate Rupees 6500 (Budget N^o 30).

The estimate is for converting a part

of the present Talag Cutcherry into

a sub jail and constructing Tahsildar's
Court room and record room with out
buildings. The loss from the sudden
stoppage of the work is stated to be
Rs. 121. No iron cage or treasure chest
is provided as there is already a treasury
room. The amount required for expenditure
this year is Rs. 3000 which is the allot-
ment in the budget.

First Class Taluq Cutcherry at Hanigherry

Estimate Rs. 20900 (N^o 29)

_____ D^r _____ at Atmakur D^r 23340 (N^o 33) ✓

_____ D^r _____ at Rapur D^r 21050 (N^o 34) ✓

_____ D^r _____ at Udiagiri D^r 20620 (N^o 35) ✓

3. These are proposed to be built in
accordance with the standard plan cir-
-culated with G. O. N^o 232 of the 23rd April
1872. The out offices in each case consist
of Cook room, hospital shed, ryots shed,
public and jail latrines with compound
wall

25
wall and well. The estimates provide
for treasure vaults. The amounts that
can be spent on these buildings in
the current year are as follows

... Hanigherry _____ Rs. 4764

... Atmakur _____ 3962

... Rapur _____ 3000

... Udiagiri _____ 3000

Second Class Taluq Cutcherry at

Tencatagherry Estimate Rs. 10100 (N^o 31)

_____ D^r _____ Sulurpet _____ D^r _____ 10190 (N^o 32)

4. These are to be built in accordance
with the standard plan circulated
with G. O. N^o 779A of the 15th March 1871.

There are to be the same out offices as
in the case of the first Class Cutcheries
with well and compound wall and
strong iron cage for the treasure. The
proposed expenditure this year on the Cutcheries
is

Tencatagherry _____ Rs. 3500

Sulurpet _____ 3000

The

5. The balances of the grants for budget items 31, 32, 34 and 35 are available for transfer to other districts, also Rs 2500 from the amount surrendered from item 29 and 1500 from item 33.

The District Engineer has recommended that Rs. 2736 from item 29 and Rs. 3538 from item 33 should be reserved for other works in the district viz.

For constructing a corpse gate for

the Nellore cemetery — Rs. 956

— D^r Sea Customs House at

Itanakala — Rs. 650

— D^r Dead house at Nellore — Rs. 1130

— D^r Sub Collector's Quarters

at Ongole — Rs. 3538

Rs. 6274

6. In anticipation of the sanction of estimates, I have authorized the District Engineer to collect the necessary materials for the above named Taluk

Quarters

Quarters.

I have the honor to be,

Sir

Your Most Obedient Servant

Ed Ford Colonel R.E.

Inspecting Engineer for Civil & Military Buildings

5. The balances of the grants for

to be left as follows

to be left

to be left as follows

Plans & estimates for
completing certain
Taluk Panchayat
buildings in the
District.

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

to be left as follows

Specification to accompany the Estimates for the construction of Hospital sheds in connection with the Taluk Panchayat &c. in the Nellore District.

The foundation to be sunk 2 feet below the general surface of the ground, the breadth being 2 feet. The retaining wall to be 1 foot in depth and 1-2 in breadth.

The basement to be 1 foot in height and 1-7 in breadth, over main & partition walls. Over the retaining walls the basement will be 6 inches in height and 9 inches in breadth.

The foundations will, where specially mentioned, rest on beds of concrete 6 inches in thickness.

The walls above are to be 7 feet in height and 1-2 in breadth, the gables to be of the same thickness.

The flooring to be of 8 inches square bricks in mortar, with a levelling course of 3" of brick.

The roof to consist of teak tie beams, teak ridge pieces, teak furlins, teak rafters, teak ropers &c. and to be covered with thatch.

best flat tiles and a course of best pan
tiles. It will be finished off with chunam
borders.

The walls to be plastered in the
inside and on the outside with one coat of
chunam and then white washed.

The masonry to be of brick in chunam.
The materials and workmanship to be of
the best description procurable.

The undermentioned Hospital
Sheds will have concrete in the foundations.

Hospital shed at Ongole

— Do — at Podela

— Do — at Alluru

— Do — at Addankur

— Do — at Kandakur

— Do — at Sooloorpet.

District Engineer's Office

Nellore

31st July 1873

Signed J R Smith

District Engineer

Nellore.

"True Copy"

Edw. Col. R. E.
Inspecting Engineer for
Civil & Mil. Buildings.

Am. P. 26

No 2539 Md
 Read the Madras Govt
 From the Inspecting Engineer for
 Buildings H. S. No. 1154 of 20 Sept 1873

With this letter the
 Inspecting Engineer for
 Buildings submits estimates
 for the following works
 in the Madras District
 the amounts of which the
 reductions necessary on
 account of Hospital sheds
 which are dispensed with
 under recent orders and the
 balances required to com-
 plete are given in the
 following statement.

J. S. S.
 Inspecting Engineer for
 Buildings

—Madras District—

Enclosed in a letter No
 1154 of 20 Sept 1873

To the Secy

P. N. 579573.

Inspected for

accompanying the estimate

for construction of

Hospital sheds in

connection with the

large buildings in the

—Madras District—

Work.	Amount Estimate	Deduct for Repairs	Balance Estimate	Expenditure in 1872	Difference	Amount provided	Amount of grant for current year	Amount for future years in 1872	Excess of grant
Improving Salubriety and constructing	6,500	650	5,850	5,788	2062	3000	3062	938	
Salubriety at Goodar									
Salubriety at									
Do at Hapurgherry	20,900	640	20,260	8680	11,580	10,000	4,800	5,200	
Do at Sitapur	23,340	640	22,700	10,712	12,988	5,000	4,000	1,000	
Do at Raptur	21,050	650	20,400	13,888	7,512	5,000	3,000	2,000	
Do at Hodiagherry	20,620	650	19,970	10,627	9,343	7,000	3,000	4,000	
Do at Taitkata									
gherry Cottas	10,100	640	9,460	2248	7,212	7,500	3,500	4,000	
2nd class do at Sitapur	10,190	660	9,530	4867	4,663	5,000	3,000	2,000	
	112,700	4,650	108,050	57,905	50,145	45,000	22,262	22,738	

His Excellency the Governor in Council sanctions these estimates and observes that of the total of the grants provided in excess of the amounts proposed ~~he~~ spent in this year, vizt Rs 25,138 Rs 5,590 have, in L.O. of the 7 August 1873 Rs 21,548 been devoted to other works leaving Rs 3,542 which will be held at the disposal of Govt. to the credit of the Revenue. It is hoped however that the District Engineer will be

able to make arrangements for the utilization of larger sums than he expects to spend on these buildings this year, and he may rely on the necessary funds being available later in the year.

G.M.

Dr. R. S. K. M. S.
Dr. R. S. K. M. S.
C. S. K. M. S.
J. S. K. M. S.

S. C. S. K. M. S. 27/10/72

Ch 5795

Govt. of 1873 Madras.

PUBLIC WORKS.

The District Engineer
Vellore.

Dated

Recd.

Encl. 1/4

G. O. 17th Dec 1873, No 2539.

Nos. 2691 & 270

By [unclear] and
Sub Jails in the Vellore
Passing orders on
letter from the District
Engineer submitting
plans & estimates for con-
structing certain [unclear]
Sub Jails.

1
J. V. V. V.
9/10/73

Before this order
goes for the signature
of the District Engineer
will be submitted to the
District Engineer
for his signature
and then to the
District Engineer